STATE OF LOUISIANA
COASTAL PROTECTION AND RESTORATION AUTHORITY

WEST GRAND TERRE
2022 VEGETATIVE PLANTING
PROJECT NO. BA-0197
JEFFERSON PARISH

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1.	TITLE SHEET
2.	GENERAL NOTES & QUANTITIES
3.	PROJECT LAYOUT
4.	VEGATATIVE PLANTING DETAILS
5.	SAND FENCING DETAILS

LICENSURE CLASSIFICATION REQUIREMENTS

MAJOR CATEGORY: HEAVY CONSTRUCTION

SUBCLASSIFICATION: LANDSCAPING, GRADING & BEAUTIFICATION

OR

MAJOR CATEGORY: SPECIALITY

SUBCLASSIFICATION: COASTAL RESTORATION & HABITAT ENHANCEMENT OR SEEDING, SODDING, LOAD & SOIL STABILIZATION, EROSION CONTROL, SHEET PILING

REV.	DATE	DESCRIPTION	BY

COASTAL PROTECTION AND RESTORATION AUTHORITY
150 TERRACE AVENUE
BATON ROUGE, LOUISIANA 70802

TITLE SHEET

2022 VEGETATIVE PLANTING

DESIGNED BY: BAC
STATE PROJECT NUMBER: BA-0197
APPROVED BY: B.B.,P.E.
DRAWN BY: BAC

DATE: 07/01/2022

SHEET 1 OF 5

GENERAL NOTES

1. PLANS AND SPECIFICATIONS ARE COMPLEMENTARY; WHAT IS REQUIRED BY ONE IS BINDING AS IF REQUIRED BY ALL. CLARIFICATIONS AND INTERPRETATIONS OF, OR NOTIFICATIONS OF MINOR VARIATIONS AND DEVIATIONS IN THE CONTRACT DOCUMENTS, WILL BE ISSUED BY THE ENGINEER, IF NECESSARY.
2. BACKGROUND AERIAL IMAGES SHOWN ON THE PLANS ARE FOR REFERENCE ONLY.
3. EXACT LOCATION OF ALL PLANTS SHALL BE DETERMINED ON SITE BY THE ENGINEER DURING PRE- CONSTRUCTION LAYOUT.
4. ALL DISTANCE MEASUREMENTS SHOWN ON THE PLANS ARE APPROXIMATE.
5. NO EQUIPMENT MAY ALTER OR DISTURB THE EXISTING CONDITIONS OF NEWLY CONSTRUCTED DUNE OR ANY EXISTING VEGETATION.

SUMMARY OF ESTIMATED QUANTITIES

BASE BID

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY
1	BITTER PANICUM - 4 INCH CONTAINERS (TS-1002)	EACH	45,500
2	SEA OATS - GALLON CONTAINERS (TS-1010)	EACH	5,400
3	SAND FENCING (TS-930)	FEET	5,000

QUANTITIES SHOWN ARE FOR BID PURPOSES ONLY. THE OWNER RESERVES THE RIGHT TO ADJUST QUANTITIES HIGHER OR LOWER WITHOUT ADJUSTMENT OF THE UNIT PRICE.

REV.	DATE	DESCRIPTION	BY

DESIGNED BY CPRA - TRO

COASTAL PROTECTION AND RESTORATION AUTHORITY
150 TERRACE AVENUE
BATON ROUGE, LOUISIANA 70802

GENERAL NOTES & QUANTITIES

DESIGNED BY: BAC

APPROVED BY: B.B.,P.E.

2022 VEGETATIVE PLANTING

STATE PROJECT NUMBER: BA-0197

DRAWN BY: BAC

DATE: 07/01/2022

NOTES:

1. SAND FENCE CORRIDOR IS APPROXIMATELY 13,500 LF TOTAL.
2. ALL PLANTS TO BE INSTALLED ALONG SAND FENCING AS SHOWN ON THE DETAILS.
3. FIRST ROW OF PLANTS ALONG SAND FENCING TO BE SEA OATS AND BITTER PANICUM ALTERNATING. SEE SHEET 4 FOR DETAILS.
4. 9 ADDITIONAL ROWS OF BITTER PANICUM TO BE PLANTED AT 5 FEET SPACING FOR FIRST 8500 FEET OF SAND FENCING. (FROM WEST TO EAST)
5. 6 ADDITIONAL ROWS OF BITTER PANUCUM TO BE PLANTED AT 5 FEET SPACING FOR REMAINER 5,000 OF SAND FENCING. (SECTION FURTHEST EAST)

TYPICAL SECTION
NOT TO SCALE

REV.	DATE	DESCRIPTION	BY

DESIGNED BY CPRA - TRO

COASTAL PROTECTION AND RESTORATION AUTHORITY
150 TERRACE AVENUE
BATON ROUGE, LOUISIANA 70802

PROJECT LAYOUT

DESIGNED BY: BAC
APPROVED BY: B.B.,P.E.

2022 VEGETATIVE PLANTING

STATE PROJECT NUMBER: BA-0197
DRAWN BY: BAC

DATE: 07/01/2022

SHEET 3 OF 5

1 DETAIL - BITTER PANICUM - 4" CONTAINER

SCALE $\frac{1}{4}$" = 1'

2 DETAIL - SEA OATS - GALLON CONTAINER

SCALE NOT TO SCALE

3 DETAIL - VEGETATION PLANTING LAYOUT

SCALE NOT TO SCALE

4 DETAIL - NOT USED

SCALE NOT TO SCALE

REV.	DATE	DESCRIPTION	BY

DESIGNED BY
CPRA - TRO

COASTAL PROTECTION
AND RESTORATION
AUTHORITY
150 TERRACE AVENUE
BATON ROUGE, LOUISIANA 70802

VEGETATIVE PLANTING
DETAILS

DESIGNED BY: BAC

APPROVED BY: B.B.,P.E.

2022
VEGETATIVE
PLANTING

STATE PROJECT NUMBER: BA-0197

DRAWN BY: BAC

DATE: 07/01/2022

SHEET 4 OF 5

1 DETAIL - SAND FENCING DESIGN, TYPICAL

SCALE $\frac{1}{4}$" = 1'

2 DETAIL - FENCING SECTION, TYPICAL

SCALE NOT TO SCALE

3 DETAIL - FENCING GAPPING DIMENSIONS

SCALE NOT TO SCALE

REV.	DATE	DESCRIPTION	BY

DESIGNED BY
CPRA - TRO

COASTAL PROTECTION
AND RESTORATION
AUTHORITY
150 TERRACE AVENUE
BATON ROUGE, LOUISIANA 70802

SAND FENCING DETAILS

DESIGNED BY: BAC

APPROVED BY: B.B.,P.E.

2022
VEGETATIVE
PLANTING

STATE PROJECT NUMBER: BA-0197

DRAWN BY: BAC

DATE: 07/01/2022

SHEET 5 OF 5