


INDEX TO SHEETS

SOUTH SHORE OF THE PEN
MAINTENANCE
PROJECT NO. BA-0041
JEFFERSON PARISH



DATE: DECEMBER 2021

SHEET 1 OF 5

LICENSURE CLASSIFICATION REQUIREMENTS
MAJOR CLASSIFICATION: HEAVY CONSTRUCTION
SUB CLASSIFICATION: COASTAL RESTORATION
AND HABITAT ENHANCEMENT

GENERAL NOTES

1. THIS PROJECT CONSISTS OF THE REMOVAL OF EXISTING TIMBER MATS WHICH WERE USED FOR CONTAINMENT OF MARSH FILL DURING CONSTRUCTION OF THE BA-0041 PROJECT.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IDENTIFYING SAFE ACCESS TO THE PROJECT AND FOR NAVIGATING WITHIN THE LIMITS OF THE PROJECT AREA. ALL EQUIPMENT SHALL BE FLOATING AT ALL TIMES DURING TRANSIT TO AND FROM THE PROJECT SITE. THE CPRA CONSTRUCTION ENGINEER OR THEIR REPRESENTATIVE SHALL MONITOR THE LOCATION OF EQUIPMENT DURING CONSTRUCTION.
3. SEE SHEETS 3 AND 4 FOR ACCESS DETAILS OVER THE EXISTING FORESHORE ROCK DIKE.
4. ANY DAMAGES TO EXISTING COAST GUARD NAVIGATION AIDS OR PRIVATE NAVIGATION AIDS SHALL BE REPAIRED BY THE CONTRACTOR TO U.S. COAST GUARD STANDARDS AT THE EXPENSE OF THE CONTRACTOR.
5. THE CONTRACTOR SHALL NOT, AT ANYTIME, TRAVERSE EXISTING MARSH OR VEGETATIVE WETLANDS AREAS UNLESS OTHERWISE DIRECTED BY THE CPRA CONSTRUCTION ENGINEER.
6. BACKGROUND AERIAL IMAGES SHOWN ON PLANS ARE FROM ARCGIS 10.5.1 - APRIL 2020.
7. ALL ELEVATIONS ARE GIVEN IN THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) U.S. SURVEY FEET (FEET). ALL HORIZONTAL COORDINATES ARE GIVEN IN THE NORTH AMERICAN DATUM OF 1983 (NAD83, LOUISIANA STATE PLANE SOUTH ZONE U.S. FEET).
8. DATA FROM CPRA GAGE BA03C-CR-61 IN BAYOU DUPONT WAS USED TO CALCULATE THE MEAN HIGH WATER AND MEAN LOW WATER. ELEVATIONS ARE REFERENCED TO NAVD 88 GEOID 12A, U.S. FEET. MHW = +1.16' AND MLW = -0.19'.
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING ALL LANDOWNERS, UTILITIES AND PIPELINE COMPANIES IDENTIFIED IN THE SPECIFICATIONS AT LEAST 5 WORKING DAYS PRIOR TO MOBILIZATION. ALL UNDERGROUND PIPELINES AND UTILITIES WITHIN 500 FT. OF THE EXISTING TIMBER MATS SHALL BE MARKED WITH BUOYS BY THE CONTRACTOR. THE CONTRACTOR SHALL MAINTAIN BUOYS DURING THE MAT REMOVAL OPERATIONS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN THE CLEARANCES FROM THE PIPELINES SET FORTH IN THE PLAN DRAWINGS OR IN THE BID DOCUMENTS. PIPELINE LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATIONS. THE OWNER IS NOT LIABLE FOR EXACT LOCATIONS. THE CONTRACTOR MUST CALL LOUISIANA ONE CALL AT 1-800-272-3020 AT LEAST 5 WORKING DAYS PRIOR TO MOBILIZATION.
10. ORIGINAL CONSTRUCTION DETAILS OF THE WOODEN MATS ARE SHOWN ON SHEET 5. THIS IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY, AS EXISTING MATS HAVE DETERIORATED SUBSTANTIALLY SINCE ORIGINALLY CONSTRUCTED.

SUMMARY OF ESTIMATED QUANTITIES

| ITEM NO. | DESCRIPTION | UNIT | ESTIMATED QUANTITY |
|----------|---------------------------------|----------|--------------------|
| 1 | MOBILIZATION AND DEMOBILIZATION | LUMP SUM | 1 |
| 2 | REMOVAL OF EXISTING TIMBER MATS | LUMP SUM | 1 |

| | | | | | | | | | |
|--|--|-----------------|--|--|------|-------------|----|--|--|
| DATE: DECEMBER 2021 | | | | | | | | | |
| SOUTH SHORE OF THE PEN MAINTENANCE | | GENERAL NOTES | | COASTAL PROTECTION AND RESTORATION AUTHORITY 150 TERRACE AVENUE BATON ROUGE, LOUISIANA 70802 | | | | | |
| STATE PROJECT NUMBER: BA-0041 | | DESIGNED BY: MA | | | | | | | |
| DRAWN BY: DRW | | APPROVED BY: BR | | | | | | | |
| | | | | REV. | DATE | DESCRIPTION | BY | | |

