



committed to our coast

Suggested Citation: Coastal Protection and Restoration Authority of Louisiana. 2023. Louisiana's Comprehensive Master Plan for a Sustainable Coast. Coastal Protection and Restoration Authority of Louisiana. Baton Rouge, LA.

This public document is published at a total cost of \$32,225.09. Two thousand (2,000) copies of this public document were published in this first printing at a cost of \$32,225.09. The total cost of all printings of this document including reprints is \$32,225.09. This document was published by OTS-Production Support Services, 627 North 4th Street, Baton Rouge, LA 70802 for the Coastal Protection and Restoration Authority, to promulgate the comprehensive master plan, to report to the Louisiana Legislature, and inform Louisiana Citizens under authority of R.S. 49:214.5.3. This material was printed in accordance with standards for printing by State Agencies established in R.S. 43:31. Printing of this material was purchased in accordance with the provisions of Title 43 of the Louisiana Revised Statutes.



2023

Louisiana's Comprehensive **Master Plan** for a Sustainable Coast

4TH EDITION

CPRA BOARD MEMBERS

Kyle R. "Chip" Kline, Jr.

CPRA Chairman

Thomas Harris

Secretary, Louisiana Department of Natural Resources Keith Lovell, Designee

Dr. Shawn Wilson

Secretary, Louisiana Department of Transportation and Development Chris Knotts, Designee

Jack Montoucet

Secretary, Louisiana Department of Wildlife and Fisheries Patrick Banks, Designee

Dr. Chuck Brown

Secretary, Louisiana Department of Environmental Quality

Don Pierson

Secretary, Louisiana Department of Economic Development Patrick Witty, Designee

Dr. Mike Strain

Commissioner, Louisiana Department of Agriculture and Forestry Joey Breaux, Designee

John "Jay" Dardenne

Commissioner, Louisiana Division of Administration Barbara Goodson, Designee

Billy Nungesser

Lt. Governor Michael Ince, Designee **Casey Tingle**

Director, Governor's Office of Homeland Security and Emergency Preparedness

James "Jim" Donelon, III

Commissioner, Louisiana Department of Insurance Billy Broussard, Designee

Scott Burke

Representative of Barataria Basin

Dwayne Bourgeois

Representative of Terrebonne Basin

Guy McInnis

Representative of Breton Sound Basin

Bill Bubrig

Representative of Mississippi Delta Basin

Monica Gorman

Representative of Pontchartrain Basin

William "Bill" Hidalgo

Representative of Atchafalaya Basin

Laurie Cormier

Representative of Calcasieu/Sabine Basin

Senator Bob Hensgens

Designee of Senate President

Representative Jerome Zeringue

Designee of Speaker of the House

Stephen Sagrera

Representative of Teche/Vermilion Basin

APRIL 2023

Dear Members of the Louisiana Legislature,

I am proud to submit for your consideration and approval, Louisiana's fourth comprehensive Coastal Master Plan. This plan represents both the evolution of a process that began eighteen years ago in the aftermath of Hurricanes Katrina and Rita, and something that, thanks to its ability to incorporate new data and new analyses, is entirely remarkable and new.

In 2005, the danger a degrading coast posed for our communities was all too real, yet our ability to respond to the enormity of the challenge was very much an aspiration. Today, we can celebrate the fact that the projects in this 2023 Coastal Master Plan are explicitly designed to build on the successes we have realized in the intervening years. Successes that include 358 miles of levee improvement, 60 miles of barrier island and headland restoration, the benefits of projects covering 82 square miles of our coastal habitats—a level of progress that would have been almost unthinkable when the coastal program first began.

Of course, not all of the changes along our coast have been positive. Persistent natural processes and the accumulating impacts of human actions are still working against us; the oiling that once spread across at least 450 miles of our shore took its toll; and too many of our communities are trying to rebuild after a new generation of destructive milestones brought by Hurricanes Laura, Delta, and Ida.

Despite these changes and challenges, Louisiana's approach to the land loss crisis remains constant. The Coastal Master Plan is still built on the most scientific and up-to-date understanding of the problem and a wide-open call for solutions. We continue to evaluate

and select future projects based on rigorous modeling, and we call on leading experts from different disciplines, stakeholder groups, and the public to guide and inform our decision-making.

This "lead with the science" approach paired with our aggressive implementation record has been the key to our success. While it brings hard truths and startling maps, it also opens the door for honest discussions about what can be done, leads us to construct only the most effective projects, and spawns new efforts to build resilience that reach beyond the Coastal Protection and Restoration Authority and the coast. While the coast of the future may not be the coast of today, this 2023 Coastal Master Plan contains 77 projects that can preserve, protect, and restore the vibrancy and the characteristics of the coast we call home and depend on. It also proudly continues a legacy of nonpartisan commitment to one of the most important issues we face, a legacy that the John Bel Edwards administration inherited from Governors Foster, Blanco, and Jindal, and one we must demand carries on through future governors.


Sincerely,

Affline

Kyle R. "Chip" Kline, Jr.

Governor's Executive Assistant for Coastal Activities Chairman of the Coastal Protection and Restoration Authority Board

CONTENTS



| This chapter presents the 202 Master Plan and describes the the suite of projects with regardland loss and limiting storm sufflood risk and associated dam |
|--|
| 6. REGIONAL APPROA This chapter contains informat five regions across the coast, to Coastal Master Plan projects of for those regions, and vignette analysis beyond project select Chenier Plain |
| Central Coast Terrebonne Barataria |
| Pontchartrain / Breton7. BEYOND THE MASTITUTE This chapter contains information |
| topics, initiatives, and program the 2023 Coastal Master Plan relevant to the future of Louisi ACKNOWLEDGMENT |
| |

| 5. | TAKE ACTION |
|------------|---|
| | This chapter presents the 2023 Coastal |
| | Master Plan and describes the benefits of |
| | the suite of projects with regard to reducing |
| | land loss and limiting storm surge-based |
| | flood risk and associated damages. |
| | |
| | |
| | |
| 6. | REGIONAL APPROACH 95 |
| | This chapter contains information about |
| | five regions across the coast, the 2023 |
| | Coastal Master Plan projects selected |
| | for those regions, and vignettes from |
| | analysis beyond project selection. |
| | |
| | Chenier Plain 98 |
| | |
| | Central Coast110 |
| | |
| | Terrebonne 122 |
| | |
| | Barataria |
| | |
| | Pontchartrain / Breton 146 |
| | |
| | |
| 7 . | BEYOND THE MASTER PLAN159 |
| | This chapter contains information about |
| | topics, initiatives, and programs beyond |
| | the 2023 Coastal Master Plan that are |
| | relevant to the future of Louisiana's coast. |
| | |
| | |
| | ACKNOWLEDGMENTS 180 |
| | |



COMMITTED TO OUR COAST

PURPOSE AND OPPORTUNITY

Fifty years from now, Louisiana's coast will look very different. The state continues its commitment to implement restoration and risk reduction projects that will result in a vibrant and more sustainable coast for residents and visitors to enjoy. We recognize the challenges of natural and human-made change to the coastal environment and are proactively working to address them through this updated master plan. The implementation of large-scale projects represents a commitment to the people of Louisiana, to our cultural heritage, and to maintaining a viable working coast.

When thinking about the future, people in coastal Louisiana have many questions. What might the future coast look like? How will hurricanes impact coastal communities in the future? Will future generations get a chance to enjoy the communities, landscapes, and natural resources of our coast? Through a rigorous evaluation effort, the 2023 Coastal Master Plan provides insight into these questions. The master plan presents projections of the future coastal landscape and how factors like climate change and subsidence may impact where and how coastal communities can thrive. But it does not stop there - master plan analyses provide a vision for a better, more productive future for our coast by proposing a robust suite of restoration and risk reduction projects to benefit every region.

The 2023 Coastal Master Plan and appendices provide information about land loss, storm surgebased flood risk, and associated challenges facing south Louisiana, explanations of how the plan was developed, and in-depth discussion of proposed

projects to address those challenges. Taken together, the many parts of the master plan provide ideas for a better future and offer ways to enhance the connection between our coast and all who depend on it.

The 2023 Coastal Master Plan is the fourth such plan developed by the State of Louisiana to articulate a clear statement of priorities to achieve comprehensive coastal restoration and risk reduction goals. The Louisiana Coastal Protection and Restoration Authority (CPRA) is tasked with updating the master plan every six years. Once approved by the Louisiana Legislature, this plan becomes the guiding document for the state's coastal activities and provides a path forward for billions of dollars of investment in the design, implementation, and operation of large-scale restoration and risk reduction solutions.

CPRA was formed following the devastating hurricanes of 2005. The first Louisiana Coastal Master Plan was released in 2007. It has since been updated in 2012, 2017, and now 2023. The 2012 plan represented a significant advancement in the plan framework, utilizing predictive models to prioritize investments, which was built upon in the 2017 plan. The 2023 plan has again built on that framework while improving evaluation tools, incorporating the best available science, and adapting the process to better utilize local knowledge.

Much has changed over the last 18 years since CPRA was formed. Additional hurricanes have ravaged our coast. We experienced the Deepwater Horizon Oil Spill – one of the worst environmental disasters in the history of our country. New funding sources became available, and CPRA and its partners developed, designed, and constructed the state's largest and most ambitious restoration and risk reduction projects.



Image: White Lake Wetlands Conservation Area, 2021 (Louisiana Sea Grant College Program)

There is uncertainty in what the future holds, but work to date demonstrates that the state is invested in the future of our coast. This plan is the blueprint for where we go from here: the goal is a sustainable coast where people can continue to live, work, and enjoy the things that make coastal Louisiana economically, ecologically, and culturally unique and valuable.

Building this resilient coast is a much larger endeavor than the projects CPRA implements. It is dependent on the decisions of individual citizens, communities, local governments, and businesses, as well as fellow state and federal agencies. In addition to prioritizing restoration and risk reduction projects, the 2023 Coastal Master Plan illustrates how the coast will change in terms of landscape, natural resources, and future hurricane risk. It also illustrates how people and communities may experience that change so they can make informed decisions.

LOUISIANA'S BOUNTIFUL COAST

With a population of more than two million people. coastal Louisiana is home to a rich diversity of people, communities, and cultural traditions. It is also home to a variety of industries, ecosystems, and natural resources which feed and nourish its people and the nation's economy. Louisianans have a deep and abiding love for their coast, and their rich cultural heritage is closely connected to the land and water. This connection between the land, water, and people is as diverse and productive as the people themselves. Louisianans include members of multi-generational fishing families that dock in Plaquemines Parish; duck hunters setting out at dawn amongst the freshwater marshes in Cameron Parish; Indigenous peoples whose traditions and histories inform their daily lives on the coast; and new residents who have begun to experience and appreciate the natural beauty and bounty of our coast. For each of these residents, and the millions of visitors to the state each year, maintaining a healthy and productive coast is of critical importance.

STRATEGIC PLANNING

THE ROLE OF THE 2023 COASTAL MASTER PLAN

Previous master plans have set an ambitious path to respond to the loss of our coastal land and threats from storm surgebased flooding. The 2023 Coastal Master Plan continues the state's mission by identifying a long-term program of project planning, design, construction, monitoring, and operations and maintenance, as well as adaptive management of the coastal program and landscape.

Louisiana's coastal program is guided by an ongoing master planning process that allows for progress to be made in advancing projects before the funding to build them is available. By laying out a vision for which projects the state prioritizes for investment, the master plan fosters efficient and effective progress such that when funds become available from any source, action can be taken quickly to implement projects. The plan is sufficiently specific about what needs to be done, and where, to provide a foundation for action. It provides a level of confidence about where funds will go and what outcomes are expected. while not being overly prescriptive on project details so their designs can be tailored to on-the-ground conditions when the time is right. This process bridges the gap between the current conditions in coastal Louisiana and future changes, while providing a path forward to support the lives, livelihoods, and culture of our coastal citizens and communities.

A SIX-YEAR UPDATE CYCLE

Every master plan cycle begins by reviewing feedback on the previous master plan process and incorporating recommended improvements. Additionally, collaboration among CPRA staff, advisory groups, expert partners and contractors, and dialogue with stakeholders across coastal Louisiana is a major component of the plan development process. Goals are identified, timelines are determined, tasks are outlined, and appropriate technical partners are engaged to undertake the work of updating the plan. We work with experts to translate up-to-date data and scientific information into a modeling framework that addresses the physical and ecological dynamics of the coastal landscape and changes in predicted damages from storm surge-based flooding.

In parallel, advisory groups are established and a broad network of coastal experts, landowners, scientists, community leaders, local officials and stakeholders are asked to provide insight and guidance during the development process. By doing this, we identify challenges, understand what Louisianans value, and develop projects that address the coastal crisis. Advisory group members provide input on topics ranging from technical updates and scientific understanding to regional and local priorities and effective communication strategies.

An extensive model improvement effort was one of the first steps in the development process of the 2023 Coastal Master Plan, the results of which are detailed in the following section. These models were used to predict changes in the landscape and storm surge damages over a 50-year period and identify future challenges across the coast.

PROJECT SELECTION PROCESS

Louisiana residents are facing enormous changes. Because people are making decisions about their families, their jobs, and their futures, they need the opportunity to provide input and feedback on plans for the future of the coast. A list of candidate projects




Figure 1.1: The 2023 Coastal Master Plan Development Process.

was developed to address future land loss and storm surge-based flood damages. Project concepts were solicited from the public and members of advisory groups to address key coastal concerns. Projects included in previous master plans that have not yet been implemented were also added to the list. All of these candidate projects were then modeled, and model outputs were used to evaluate project performance in reducing land loss, reducing storm surge-based flood risk, and other impacts on important coastal metrics (such as navigation, habitats, and support of resource-based industries and workers).

We modeled 50 years of a future with each project and compared that to the predictions without the project in place to understand the project's impacts (positive or negative). Then, a computer-based decision support software system, called the Planning Tool, was used to identify groups of robust projects that are predicted to have beneficial impacts under a variety of future conditions. More information on the Planning Tool can be found in Chapter 4 - Evaluate.

Throughout the project selection process, members of the public and advisory groups were kept informed and regularly asked to provide feedback and guidance. As each step of the process was completed, methods and outputs were documented, and modeling results underwent a quality assurance protocol to ensure decisions were made based on accurate and reliable data. Information was communicated to advisory groups, stakeholders, local and state officials, and other interested parties at several points during plan development, followed by an extensive outreach effort that presented the plan to Louisianans. Ultimately, the 2023 Coastal Master Plan is presented to the CPRA Board and the Louisiana Legislature for consideration and, upon approval, becomes the official guidance for the state's coastal program. This process, along with feasibility studies and engineering and design work, allows the state to be more responsive to funding as it is identified by having projects on hand that have already been evaluated and are well developed. This leads to project implementation that is both efficient and effective.

LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY

A PLAN TO ACHIEVE

GOALS, OBJECTIVES, AND PRINCIPLES

The master plan serves as a guide for the state's restoration and risk reduction efforts. This is accomplished by identifying robust projects that meet the goals of the plan by reducing land loss and limiting storm surge-based flood risk across the coast both today and into the future. However, those are not the only concerns of coastal Louisiana residents and the master plan has been developed with people in mind. To better meet the needs of Louisianans,

the master plan refines the vision of our future coast by identifying objectives and principles. Here, we present objectives and principles which have been identified to help support the master plan's goals and provide clarity about what Louisianans value. Together, these goals, objectives, and principles reflect years of coastal planning experience and serve as guidelines for developing and implementing a comprehensive 2023 Coastal Master Plan.

PLAN GOALS

LAND LOSS REDUCTION

Candidate projects are evaluated based upon how much land they create and maintain over 50 years, as compared to the projected landscape without the projects.

STORM SURGE RISK REDUCTION

Candidate projects are evaluated based on how well they reduce expected annual damage in dollars and in terms of structure damages, from storm surgebased flooding as compared to the projected damage without the projects.

PLAN OBJECTIVES -

FLOOD PROTECTION

Reduce economic losses from storm surgebased flooding to residential, public, industrial, and commercial infrastructure.

NATURAL PROCESSES

Promote a sustainable coastal ecosystem by harnessing the natural processes of the system.

COASTAL HABITATS

Provide habitats suitable to support an array of commercial and recreational activities coastwide.

CULTURAL HERITAGE

Sustain the unique cultural heritage of coastal Louisiana by protecting historic properties and traditional living cultures and their ties and relationships to the natural environment.

WORKING COAST

Promote a viable working coast to support regionally and nationally important businesses and industries.

PRINCIPLES

Urgent Need to Take Action. In order to have the best future outcomes, we must plan, design, and implement projects now to address increasing land loss and storm surge-based flood risk in the future.

A Systems Approach. The master plan was developed using a systems approach to risk reduction and restoration, whereby projects that are effective under a range of future conditions were selected.

Planning for the Future. The master plan is charged with providing a sustainable long-term solution for coastal protection and restoration. Projects were evaluated and prioritized based on their effects over the next 50 years. Beyond 50 years, uncertainties about environmental conditions such as sea level rise, project costs, and other factors become too great for the evaluation results to be reliable.

Clear Expectations. We cannot recreate the coast of the 20th century or even retain the coast of today. Instead, we must plan to help shape a new landscape that will continue to support viable natural and human communities into the future.

Acknowledging Residual Risk. Risk reduction measures and restored coastal habitats cannot eliminate all storm surge-based flooding risks. Some degree of residual risk is inevitable.

Collective Responsibility. The state, through the master plan and with its partners, develops the common vision for our coast. Achieving a sustainable coast, however, is a collective endeavor that requires stakeholder input and feedback, and coordinated action from our state, federal, and local government partners, and various other stakeholders including non-governmental organizations (NGOs), business, industry, and academic and research institutions.

Providing for Transitions. Louisiana's coastal crisis has and is displacing people, infrastructure, businesses, and entire communities. Sensitivity and fairness must be shown to those whose homes, lands, livelihoods, and ways of life may be affected by master plan projects or by continued land loss and flooding.

Participatory Process. The master plan was developed with the participation of the many diverse interests that live, work, play, and own property in coastal Louisiana, along with national interests that have a stake in coastal Louisiana's landscape.

Accounting for Uncertainties. Planning for the next 50 years means acknowledging a certain level of financial, environmental, and scientific uncertainty. We do know, however, that land loss and increased flood risk will continue, and the risk of doing nothing is far greater than the risk of acting with incomplete knowledge.

Adapting to Changing Circumstances. The master plan is updated every six years with model and process improvements, including the integration of newly available data, to respond to changing economic, social, environmental, and climatic conditions in Louisiana's dynamic coastal communities.

Efficient Use of Resources. The master plan was developed in a way that acknowledges the need for efficient use of resources, such as funding and sediment. The plan's analysis seeks to capitalize on synergies among projects, resolve overlaps and conflicts, and promote sound management of resources.

Sediment for Restoration. At present, limited supplies of, or access to, renewable sediment resources constrain the restoration efforts we can undertake. We consider both natural processes and dredging options to meet our needs, and focus on introducing sediment from outside the system.

Regulatory Effects. Revisions to some laws and regulations may be needed to help the state's coastal program better achieve its goals, and cooperation is needed from local, state, and federal partners.

Role of Private Landowners, Business, and Industry. Close working relationships with private landowners are essential, not only for their support, but to gain knowledge about private coastal lands. Since Louisiana is also a working coast, partnerships with businesses and industries are also important for the success of the coastal program.

Project/Program Milestone

Legislative Milestone

Notable Hurricane Event

Notable Event -

LEADING UP TO 2023

A TIMELINE OF PROGRESS




Figure 1.2: Timeline of Master Plan Efforts Leading up to 2023 and Other Notable Events.



CPRA is an implementation agency – we do not just plan projects, we build them. For decades, the state and our partners have moved projects forward from conception to construction, securing \$21.4 billion in pursuit of coastal restoration and risk reduction efforts since 2007. Over that time, CPRA has completed more than 140 projects to benefit coastal Louisiana. Since 2007, these efforts have totaled:

- 55,807 acres benefited (87.2 sq mi)
- 193 million cubic yards of sediment placed
- 369 mi of improved levees

10

71.6 mi of restored barrier islands

Louisiana is committed to mobilizing dollars quickly and efficiently through the master plan process and to leveraging advanced science and technology and the dedication of people working to implement the master plan.

The following spread provides more details on some example projects highlighted in the coastwide map shown above.






Figure 1.3: Acres Created by Dredging per Year.



Map 1.1: Implemented Projects as of January 2023.



INTRODUCTION

ROCKEFELLER SHORELINE PROJECTS

The Rockefeller Shoreline projects, three in all, together represent over 5 mi of foreshore breakwaters. They protect reaches of the Gulf shoreline that have been eroding at some of the highest rates in Louisiana.

Due to soft substrates this project involved the development of novel techniques for the placement of breakwaters, including testing of different approaches. Lightweight aggregate in the core of the breakwaters reduces their weight, while providing the necessary structure to reduce wave erosion.





GREATER NEW ORLEANS HURRICANE RISK REDUCTION


The Hurricane and Storm Risk Reduction System (HSDRRS) project includes the construction and improvement of 133 mi of perimeter risk reduction features, such as levees, floodwalls, floodgates, and pump stations to reduce risk for an event with a 1% annual exceedance probability. It also includes about 70 mi of interior risk reduction features such as large-scale pump stations. It is among the most advanced storm surge risk reduction systems in the world.





TERREBONNE BASIN BARRIER ISLAND RESTORATION

The Terrebonne Basin Barrier Island and Beach Nourishment project includes the engineering, design, and construction of approximately 1,100 acres of beach, dune, and marsh habitat within the Terrebonne Basin barrier shoreline system. It uses dredged material from Ship Shoal, and includes restoration of beach, dune and marsh habitat on West Belle Headland, Timbalier Island, and Trinity Island.





SPANISH PASS RIDGE AND MARSH CREATION

The Barataria Basin Ridge and Marsh Creation Project, Spanish Pass Increment project involves dredging sediment from the Mississippi River to restore 132 acres of earthen ridge and 1,538 acres of marsh along Spanish Pass in Plaquemines Parish, a natural historic river distributary west of Venice, Louisiana.





THIS UPDATE OF THE MASTER PLAN

The master plan serves as a long-term, comprehensive guide to restoration and risk reduction investments by the State of Louisiana and is undertaken in parallel with other efforts to address more acute challenges in the coastal zone. In the past six years, several events and initiatives have influenced the conversations and actions around issues of environmental and community change across the coast.

SINCE THE 2017 COASTAL MASTER PLAN

The state and its partners have remained hard at work since the adoption of the 2017 Coastal Master Plan to address challenges across the coast. Thousands of Louisiana residents were negatively affected and/or displaced as a result of Hurricanes Laura and Delta in 2020, and Ida in 2021 among others, and state and federal assistance related to these events is ongoing. The Louisiana Office of Community Development's resettlement of Isle de Jean Charles has begun to see the first residents move to their new homes near Schriever, Louisiana. The Chitimacha Tribe of the Central Coast was awarded \$5 million as part of the U.S. Bureau of Indian Affairs' greatly expanded efforts to assist tribes severely affected by climate-related environmental threats.

Permits for the Mid-Barataria Sediment Diversion were approved by the U.S. Army Corps of Engineers (USACE) and the project received necessary funding to start construction. The HSDRRS was completed and handed off to the state and levee boards. The West Shore Lake Pontchartrain Risk Reduction project was funded and construction has started. In addition, Governor John Bel Edwards' administration

appointed Louisiana's first Chief Resilience Officer and encourages state agencies to incorporate long-term coastal change projections into their planning and operations. Governor Edwards also established the Climate Initiatives Task Force, which released a plan to guide the state's pursuit of carbon neutrality by 2050. In 2018, in response to the statewide flood events of 2016, the state launched the Louisiana Watershed Initiative, a watershed-based approach to reducing flood risk in Louisiana. It is designed to coordinate and align various state and federal programs, and coordinate policies and decision-making among local jurisdictions within a watershed.

WHAT'S NEW IN 2023

Building on the capabilities and advancements of previous plans, the 2023 Coastal Master Plan includes efforts to improve project development and evaluation; incorporate the best available science to refine tools and analyses; collaborate with federal, state, and local governments, academia, and NGO partners; and effectively engage stakeholders.

Following two public solicitations for new project ideas, CPRA worked with Regional Workgroups (RWs) to refine project concepts and identify areas of need that were not represented among the initial proposals. Ultimately, 131 candidate projects were evaluated. Projects were developed with a focus on addressing regional-scale challenges and integrating restoration techniques to amplify benefits. A new robust project selection process was used to identify projects that perform well under a range of possible future conditions to address climate and other uncertainties in the decision-making process. Improvements to predictive models include updates to inputs and assumptions, such as the vegetative response to




Image: Pass A Loutre, 2020 (CPRA)

stressors and ensuring environmental scenario values vary consistently with potential climate change pathways and sea level rise. Risk modeling now incorporates updated and higher resolution coastal assets data, population change, and community demographics information. The development of new risk metrics allows us to better understand and illustrate who is currently most vulnerable to flood risk and how different communities may experience future flood risk. Nonstructural risk reduction strategies are considered coastwide to better support funding and implementation opportunities provided by multiple agencies and programs.

To facilitate effective communication of the results, the 2023 Coastal Master Plan makes more results from the analyses accessible through the Master Plan Data Viewer.

These improvements work together to create a plan that is both realistic and practical, links risk reduction and restoration projects, and focuses on a message of transition and adaptation for coastal Louisiana residents.

FOCUS ON THE COAST

The 2023 Coastal Master Plan presents a vision for the coast and illustrates the benefits of continued investment and implementation of projects.

- The plan relies on a variety of restoration project types that harness natural processes and use available dredge material to create and maintain land over time.
- The plan looks to both structural and nonstructural risk reduction projects to provide storm surgebased flood risk reduction to communities across the coast and provides information on the residual risk faced over the next 50 years.
- The plan provides tremendous economic development opportunities for Louisiana and its citizens. Our investment in coastal research has spurred the growth of this and related fields.
- The ecosystem benefits provided by the plan will support commercial and recreational fisheries and wildlife across the coast and provide additional benefits to our communities.
- The plan provides a blueprint for action that is consistent with and supportive of other efforts at the local, state, and federal level and provides information to support the work of other agencies.



A PART OF THE SOLUTION

PLANNING AND COOPERATION

Coastal resilience is more than restoration and protection. State agencies, parishes, municipalities, levee districts, federal partners, businesses, and individuals must work together in support of a comprehensive approach to enhance the resiliency of our communities, livelihoods, culture, and coastal environment.

The 2023 Coastal Master Plan serves as the guiding document for the state's investments in coastal restoration and risk reduction. While updating each master plan is complex and takes six years to complete, plan development is only one part of CPRA's work.

The master plan process develops and evaluates project concepts to generate regionally significant impacts over decades that complement local and parish-level efforts, and that help respond to specific events, like hurricanes or oil spills. The master plan process allows the state to be prepared when restoration or risk reduction funding becomes available by evaluating project concepts and advancing promising ideas.

Once funds are identified and incorporated into CPRA's Integrated Ecosystem Restoration & Hurricane Protection in Coastal Louisiana: Fiscal Year Annual Plan (annual plan), projects can efficiently move forward. They are analyzed in more detail during the feasibility process through which CPRA, the state, and our partners refine our understanding of how a project is expected to perform and what it will take in terms of funding, timelines, permitting, etc. to construct and operate.

From there, projects can move forward to engineering and design.

The next stage, once funds and permits are in hand, is construction. Depending on the project type and size, this can take several years, and hundreds of local jobs may be created during the construction phase.

Following construction, CPRA or its partners are responsible for project operation, maintenance, and monitoring. This improves project outcomes and provides data and information necessary to inform future planning efforts and adaptively manage the state's coast with respect to ongoing challenges.

CPRA is both a planning and an implementation agency, which ensures consistency between the master plan and CPRA's other charges.

EXPANDED COORDINATION

In addition to the work of CPRA, the State of Louisiana leverages local government initiatives, the efforts of other state agencies, federal studies and funding, and the work of NGO and community-based organizations to expand the reach of our coastal program.

Through state and local partnerships, large-scale risk reduction projects, such as the Morganza to the Gulf project, have been pursued incrementally.

The Governor's Adaptive Governance Initiative (AGI) has promoted information sharing among state agencies and their assessment of



Figure 2.1: Six-Year Cycle to Update the Master Plan.

vulnerabilities, identification of adaptation actions, and pursuit of measures to make our coastal communities more resilient. CPRA supports the agencies in their efforts to consider environmental change projections from the master plan in their long-term planning and decision-making.

In addition to state and local partners, CPRA also works directly with USACE to monitor and maintain levees and coordinates with the Federal Emergency Management Agency (FEMA) and other federal partners during and in the aftermath of damaging storms.

The state's pursuit of these endeavors is anchored in a commitment to the people and places that make up coastal Louisiana. While restoration and risk reduction planning is essential for managing the coast and providing consistent, long-term investment in our communities and ecosystems, it cannot meet every need.

Resilience and the future of coastal Louisiana rely on identifying goals, cultivating a shared vision, and continuing to adapt to changing conditions. The state, through updates to the master plan and each of the efforts above, supports Louisianans in understanding how the coast will change in the future allowing them to prepare accordingly.

>>> Adaptive management is a structured, iterative process of incorporating new information to improve decision-making over time and it is foundational to CPRA's work. As CPRA and its partners continue to plan, design, implement, and monitor large scale restoration and risk reduction projects, the lessons learned are incorporated into each step of the process. Updating the master plan every six years helps ensure adaptive management and allows CPRA to incorporate the best available science and to reassess the tools and processes used to develop the plan.

UNDERSTAND

THE VALUE OF OUR COAST

A trip to coastal Louisiana makes clear what a valuable resource it is. It boasts extensive swamps filled with Spanish moss-draped cypress trees and miles of coastal marshes. Alligators float on the water's surface, between the fish swimming below and the birds flying above. This landscape supports a thriving ecosystem and is home to a diverse group of people and their rich cultures. Many make their living on the Louisiana coast – fishing, hunting, and working in industry. Louisiana's working coast benefits the U.S. economy and Louisiana-made products can be found throughout the world.



Image: Atchafalaya Basin, 2018 (Louisiana Sea Grant College Program)

Image: Fort Pike, 2021 (CPRA)






Image: Pier Fishing at Pointe-aux-Chênes, 2015 (Louisiana Department of Wildlife and Fisheries [LDWF])




Image: Pointe-aux-Chênes, 2020 (CPRA)

A HISTORY OF CHANGE

DYNAMIC LANDSCAPES AND COMMUNITIES

The landscapes and communities of Louisiana have changed immensely over time – from the early Indigenous settlements to our present-day rural and urban populations and industries – and will continue to do so in the future.

Much of the land that makes up coastal Louisiana was formed from sediment that washed down the Mississippi River and was distributed over thousands of years as the river changed course and left behind enormous deltas with vast areas of coastal wetlands. As one delta was built and others degraded, the diversity of the ecosystems—from swamps to salt marshes to barrier islands—emerged. To the west, sediments moved along the coast as the Mississippi changed course, and periodic deposition and erosion led to chenier ridges across the wetland plain.

These underlying formations created a vast complex of wetlands interspersed with protected lakes and bayous that provided essential navigable waterways during pre-colonial and post-industrial periods. The fertile lands, made of rich sediments from overflowing rivers and bayous, first made this region desirable to early native and settler populations.

Louisiana's population, culture, and economy have evolved over time. The original inhabitants of this land were the Indigenous peoples that lived in the area for thousands of years before the arrival of Spanish and French settlers in the 16th and 17th centuries. The population expanded and diversified with the arrival of thousands of enslaved people transported from West and Central African nations. The 18th century saw the arrival of Acadians from present day Nova Scotia who, when they were expelled by the

British, chose to settle in Louisiana. Descendants of these groups, including the geographically unique Creole population, have continued to make their home in Louisiana alongside more recently arrived residents, including members of Louisiana's large Vietnamese and Latin American communities.

During and after World War II, Louisiana's significant economic development was associated with the petrochemical industry and increased drilling for oil and natural gas, both inshore and in the Gulf of Mexico. This energy development completely transformed the state's economy and its landscape. As the oil and gas industry expanded, thousands of miles of canals were cut through Louisiana's coastal wetlands, unintentionally contributing to and exacerbating land loss. Chemical production, leveraging the state's readily available hydrocarbons, sulfur, salt, and water resources, boomed between 1947 and 1957 when the first big move to offshore petroleum production was made. After the war, the rise of global economic markets led to rapid industrialization in Louisiana including oil refineries, petrochemical plants, foundries, food production, fishing, timber, transportation equipment, and electronic equipment. Today, chemical, petroleum, and coal products remain Louisiana's leading industrial sectors, providing approximately 30% of all industrial activity in the state. These industries are located predominantly along the Mississippi River between Baton Rouge and New Orleans, and near Lake Charles, where they are served by deep water navigation channels.

While petrochemical production is still important, the agricultural foundation of rural Louisiana remains strong. Louisiana farmers produce a variety of commodities, including sugarcane, soybeans, rice, feed grains,



Image: Map of the Alluvial Region of the Louisiana Coastal Plain, 1861 (Library of Congress)

cotton, strawberries, hay, and pecans. Louisiana is also the nation's second largest seafood supplier and the seafood industry is a major employer across the coast. From shrimp to oysters and crabs to crawfish, Louisiana seafood remains an iconic product for the state.

Many of these coastal industries and businesses rely on workers living in coastal communities that have been increasingly impacted by damage from hurricanes in recent decades. Repeated flooding, frequent and unpredictable evacuations, and challenges with obtaining affordable insurance are all factors that have contributed to many residents' decisions to move. The residents of south Louisiana have always moved with the changing coast and will continue to do so as they weather these challenges. However, moving away from the coast today is a different proposition than it was 100 or even 50 years ago. The way we currently live and work in coastal Louisiana means most of us move houses or jobs relatively infrequently and have strong ties to our local communities. Long-term, gradual changes to the coastal landscape and increased flooding risks, along with the more acute impacts of hurricanes such as Katrina, Rita, Ike, Gustav, Laura, Delta, and Ida have led some coastal residents to move north. People are moving to areas that might not be ready for them. Increases in traffic, needs for road improvements, and a lack of affordable housing are all problems that expanding communities and their new arrivals face. Understanding the challenges that come with a changing coast is important so individuals and communities can plan and adapt. The 2023 Coastal Master Plan presents a detailed picture of what the future may hold and a plan for transition through continued investment in coastal restoration and risk reduction projects.

ENVIRONMENTAL AND CLIMATE CHANGE

Unfortunately, over the past century, the State of Louisiana has experienced changes to its landscape and the environment that pose significant challenges to the lives and livelihoods of many Louisianans. Since 1932, more than 2,000 square miles of Louisiana's coast, and the benefits they provide, have been lost. Both natural processes – such as hurricanes, erosion, subsidence, sea level rise – and human-made challenges – like the cutting of canals, oil spills, and building levees on the Mississippi River – impact coastal wetlands and barrier islands and undermine their ability to replenish naturally.

These issues are exacerbated by the impacts of climate change, which contributes to increasing rates of sea level rise and more intense hurricanes. Climate change will increase flooding in coastal communities, as tides get higher and roads flood more frequently. Drainage becomes more difficult as water levels rise, flooding fields and yards and causing excessive inundation of previously vibrant wetlands. The remaining wetlands and communities of coastal Louisiana are especially vulnerable, and additional land loss and increased flooding risk are inevitable over the coming decades.

23

PREPARING FOR THE FUTURE

Change is inevitable for Louisiana's coast. The state's landscape will look different in 50 years regardless of the environmental conditions we face. It is important that we prepare for the future in order to protect our way of life. Although the future is uncertain, predictions of climate change are constantly improving and can provide significant insight for how we should adapt to oncoming change in order to retain our culture and traditions. The master plan looks at a range of potential future environmental conditions to best be prepared for what the future brings. The plan looks forward to the next 50 years in order to identify a path forward. This allows us to make timely progress toward the future and be proactive. As the plan is implemented, we evaluate at every step and are able to adapt to the way the future unfolds.



Image: Elevated Camps along Bayou Decade, 2021 (CPRA)

Image: Bridge Repair Post Hurricane Ida, Lafitte, 2021 (CPRA)



Implementing projects to restore wetlands and reduce flood risk are part of how we prepare for the future, but they cannot fully address the impacts that a changing coast will have on residents and communities. Through the state's Adaptive Governance Initiative, CPRA will continue to coordinate with fellow state agencies to help them consider coastal change as they manage programs that support coastal communities and resources—ranging from access to key services to supporting cultural preservation.

For more information on the state's Adaptive Governance Initiative, see **Chapter 7: Beyond the Master Plan**.

P 164



Image: Hurricane Laura Damage in Cameron Parish, 2020 (Louisiana Sea Grant College Program)



Atchafalaya Delta WMA (LDWF)

A PEOPLE-FOCUSED PROCESS

STAKEHOLDER INPUT

The 2023 Coastal Master Plan was developed through years of discussion, engagement, and input from the people of Louisiana.

From the very first master plan, interaction with a broad array of local stakeholders, communities, and technical experts has been crucial to defining the goals of the state's coastal program and developing solutions to address land loss and storm surge-based flooding.

Engagement with the master plan process takes many forms. In 2018, several advisory groups were established to bring experts from across the state into the plan and project development process. The insights and participation of our Coastal Advisory Team (CAT), five Regional Workgroups (RW), and Community Engagement Workgroup (CEW) helped to focus efforts on meaningful advancements, refine project concepts to address critical regional issues, and understand the hopes and concerns of individuals and communities coastwide. One result of this was the development of new project concepts by local experts with on-theground experience and knowledge of conditions.

Throughout plan development, CPRA staff had conversations with a variety of groups and individuals, including fishers, students, landowners, business and industry representatives, NGOs, parish officials, elected leaders, and tribal leaders. Discussions focused on the future of our coast and actions we can take now to achieve a more resilient future. These conversations occurred in many places, including classrooms, civic centers, ports, council chambers, banquet rooms, and boat launches. The figure to the right provides a summary of these efforts for the 2023 Coastal Master Plan.

Briefings (Community groups, civic and NGOs, media, etc.) Coastal Advisory Team meetings Community Engagement Workgroup meetings 28 Regional Workgroup meetings **Predictive Models Technical Advisory** 19 Committee meetings 23 Conferences 9 **CPRA Board meetings** Workshops Informal public meetings Governor's Advisory Commission on Coastal Protection, Restoration and Conservation Master Plan Data Viewer demonstrations Official Public

Master Plan Hearings

218 Engagement touch points





More than 200 hours of engagement

118 Technical Partners

from 31 Institutions / Organizations

113 Advisory Group members



THE ROLE OF SCIENCE

USING WHAT WE KNOW

While we do not know exactly how the coast will change in coming decades, the fact is that the coast will certainly be different than it is today, just as it is different now than in the past. The master plan's intent is not to halt or reverse that change. Rather we use advanced tools to predict a range of possible future coastal conditions. These predictions provide a basis for a plan that moves toward more desirable and sustainable outcomes for Louisiana residents, businesses, and our natural coastal resources.

To ensure the 2023 Coastal Master Plan is built on the best possible scientific foundation, the State of Louisiana brought together local, national, and international experts to refine data, improve predictive models, and design comparative analyses. Through this process and by building on experience from previous master plans, we believe that the 2023 Coastal Master Plan is the most advanced coastal plan of its kind anywhere in the world.

PREDICTIVE MODELS

The master plan uses predictive modeling tools that consider landscape change, storm surge and waves, and flood-related damages to coastal Louisiana structures and assets to understand what the future holds under a range of environmental conditions. These models are also used to evaluate the potential benefits of restoration and risk reduction projects and identify projects that best reduce land loss and storm surge-based flood damages through the 50-year planning time frame. CPRA partnered with multiple entities to use advanced and high performance computer systems to run these models.

THE LANDSCAPE MODEL (ICM)

The landscape of coastal Louisiana is represented using the ICM which predicts coastal hydrology, wetland morphology, vegetation dynamics, and the suitability of habitats to support an array of fish and wildlife. The ICM builds on the version used for the 2017 Coastal Master Plan, but recent improvements include refined resolution in key areas and the incorporation of additional processes.

The State of Louisiana's Coastwide Reference Monitoring System (CRMS) is a large network of more than 300 wetland-based observation stations that, since 2006, have collected data about wetland elevation, water levels, salinity, vegetation, and land change. In the 2023 Coastal Master Plan, data from CRMS stations has been used to refine how wetland vegetation in the ICM responds to changes in salinity and inundation stress. CRMS data, along with data and information from other CPRA-funded studies, were also used to improve the evaluation of subsidence (i.e., sinking of the ground) across the coast.

Future environmental change is an important driver of the predictive models used to inform master plan development and decision-making. During plan development, the most recent available global climate model outputs were leveraged to develop environmental scenarios that use climate-related variables, such as sea level rise rates and temperature changes, to represent plausible future conditions.




Figure 2.2: Predictive Model Inputs.

STORM SURGE AND WAVE MODELS (ADCIRC+SWAN)

Risk to coastal communities from hurricanes and other tropical events will continue into the future. Storm surge and wave models (ADCIRC+SWAN) are used to model storms and provide water level inputs to the risk assessment model.

Synthetic storms with varying characteristics, such as wind speed and central pressure, are used to test the impacts of a range of plausible events.

Working with the USACE Engineer Research and Development Center, an updated set of storms was used to model hurricanes and tropical storms, including more extreme and less intense events than were previously available, to predict associated storm surge and wave heights across the coast.

COASTAL LOUISIANA RISK ASSESSMENT (CLARA) MODEL

The CLARA model is designed to estimate flood depths and direct economic damages from hurricanes and other tropical events. CLARA is used to estimate risk under a range of assumptions about future environmental and economic conditions and with different combinations of structural and nonstructural risk reduction projects in place. The CLARA framework considers uncertainty related to future storms and their effects, as well as the physical landscape.

For the 2023 Coastal Master Plan, multiple detailed asset inventories were combined to characterize residential, commercial, industrial, and public structures across the coast to improve economic damage estimates. Additionally, through work with scholars at Purdue University, artificial intelligence was utilized to produce more accurate first floor elevations (which is used in damage estimates) than in any previous plan.




Figure 2.3: Predictive Model Outputs.

An economic measure of damages, known as expected annual damage in dollars (EADD), is an annualized estimate of storm surge damage. EADD includes damage to structures, their contents, and other direct losses incurred during the recovery period after a storm event, such as lost wages, costs associated with evacuation and temporary displacement, and other considerations. Another metric, expected annual structural damage (EASD) is an annualized estimate of structural damage. EASD is reported in 'structure equivalents' and represents an aggregate risk to structures, with damage to each structure expressed as a proportion of its replacement cost. Using EASD to represent flood damages ensures that the project selection process will not be more heavily weighted toward reducing damages in affluent communities at the expense of communities with lower property values. The incorporation of EASD in the 2023 Coastal Master Plan was an important step in providing an equitable and balanced risk reduction project portfolio.

>>> WANT TO KNOW MORE?

The following appendices provide additional information on model improvements, inputs, and other aspects of the predictive models used in developing the 2023 Coastal Master Plan.

- > Appendix C: Use of Predictive Models in the 2023 Coastal Master Plan provides an overview of all the predictive models and their uses in the 2023 Coastal Master Plan development process.
- Appendix D: Overview of Improvements to Landscape Modeling (ICM) for 2023 provides an overview of the ICM landscape model and how it functions, as well as details on improvements to individual model components.
- > Appendix E: Overview of Improvements to Risk Modeling (ADCIRC+SWAN, CLARA) for 2023 provides an overview of two risk-related models focused on storm surge and waves (ADCIRC+SWAN), and risk assessment (CLARA).

FREQUENTLY ASKED QUESTIONS

Why is the master plan important to Louisianans?

The master plan provides a way for Louisiana leaders, residents, and businesses to understand what may happen in the future to their neighborhood, their favorite fishing areas, and how much flooding may occur in future storms. This allows them to prepare for, rather than react to, the changing coast. By knowing which projects are planned and how they can improve future conditions, individuals and communities can support these efforts, inform others, and work with local, state, and federal officials to expedite project implementation.

How can I get involved in the master plan process?

By reading the plan you are already engaged! The CPRA Board meets monthly to share updates on progress and allow individuals time for public comments. You can also sign up for master plan updates (email us at masterplan@la.gov) and follow our social media to stay informed of recent advancements and upcoming events. Providing your thoughts and comments about coastal change and how it impacts you, gives the state important context for when and where action is needed.

If new data is incorporated into the master plan models and it changes the results from the last plan, does that mean that the previous models were wrong? How do we know this plan is right? The master plan models are neither right nor wrong. Their job is to tell us how our current understanding of how the coast works will play out in the future as conditions change. The regular updates to the state's coastal master plan allow us to ensure that the plan is based on what we know now, and leverage new developments in

understanding the coast. The updates to the models have been related to processes or data sets that we identified as major uncertainties in the previous plan. We have confidence in the plan as we test the models against data, and we use them to select a set of projects that will perform well under a range of assumptions about future conditions.

In this plan, restoration and risk reduction projects were selected based on their performance across multiple future conditions, which means they should provide benefits no matter how conditions change.

Coastal Louisiana has changed throughout history - why do we need a whole plan to deal with future changes? Coastal Louisiana is a very dynamic system and, over time, people have changed how they live to adjust to those changes, sometimes moving across the coast seasonally to harvest wildlife or catch shrimp. People have strong ties to their communities and those communities are one of the great strengths of coastal Louisiana. This plan aims to allow us to continue to live, work, and play in as many places as possible and ensure that Louisianans can continue to make a living in coast-dependent industries like ports, energy, and commercial fishing. Anticipating future change, and preparing for it with restoration and risk reduction projects, supports both our unique cultural heritage and the contribution of coastal residents critical to state, regional, and national economies.

>>> HAVE MORE QUESTIONS?

Visit us online at <u>coastal.la.gov</u> or contact us directly at <u>masterplan@la.gov</u>.

31



PLANNING WITH MODELS

USING PREDICTIVE MODELING TO MAKE INFORMED DECISIONS

Since the 2007 Coastal Master Plan, the state has clearly articulated goals and objectives around reducing land loss, reducing storm surge-based flood risk, and realizing a future coast that supports how Louisianans live, work, and play. Each subsequent master plan used the most up-to-date information to predict how the coast may look in the future due to climate change and other environmental changes.

A combination of observations and scientific projections indicate that rising sea level, more intense hurricanes, and other environmental stressors will have major impacts on coastal systems, but exactly when, where, and how remains uncertain. In the face of this uncertainty, knowing how to adapt to a range of potential futures and achieve the goals of the state's coastal program requires the use of predictive models to inform decision-making.

Predictive models can be used to understand potential future conditions and to test the impact of different strategies in meeting our goals. For example, the ICM was specifically developed to support the master plan process. It represents the landscape of coastal Louisiana and the physical and ecological processes, and feedbacks that drive coastal change. This model uses established and newly developed understandings of coastal dynamics to predict change on the landscape. The interaction between storms, waves, and the landscape are represented in two other models, ADCIRC and SWAN, which predict changes in storm surge flooding. These predictive models, when supplied with boundary conditions and inputs, produce outputs that reflect the complexity of coastal processes and how they change over time.

Boundary conditions are external inputs to the models that vary over time, such as water levels, river flows, or

wind speeds. They are based on historical conditions or predictions of future conditions. Data about elevation, water levels, vegetation, and other aspects of the landscape serve as a starting point, or initial conditions, for the 50-year predictions of landscape change in the ICM. The storm surge and risk assessment models are also informed by the boundary conditions imposed on the ICM as well as information about existing structures and infrastructure across the coast.

The future is uncertain with regard to climate-related environmental conditions and, therefore, assumptions about how climate will change must be made to make landscape- and storm damage-related predictions. We know that sea level rise and subsidence, along with precipitation, temperature, tributary flows, and hurricane intensity are key environmental drivers that influence our coastal landscape. We also know that there is uncertainty in how these variables may change over time. To make informed decisions, the master plan employs a scenario approach to define a range of plausible future environmental conditions.

SCENARIOS AND DRIVERS

For the 2023 Coastal Master Plan, we defined two scenarios, referred to as the "lower" and "higher" scenarios, to drive change within the ICM and ADCIRC+SWAN for use in project selection. Analyses from the 2017 Coastal Master Plan showed that two variables, subsidence and sea level rise, had the greatest impact on model outputs; therefore, development of scenarios for this plan began with choosing values for these two model inputs. Sea level rise rates were selected based on climate change modeling from external sources such as the National Oceanic and Atmospheric Administration (NOAA) sea level guidance and the Intergovernmental Panel on Climate Change (IPCC). Subsidence rates were determined through analysis of shallow and deep subsidence rates




Figure 3.1: Sea Level Rise Curves for Project Selection and Range of Plausible Curves.




Figure 3.2: Environmental Drivers for the Higher and Lower Scenarios.

derived from CRMS and global positioning system (GPS) elevation data, with a greater rate of shallow subsidence applied in the higher scenario than in the lower. Overall, the lower scenario represents more moderate future conditions, while the higher scenario represents more severe conditions with greater sea level rise and shallow subsidence, leading to increased land loss and flood depths compared to the lower scenario.

Once sea level rates were selected for the two scenarios, values for the other scenario variables were derived from related global climate model outputs. When considered together, the model outputs of the two scenarios delineate a range of possible future landscapes and damage profiles that can be used to inform decision-making. While the use of this scenario approach does not make the future more certain, it does provide a better understanding of what may come and, thereby, increases confidence in the master plan being well-suited for whatever the future holds. Additional scenario values

are used in the prediction of storm surge-based flood damage in CLARA. The analysis does not necessarily assume that all storm surge protection levees hold when storm flooding occurs. Rather, CLARA uses two fragility (i.e., infrastructure performance) scenarios: 1) a no fragility scenario, where levees hold, and 2) a fragility scenario that uses assumptions developed by USACE in post-Katrina studies regarding when and where levee breaches could occur. Similarly, whether interior drainage pumps continue to operate during a storm to remove rainfall from poldered areas is also dependent on a variety of unpredictable factors. Therefore, CLARA uses three pumping scenarios: 1) drainage pumps are fully operational, 2) pumps operate at 50% capacity, or 3) no pumping.

>>> Additional details on scenario values can be found in Appendix B: Scenario Development & Future Conditions.

35

THE CURRENT OUTLOOK

THE FUTURE DEPENDS ON WHERE YOU START

When modeling the possible futures of coastal Louisiana, outcomes are significantly impacted by the chosen starting point. As part of the master plan development process, the starting landscape was updated from the one used in the 2017 Coastal Master Plan. This landscape update reflected changes in surface elevation, land/water distribution, and vegetation cover and was adjusted to include new restoration or levee projects that were recently constructed.

It is important that the initial landscape conditions used in the modeling represent the on the ground conditions as much as possible so that there is confidence that model outputs reasonably reflect landscape responses to candidate restoration and risk reduction projects.

FUTURE WITHOUT CURRENTLY FUNDED PROJECTS (FWOCFP)

As part of the 2023 Coastal Master Plan development, the ICM was run for 50 years under a condition referred to as "Future Without Currently Funded Projects (FWOCFP)." For these model runs, the only restoration or risk reduction projects modeled on the landscape are those that have already been constructed. Some of these projects are included in the existing conditions coastwide digital elevation model (DEM), which captures the location and elevation of these projects along with the rest of the landscape features.

The characteristics of other projects or features that were constructed after data were collected for the DEM were imposed on the model based

on engineering design documents, conversations with local landowners, institutions like levee boards, and others who have knowledge of their community and these features.

These model runs serve to demonstrate the possible future of coastal Louisiana if all future planned restoration and risk reduction efforts were halted and the coastal program only continued to operate existing projects. Given that funding for future projects is not guaranteed and that unforeseen circumstances could complicate the process of implementing projects that are already funded, comparing these model runs to those with projects that have funding but are not yet constructed can provide insight into the long-term effects of ongoing investments in the coastal program.

The 2023 Coastal Master Plan, however, does not assume this FWOCFP landscape to be the starting point. The next section provides additional detail about what is included in the master plan's starting landscape or "Future Without Action (FWOA)."

FUTURE WITHOUT ACTION (FWOA)

The FWOA condition in the 2023 Coastal Master Plan serves as the baseline for predicting changes to the landscape and storm surge-based risk into the future. The initial landscape represented in the ICM and passed to the ADCIRC+SWAN and CLARA models reflects a snapshot in time while the coastal program continues its activities. Thus, a decision must be made about how to include the effects of ongoing work in the modeling.

To start, completed projects and existing landscape features are included in the DEM, as for FWOCFP.



Image: Operations at West Belle Headland after Hurricane Ida, 2021 (CPRA)

Then, additional projects and features are included based upon expectations around progress in implementing those projects. This includes projects that have undergone significant advancements in engineering and design, those that have availability of funding for construction, and those for which construction permits are currently being obtained.

Some of the projects included in FWOA are very large and are expected to have significant impacts on the future landscape following implementation. Of particular note are several projects that were included in the 2017 Coastal Master Plan and have been successful in advancing toward construction since that time.

For the first time, two large-scale sediment diversions off of the Mississippi River — the Mid-Barataria and Mid-Breton Sediment Diversions — are included in FWOA. These projects, when implemented, will divert sediment and water from the river when flows are favorable to transport sediment and deliver it to

the Barataria and Breton basins, respectively. The two mid-basin sediment diversions are anticipated to reconnect the adjacent basins to the Mississippi River as a source of sediment to nourish and maintain existing wetlands and to create coastal wetlands over time, in much the same way as southeast Louisiana was originally built by the Mississippi River before levee construction (see Chapter 2 for more details about the history of coastal Louisiana's landscape).

Analysis from the 2017 Coastal Master Plan and subsequent engineering and design studies suggests that the Mid-Barataria Sediment Diversion has the potential to build 21 sq mi of new land over a 50-year period. In September 2022, USACE issued the final environmental impact statement (EIS) for this project. Federal and state permits and permissions for construction are under review as of December 2022. The Mid-Breton Sediment Diversion project is currently in advanced stages of design, and it is anticipated that initial construction could commence upon permit approval.

Another project that is assumed to be on the landscape in FWOA is the River Reintroduction Into Maurepas Swamp. This project includes a gated diversion structure in Reserve, Louisiana, and a conveyance channel crossing Highway 61 and Interstate 10 to allow a maximum of 2,000 cubic feet per second (cfs) of water from the Mississippi River to restore natural swamp hydrology and reduce salinity levels in the Maurepas Basin. Design of the River Reintroduction Into Maurepas Swamp project is nearly complete and construction is expected to begin in 2023. This diversion project was selected as a mitigation feature for the West Shore Lake Pontchartrain levee project, which is a largescale structural risk reduction project currently under construction which is building over 18 mi of levee and floodwalls on the east bank in the river parishes of St. James, St. John the Baptist, and St. Charles. The integrated risk reduction and restoration project features from these two projects marks an important step forward in recognizing the value in mitigating wetland impacts directly adjacent to projects; this will increase the resiliency of the West Shore Lake Pontchartrain Risk Reduction project and is an on-the-ground example of the master plan's emphasis on both reducing coastal flood risk and restoring coastal habitats.

The impact of these projects can be seen in output maps for FWOA model runs (see maps 3.1-3.4) showing land creation that helps to strengthen wetlands in both basins. It is important to note that because these projects are in FWOA their benefits are not attributed to the 2023 Coastal Master Plan. Those benefits, however, are an important part of Louisiana's coastal program and are the result of targeted, significant investment in large-scale restoration projects.




Figure 3.3: Land Area Over 50 Years, FWA and FWOCFP, Higher and Lower Scenario.

FUTURE WITHOUT ACTION OUTCOMES

Even with these projects assumed to be on the ground, the FWOA landscape realizes significant land loss and increases to storm surge-based flood depths over the 50-year model prediction. Under the lower scenario, 1,100 sq mi of land are lost at Year 50; an equivalent amount of loss occurs by Year 34 under the higher scenario, with up to 3,000 sq mi lost at Year 50 under those more severe environmental conditions.

This land loss impacts not only the landscape configuration and ecology but also results in changes to storm surge and waves and, thus, flood-related damages. Without additional project implementation, flood damages could increase by up to \$19 billion annually, with 17,000 additional structures damaged due to significant increases in flood depths. These possible futures without action reveal the challenges that the 2023 Coastal Master Plan was developed to address.





Figure 3.4: Expected Annual Damage in Dollars (EADD) and Expected Annual Structural Damage (EASD),

Over 50 Years, Future Without Action, Higher and Lower Scenario.



Because Louisiana's coast is a dynamic system that will continue to be impacted by a changing climate, environmental conditions 50 years in the future will be different from those experienced today.


Predictions of the FWOA landscape define the scale of the land loss challenge in coming decades and serve as a baseline against which candidate projects can be compared to determine their potential benefit.


Land change projections for the master plan's lower environmental scenario, one of two scenarios used for project selection, are shown above. Under this environmental scenario, coastal Louisiana would experience moderate

climate change impacts, including sea level rise of 1.6 ft over 50 years. Without the 2023 Coastal Master Plan projects, the lower scenario ICM outputs predict 1,100 sq mi of land lost in that same time period. Much of the projected loss is concentrated in lower basins and on marsh edges.

>>> Go to **Chapter 5: Take Action** to read about how CPRA addresses these anticipated challenges through protection and restoration projects.

P 73







Planning under uncertainty requires considering multiple possible future environmental scenarios to understand the range of possible outcomes that the master plan may need to address. Land change projections for the master plan's higher environmental scenario after 50 years are shown above. Under this possible environmental scenario, coastal Louisiana would experience severe climate change impacts, including sea level rise of up to 2.5 ft over the next 50 years. Without the projects selected for the 2023 Coastal Master Plan, the higher scenario ICM outputs predict extensive land loss of 3,000 sq mi over that same time period, with every region of the coast affected.

Due to uncertainty around future climate conditions, both scenarios are used in the development of the 2023 Coastal Master Plan to represent a range of future landscapes and to select robust projects that can provide benefits for the coast for whatever future conditions transpire.

>>> Go to **Chapter 5: Take Action** to read about how CPRA addresses these anticipated challenges through protection and restoration projects.

P 73







Storm surge-based flood depths are projected to increase in the future as more intense storms interact with higher sea levels, lower land, and with the continued degradation of coastal wetlands that can act as natural defenses. Under the lower environmental scenario, an additional 1.6 ft of sea level rise is expected over the next 50 years, adding height to already damaging storm surge levels. As a result of climate change, hurricanes are assumed to increase in intensity by 5% over the same period, exacerbating the risk posed by storm surge. Lower scenario projections of storm surge-based flood depths at locations across the coast with a flood depth of 1% Annual Exceedance Probability (AEP)

are displayed above. That means that every year there is a 1% chance that these flood depths will be met or exceeded. These projections are for a future without the structural risk reduction projects selected for the 2023 Coastal Master Plan and show significant risk of flooding in communities across the coast.

>>> Go to **Chapter 5: Take Action** to read about how CPRA addresses these anticipated challenges through protection and restoration projects.

P 73






Higher scenario projections of storm surge-based flood depths at locations across the coast with a flood depth of a 1% AEP are illustrated above. When compared to the lower scenario, it is clear that more severe climate change impacts — such as sea level rise of up to 2.5 ft and increased storm intensity of up to 10% at Year 50 — combined with higher subsidence have a significant impact on the potential depth of storm surge-based flooding. The northward migration of the storm surge-impact and the expansion of areas projected to experience the largest storm surge heights (more than 21 ft in some areas) can be seen under the higher scenario without the implementation of 2023 Coastal Master Plan projects.

Due to uncertainty around future climate conditions, both the lower and higher environmental scenarios are used in the development of the 2023 Coastal Master Plan to represent a range of future landscapes and to plan robust projects that can provide benefits for the coast under any plausible future condition.


>>> Go to **Chapter 5: Take Action** to read about how CPRA addresses these anticipated challenges through protection and restoration projects.





BY THE NUMBERS

A FUTURE WITHOUT THE 2023 COASTAL MASTER PLAN



FREQUENTLY ASKED QUESTIONS

Two different maps are shown for land change – how do I know which one is right? The maps are based on different assumptions about the future, so neither is right nor wrong. Rather, they show us where land could be lost, where it could be built, and how much change could occur. If an area of land is lost – or built – in both maps, then we are more certain that type of change is going to occur. Both maps make assumptions about future climate and river conditions as well as how projects and structures, such as locks, are operated. If these assumptions do not play out exactly as predicted, the coastal map could be different from those presented.

I've always heard about flooding from a "100 year storm", but the master plan doesn't use this term – why? What is used instead? The master plan does not focus on recurrence intervals (e.g., 100-year storm), as those descriptions are based on long-term averages. As Louisianans have experienced, we can have a 100-year storm two years in a row. Instead, the maps show flood depths that have an AEP of 1% — that means every year there is a 1% chance that these flood depths will be met or exceeded. The depths and probabilities are calculated using flood depths associated with a set of storms that statistically reflect historical storm characteristics and the probability of those storms occurring in coastal Louisiana.

The land change maps show my community at risk of significant land loss through the model period – how should I use this information?

The change shown in some areas is dramatic and is clearly concerning. Remember, however, that FWOA is used as a baseline to select restoration and risk reduction projects. Compare these maps with those shown later to see what difference the master plan can make in your area. You can use that information to advocate for construction of projects in the plan or to work with officials on other projects that could be included in future master plans to alleviate the loss and mitigate risk.

>>> HAVE MORE QUESTIONS?

Visit us online at <u>coastal.la.gov</u> or contact us directly at <u>masterplan@la.gov</u>.

2023 COASTAL MASTER PLAN



PROJECT SELECTION

SETTING PARAMETERS FOR PLANNING

Selecting projects for inclusion in the master plan is a complex endeavor, because the process needs to be guided by realworld considerations, such as funding, resource constraints, and environmental change. It is also important to consider how projects may interact and the impact of the full plan on different aspects of the coast. In the end, the projects included in the master plan represent a suite of solutions to address a variety of coastal issues Louisianans face now and into the future.

DECISION DRIVERS

As discussed in Chapter 2, the projects evaluated in the master plan process are compared based upon their performance with regard to two decision drivers: land area built and maintained and reduction of flood risk. While many of the projects included in the 2023 Coastal Master Plan have additional important benefits (e.g., supporting habitat and ecosystems, maintaining salinity gradients, supporting resource-based industry, etc.), the evaluation process is based upon project performance with regard to the two decision drivers.

Land Loss

Reduction



Storm Surge Risk Reduction

PLANNING HORIZON

When planning, it is important to define the planning horizon — how far in the future will projects continue to yield results? In the master plan process, a 50-year planning horizon has been selected for a variety of reasons. Assessing project benefits over several decades allows long-term effects to be considered as well as near-term outcomes, and over 50 years the plan provides benefits for multiple generations.

Additionally, with the uncertainty inherent in the master plan process regarding both funding and climate change, a 50-year planning horizon is considered to be as far into the future as we can reasonably project those considerations with an acceptable level of confidence. The further into the future projections are made, the less certain we are about them.

Finally, 50 years is thought to be a sufficiently long planning horizon to be separated from political cycles at local, state, and federal levels and instead encourage "big picture" thinking and decision-making.






Image: Caminada Headlands Restoration Project, 2016 (CPRA)

CONSTRAINTS


The 2023 Coastal Master Plan was developed using two fundamental constraints. First, a \$50 billion total planning budget for a 50-year period was selected with the funds divided evenly between restoration projects and risk reduction measures. This represents an aspirational but potentially achievable level of investment. While the State of Louisiana has budgeted more than \$1 billion annually for the coastal program in recent years (as documented in the CPRA Fiscal Year 2023 Annual Plan), that level of funding has not been secured for the full 50 years considered in the master plan. Because funding for the coastal program is not guaranteed, the master plan is also divided into two implementation periods (IP1 [Years 1-20] and IP2 [Years 21-50]), with the most beneficial projects identified for near-term construction in the first 20 years of the plan with a budget of \$25 billion. More information on funding and implementation periods can be found in Chapter 5.

The second constraint considered is sediment availability. Restoring, creating, or maintaining

wetlands often requires sediment. The master plan recommends marsh creation projects that require a source of sediment to create wetlands. For the 2023 Coastal Master Plan, the sediment needed for marsh creation and landbridges is calculated and matched against how much sediment is available in potential borrow areas. This constraint, due to the variable cost of accessing different sediment sources and transporting material to project sites, also impacts project costs and, thus, which projects can be selected under the budget constraints discussed above.



Funding



Sediment Availability

PROJECT TYPES

ONE COAST, MANY SOLUTIONS

To address coastal land loss and storm surge-based flood risk, 131 candidate projects (113 restoration and 18 structural risk reduction projects) were considered for selection in the 2023 Coastal Master Plan. Programmatic projects that address locally important issues and concerns were not specifically evaluated and remain consistent with the master plan.

A LONG-TERM, COASTWIDE PLAN FOR RESTORATION AND RISK REDUCTION

The projects included in the master plan are based on scientific and engineering concepts and our understanding of the coastal landscape. The modeling shows they each provide benefit over the 50-year planning horizon. The \$50 billion planning budget accommodates a variety of project types that are consistent with the goals and objectives of the 2023 Coastal Master Plan.

FOCUS ON ADDRESSING REGIONAL CONCERNS

Not every part of the coast will change in the same way due to climate change and other local factors; therefore, some project types are better-suited to address the issues in a specific location than in others. Projects need to address the concerns experienced both today and into the future.

>>> For more information, see Appendix F: Project Concepts and Appendix C: Use of Predictive Models in the 2023 Coastal Master Plan to learn more about the design and the performance of projects.

SUPPORTS MASTER PLAN OBJECTIVES

Beyond their individual benefits, the suite of master plan projects should collectively support master plan objectives (see Chapter 1 for more details). This is tracked through a series of metrics that consider whether the master plan as a whole supports the lives, livelihoods, and cultures of coastal Louisianans.

See the following pages for more information on the project types considered in the master plan analyses as well as examples of programmatic project types.

RISK REDUCTION PROJECTS



Structural Risk Reduction

One effective means to address storm surgebased flood risk in coastal Louisiana is through the implementation of structural risk reduction projects. This project type encompasses new and improved levees, flood gates, storm surge barriers, and other structural elements that reduce flooding.



Nonstructural Risk Reduction

Risk reduction can also be successfully achieved through nonstructural mitigation measures. For the 2023 Coastal Master Plan, nonstructural measures, including elevating residences, commercial floodproofing, and voluntary acquisition, are considered to be applicable across all coastal communities. More information on implementing nonstructural risk reduction can be found in Chapter 5.

RESTORATION PROJECTS

Restoration projects utilize varied approaches to restore, create, and sustain land. Projects using a single approach were considered for selection alongside integrated projects, which combine features from multiple project types into one integrated concept. In the end, a suite of restoration projects is planned and operated together to maximize their effectiveness and benefits over time, and surpass the benefits of any single project or project type.



Ridge Restoration



Marsh Creation



Landbridge



Diversion



Hydrologic Restoration



Integrated Projects

PROGRAMMATIC RESTORATION PROJECTS

CPRA implements several types of projects that are not individually identified in the master plan. With the exception of barrier island maintenance, these projects are often smaller scale, designed to address site-specific issues, and typically provide highly localized benefits. While these types of projects are not explicitly listed in the plan, they are consistent with the master plan. More information on programmatic restoration projects can be found on p. 64.



Barrier Island Maintenance



Oyster Reef Restoration



Shoreline Protection



Bank Stabilization



Programmatic Restoration

55

Structural Risk Reduction

Structural Risk Reduction projects protect people and property with earthen levees, concrete T-walls, floodgates, and other structural components. They reduce the risk of storm surge flooding and damage within the protected area.



Image: Plaquemines Levee (CPRA)



Nonstructural Risk Reduction measures include the floodproofing, elevation, or acquisition of at-risk properties depending on projected flood depths. Nonstructural Risk Reduction measures are entirely voluntary and are undertaken in close collaboration with local residents and property owners.



Image: Elevated Houses on Grand Isle (Lindsey Janies)




Figure 4.1: Structural Risk Reduction Project Type Visualization.




Figure 4.2: Nonstructural Risk Reduction Project Type Visualization.



Ridge Restoration

Ridge Restoration projects re-establish historic coastal ridges and forested maritime habitat through sediment placement and new plantings. Restored ridges are high points during storm events, providing refuge for animals and potentially reducing storm surge.



Image: Barataria Basin Ridge And Marsh Creation Spanish Pass Increment, 2022 (CPRA)



Marsh Creation

Marsh Creation projects restore landscape and ecosystem processes, enhance habitat, and provide additional storm surge attenuation. Wetlands are created through placement of dredged material and plantings in shallow open water or areas with deteriorated marsh.



Image: Lake Borgne Marsh Creation, 2022 (CPRA)




Figure 4.3: Ridge Restoration Project Type Visualization.




Figure 4.4: Marsh Creation Project Type Visualization.

EVALUATE



Landbridge

Landbridges are linear tracts of constructed marshes oriented across coastal basins which provide important habitat and help attenuates waves. They include additional features to plug or constrain channels which help restore basin hydrology.



Image: Project Construction (Lindsey Janies)




Figure 4.5: Landbridge Project Type Visualization.



Diversions convey freshwater and sediment from rivers into adjacent wetland basins. These projects restore historic deltaic processes, build new land, nourish existing wetlands, and prevent saltwater incursion into the estuary.



Image: Caernarvon Freshwater Diversion, 2021 (CPRA)




Figure 4.6: Diversion Project Type Visualization.

Innl

Hydrologic Restoration

These projects use techniques to ensure water movement across the landscape supports a healthy ecosystem at a basin or sub-basin scale. Small-scale hydrologic restoration focusing on restoring more localized hydrologic patterns (e.g., utilizing plugs and control structures, canal backfilling, channel cleanout) are considered programmatically consistent with the master plan.




Image: Cameron-Creole Maintenance Structure (CPRA)



Barrier Island Maintenance projects use dredged sediment to rebuild and strengthen the beaches, dunes, and backbarrier marshes of degrading barrier islands in response to damage from storms. This work enhances natural storm surge attenuation and maintains or improves critical wildlife habitat.



Image: Whiskey Island, 2009 (CPRA)




Figure 4.7: Hydrologic Restoration Project Type Visualization.




Figure 4.8: Barrier Island Maintenance Project Type Visualization.

EVALUATE



PROGRAMMATIC Programmatic Restoration

A comprehensive approach to coastal restoration requires the use of a variety of techniques to restore ecosystems and improve future outcomes for the coast. In addition to the project types described on the previous pages, a wide variety of additional project types are considered effective and consistent with the master plan. For example, smaller scale programmatic projects like shoreline protection, vegetative plantings, and small-scale hydrologic restoration may be pursued through programs that allow them to be evaluated on a case-by-case basis, like the Coastal Wetlands Planning, Protection, and Restoration Act (CWPPRA), Revived Economies of the Gulf Coast States (RESTORE) Parish Matching Fund, and the Restoration Partnership Fund.



Image: Vegetative Planting at Elmer's Island (CPRA)



Image: Grand Isle Oyster Hatchery (Louisiana Sea Grant College Program)



Image: Living Shoreline Demonstration Project, St Bernard Parish, 2018 (CPRA)



Image: Vegetative Planting in St. Bernard Parish (Louisiana Sea Grant College Program)

EVALUATE PERFORMANCE

A PLANNING TOOL TO SUPPORT DECISION-MAKING

After project effects are evaluated with predictive models, projects are selected for inclusion in the plan using the Planning Tool. This tool helps the state formulate a robust, long-term plan objectively and transparently.

The Planning Tool is a computer-based decision support system, composed of a database of predictive model results, an optimization model to define collections of projects based on decision drivers and constraints, and an interactive visualization package to support deliberations between different groups of projects (or alternatives).

The models predict how the coastal landscape and associated flood risks may change over the next 50 years under different environmental scenarios, and how different restoration and risk reduction projects could change the coastal landscape and flood damages 50 years into the future.

The Planning Tool uses the model outputs to develop groups of projects to implement in IP1 and IP2 that best achieve the state's goals, subject to budget and sediment constraints. There is no correct alternative, and the Planning Tool is designed to formulate many alternatives and summarize the key differences among them. The Planning Tool is part of a deliberation-with-analysis approach to support the state's complex planning challenge.

Although the Planning Tool has been used to support the master planning process since 2012, several improvements were made for this plan to address limitations of previous analyses.

ROBUST PROJECT SELECTION

In previous master plans, projects were selected based on a single environmental scenario. The Planning Tool was updated to use a robust selection process for the 2023 Coastal Master Plan that considers both scenarios. This process first identifies high-confidence projects by formulating alternatives for each of the two scenarios – called "optimal" alternatives. Projects common to both optimal alternatives are referred to as high-confidence projects (see Figure 4.9).

The Planning Tool then iteratively increases the budgets for each optimal alternative until a set of high-confidence projects are defined that expend that original amount of funding. This process was applied for both IP1 and IP2 for restoration project selection. For structural risk reduction, fewer candidate projects were considered, and the same set of projects was chosen for each scenario for IP1.

A NEW APPROACH TO NONSTRUCTURAL PROJECTS

Risk reduction projects can be either structural or nonstructural. Previous master plans selected specific projects in both categories. For the 2023 Coastal Master Plan, the state recognizes that nonstructural damage mitigation is often carried out at the local scale through a number of different state and federal programs, and that its effectiveness is highly dependent on local participation that may not be well characterized in the predictive models. With this in mind, nonstructural projects are considered programmatically consistent. This means that the plan does not identify individual communities as 'selected' or not selected.

However we do define and evaluate nonstructural projects for each community as a way to help prioritize structural risk reduction projects and identify how much of the total budget could costeffectively be invested in nonstructural. In IP1, nonstructural projects were identified, defined by 1% AEP flood depths at initial conditions and a 75% participation rate, and their benefits compared to those of structural protection projects by community. The Planning Tool used these to support the selection of structural risk reduction projects in two ways. First, for a single community, the Planning Tool could select only the structural or the nonstructural project, not both. Second, a structural project for a given community must perform favorably against all potential nonstructural projects, anywhere on the coast. In other words, if any nonstructural project was higher-performing than a given structural project, the structural project would be lower priority in the Planning Tool selection process.

In IP2, the flood depths used to define nonstructural projects were adjusted to account for future conditions, and the participation rate was adjusted based on the selection of projects in IP1. For both IP1 and IP2, the Planning Tool identified the best set of projects – from both structural and nonstructural options – to reduce storm surge-based flood damages.

BENEFITS OVER TIME

As the coastal landscape changes over time and sea level rise increases, the benefits of restoration and risk reduction projects change over the 50-year period of analysis. In previous master plans, specific points in time were averaged to characterize project benefits: 20 and 50 years for restoration projects and

25 and 50 years for risk reduction projects. While the objective was to ensure that both nearer- and longer-term benefits were considered, the approach penalized projects with benefits that rapidly declined in the last few years or those with higher benefits that were delayed in time. For the 2023 Coastal Master Plan, the state's goals are represented by equally weighting annual damage reduction and annual land building across all 50 years of the plan period. For risk reduction projects, EASD (a term that captures how many structures are impacted by flooding and to what degree) is equally weighted with EADD to better reflect equity in damage reduction investments.

PROJECT INTERACTIONS

Another important modification to the project selection process is the addition of an intermediate modeling step in which restoration projects selected for IP1 are assumed to be already constructed in the evaluation of the remaining projects for IP2. The restoration projects identified for IP1, are included when the predictive models are run to evaluate the effects of the remaining candidate projects. The candidate projects interact with the IP1 projects and the resulting benefits are used in the selection of projects for IP2.

This approach assumes that remaining candidate projects are only eligible to be selected for IP2, and the new project evaluations are used to determine which remaining projects to select.

METRICS

In addition to the decision drivers and constraints used in the Planning Tool, we developed metrics based on model outputs and used community characteristics, such as demographic information

67




Figure 4.9: Project Selection Process.

and major industries, to better understand how the changing coast and the projects being evaluated impact different communities and resources.

Ecosystem metrics help us consider the ability of projects to create or maintain suitable habitat for various species. Community metrics combine ecosystem outputs and risk outputs to help us characterize how certain communities, like those associated with traditional fishing or agriculture, may be impacted.

Demographic data helps us understand how structural risk reduction projects impact more vulnerable communities. During the project selection process, these can be used as a check on the Planning Tool optimization to make sure we are directly addressing questions of equity and resilience and not selecting suites of projects that disproportionately impact certain communities.

SEDIMENT BORROW SOURCES

Sediment is an important resource for some types of restoration projects, and cost-effective sources in coastal Louisiana are limited. In previous master plans, each project requiring sediment was associated with a specific borrow area and sediment availability was a constraint. For the 2023 Coastal Master Plan, the Planning Tool was configured to allow an individual project or project element to borrow from more than one source, if cost efficient to do so. Thus, sediment availability is now a factor in the cost of a project and is reflected in the budget constraint, rather than being a separate constraint. For the 2023 analysis, 41 individual sediment sources were defined. For sources that are not within the Mississippi River channel, a single amount of sediment was specified that can be drawn upon until exhausted. For Mississippi Riverbased sources, sediment is considered renewable. These sources were assigned a 10-year renewable fill volume available at any time in those 10 years.

PROJECT SELECTION

The Planning Tool uses the outputs from the predictive models summarized by 25 geographic areas (or ecoregions) for restoration outcomes and 374 communities for damage reduction outcomes. Each selected project begins accruing engineering and design costs in the first year of IP1. Construction costs are incurred immediately following engineering and design, and operation and maintenance continues through the end of the 50-year planning horizon. For both restoration and risk reduction projects, the procedure first selects projects to implement in IP1. The Planning Tool assumes that these projects are implemented in the first year and that cost (and sediment requirements for restoration projects) for the first 20 years of each project must be met by IP1 funding and sediment sources. For some projects, construction costs and sediment requirements extend beyond the first 20 years. In this case, the Planning Tool ensures that sufficient budget

and sediment are available in IP2. When projects are selected for IP2, the requirements for the projects selected in IP1 must be satisfied before the Planning Tool selects projects to implement in IP2. Any project not selected in IP1 is a candidate for selection. These projects are assumed to begin engineering and design in the first year of IP2 and accrue costs from that year forward. The Planning Tool again ensures that all funding and sediment requirements are met.

Throughout this process, the visualization component of the Planning Tool was used to compare different alternatives and consider the coastwide distribution of projects and their benefits, while considering varying budgets.

>>> For more information on the Planning Tool, see **Appendix G: Decision-Making**.

COMMUNICATING THE PLAN

REACHING STAKEHOLDERS

The 2023 Coastal Master Plan identifies the projects our state should implement and provides important information about how that translates to land created or maintained. The plan also provides details about which communities will be most vulnerable to flooding in future years and how structural and nonstructural risk reduction projects can address that risk. We cannot predict exactly how our coast will change, but based on what we know today, the projects in this plan will allow us to build land in crucial areas and reduce current and future storm surge-based flood risk. Because this information is critical to individuals and communities, a key part of the master plan development process is communicating the possible future landscape and projects that can mitigate land loss and reduce storm surge-based flood risk. Conversations with stakeholders and advisory groups take place throughout the master plan update cycle, and emphasis is placed on producing materials and tools to facilitate that communication.

As the 2023 Coastal Master Plan is drafted, work begins on communicating the project list and what the plan delivers. This includes posting a digital version of the master plan document on the CPRA website along with technical appendices and



Figure 4.10: Project Information in the Data Viewer Desktop View.

attachments that document the development process and provide details on models, outputs, and other topics. These resources are hosted on the website alongside outreach resources, such as technical webinars and corresponding presentation slides.

The Master Plan Data Viewer was updated, and a Guided Tour feature will help first-time users understand the nature of the coastal crisis and what implementation of this plan would accomplish. An Explore feature allows users to dive deeper into data from across the coast, including maps of the FWOA coast and the effects of the 2023 Coastal Master Plan. New features of the data viewer include a map export function to facilitate easy printing of master plan-related maps and expanded data download capabilities to ensure master plan-generated data is available for researchers and interested audiences.

Print materials were also developed to supplement technical documentation and presentations at outreach meetings. Four different types of fact sheets were developed to provide quick overviews of key master plan information. These fact sheets provide data at levels ranging from the individual project to regional overviews.



Figure 4.11: Land Change Data in the Data Viewer Desktop View.

FREQUENTLY ASKED QUESTIONS

Which type of project is best at restoring the coast? Different project types perform best in different circumstances. Projects that restore hydrology or increase delivery of freshwater and sediment may perform well where saltwater intrusion and a lack of sediment contributes to land loss. Marsh creation projects do well in fragmented marsh areas; this is accomplished by filling shallow water areas and elevating the marsh surface. In some cases, integrated projects are needed to address multiple issues.

Why does CPRA use the Planning Tool to select **restoration projects?** If funding were the only constraint, ranking projects based on costeffectiveness might be a reasonable approach to project selection. However, we recognize that sources of sediment near project sites are limited. The Planning Tool allows both funding and sediment to be considered simultaneously, allowing CPRA to choose robust project sets. It also enables the evaluation of how the master plan may benefit or impact other things that are important to Louisianans, such as habitat creation, navigation, and the working coast.

What are expected annual damages? Our analysis considers storms of different intensity and tracks, and their expected probability of occurring in any one year. The flood depths resulting from those storms change over time as the coast degrades and sea level rise increases water levels. Rather than selecting a single probability of flooding or a single time period, the Planning Tool combines the total damage from all possible flood events considered and the likelihood of each event occurring, or expected annual damages. The change in expected annual damage due to a project being built is used

to summarize the benefits of projects over time, considering different types of storms that could occur. This damage is reported both in dollars and based on reductions in the number of structures damaged and the degree of damage experienced.

Why are different implementation periods used?

The state recognizes that we need to address the coastal crisis as soon as possible and that we need to build projects that will continue to provide benefits to future generations, but that the funds we need will not all be available right away. Therefore, the state wants to identify the best performing projects for implementation. Projects are evaluated over the entire 50 years, and those that perform best in terms of maintaining/building land or reducing expected annual damage, based on a set amount of funding, are assigned to IP1. The remaining projects are evaluated on their benefits over the last 30 years (i.e., IP2) of the 50-year planning horizon. Using two implementation periods ensures the master plan is making reasonable assumptions about project funding streams while maximizing the timing and benefits the projects provide.

>>> HAVE MORE QUESTIONS?

Visit us online at <u>coastal.la.gov</u> or contact us directly at masterplan@la.gov.





The 2023 Coastal Master Plan identifies projects designed to restore, create, and maintain land; reduce flood risk to citizens and communities; and sustain habitats that support a variety of recreational and commercial activities. The restoration and risk reduction projects selected perform well with respect to future conditions and reflect a comprehensive, long-term focus and continued commitment to balancing the diverse objectives of the master plan. In addition to these specific projects, \$2.5 billion is allocated to programmatic restoration efforts, including barrier island maintenance and repair, small-scale hydrologic restoration, and local strategies, such as bank stabilization and oyster reef

restoration. Additionally, \$11.2 billion is allocated to nonstructural risk reduction activities across the coast.

Beyond the projects, the master plan acknowledges that the coastal area is dynamic, and additional adaptation will be required to continue living, working, and playing in coastal Louisiana. The plan alone is not sufficient to respond to all of the challenges the future may bring, but it is a catalyst for coordinating local, state, and federal efforts to help address our coastal land loss crisis and threats from storm surge-based flooding. The plan also highlights the need to continue to pursue the greenhouse gas reductions that are necessary to avoid the most severe impacts of climate change.



TAKE ACTION

| | | PROJECT TYPE | ID# | PROJECT NAME | IP | COST |
|--|---------------|------------------------------|------|--|----|---------|
| CHENIER PLAIN | | Hydrologic Restoration | 347 | Mermentau Basin Hydrologic Restoration | | \$ 130M |
| OHENIER I EAIR | PARI | nydrologic Restoration | 349 | Cameron-Creole to the Gulf Hydrologic Restoration | 1 | \$ 59M |
| See page 98 for regional | | | 207 | South Grand Chenier Marsh Creation | 1 | \$ 390M |
| project map and project descriptions. | | | 210 | Mud Lake Marsh Creation | 1 | \$ 330M |
| ucscriptions. | | - | 216 | Southeast Calcasieu Lake Marsh Creation | 2 | \$ 450M |
| | | | 218 | Cameron Meadows Marsh Creation | 1 | \$ 150M |
| | proport | Marsh Creation | 221 | East Pecan Island Marsh Creation | 1 | \$ 650M |
| | | | 224c | East Calcasieu Lake Marsh Creation | 1 | \$ 340M |
| | | | 228 | Calcasieu Ship Channel Marsh Creation | 1 | \$ 83M |
| | | | 293c | Freshwater Bayou North Marsh Creation | 1 | \$ 150M |
| | | • | 296 | Little Chenier Marsh Creation | 2 | \$ 51M |
| | | • | 298b | West Brown Lake Marsh Creation - North | 2 | \$ 410M |
| | | | 298c | West Brown Lake Marsh Creation - South | 1 | \$ 240M |
| | | | 300b | West Sabine Refuge Marsh Creation | 2 | \$ 640M |
| | | | 300c | West Sabine Refuge Marsh Creation - Central | 1 | \$ 130M |
| | | Ridge Restoration | 232 | Pecan Island Ridge Restoration | 1 | \$ 20M |
| | 4 | | | | | - |
| OFNITRAL COACT | | | 157c | East Rainey Marsh Creation | 1 | \$ 350M |
| CENTRAL COAST | (1) | Marsh Creation | 213 | West Rainey Marsh Creation | 1 | \$ 400M |
| See page 110 for regional | | | 344b | Central Coast Marsh Creation - Point Au Fer | 1 | \$ 270M |
| project map and project descriptions. | | | 346 | Marsh Island Barrier Marsh Creation | 1 | \$ 710M |
| | | Structural Risk Reduction | 148 | Franklin and Vicinity | 2 | \$ 310M |
| | ≋ ∧ | | 150 | Iberia/St. Mary Upland Levee | 1 | \$ 1.7B |
| | Ĭ | | 292 | Abbeville and Vicinity | 2 | \$ 610M |
| | 20 | Ridge Restoration | 231 | Cheniere au Tigre Ridge Restoration | 1 | \$ 26M |
| | ,oes, | | | | | |
| TERREBONNE | | Hydrologic Restoration | 113 | Central Terrebonne Hydrologic Restoration | 1 | \$ 16M |
| ILIMEDOMINE | | | 342 | Western Terrebonne Hydrologic Restoration | 1 | \$ 22M |
| See page 122 for | M | Landbridge | 335d | Eastern Terrebonne Landbridge - East | 1 | \$ 460M |
| regional project map and | | | 335e | Eastern Terrebonne Landbridge - West and Central | 2 | \$ 1.0B |
| oroject descriptions. | | | 123 | Belle Pass-Golden Meadow Marsh Creation | 1 | \$ 1.2B |
| | | Marsh Creation - | 125 | North Terrebonne Bay Marsh Creation | 1 | \$ 210M |
| | hidita | | 286c | North Lake Mechant Marsh Creation - East | 1 | \$ 250M |
| | Proper | | 286d | North Lake Mechant Marsh Creation - West | 2 | \$ 230M |
| | | | 337 | Fourleague Bay - Blue Hammock Bayou Marsh Creation | 1 | \$ 370M |
| | | | 339 | West Terrebonne Marsh Creation Project | 1 | \$ 1.5B |
| | Ī | Ridge Restoration | 127 | Bayou Decade Ridge Restoration | 1 | \$ 13M |
| | | | 130 | Mauvais Bois Ridge Restoration | 1 | \$ 13M |
| | | | 340 | Lower Bayou Petit Caillou Ridge Restoration | 1 | \$ 3.3M |
| | \$ | Diversion | 362 | Atchafalaya Diversions | 1 | \$ 790M |
| | i | - | 110b | Morganza to the Gulf | 1 | \$ 3.9B |
| | | Structural Risk | 111 | Larose to Golden Meadow | 2 | \$ 500M |
| | ₩. | Reduction | 144 | Amelia Levee Improvements | 2 | \$ 840M |

| BARATARIA | £. | Integrated Project | 329 | Caminada Bay Marsh Creation and Fifi Island Ridge | 1 | \$ 78M |
|---------------------------------------|----|--------------------|------|--|---|---------|
| BARAIARIA | | Landbridge | 325c | Lower Barataria Landbridge - East | 2 | \$ 840M |
| See page 134 for regional | | | 326b | Mid-Barataria Landbridge - West | 2 | \$ 520M |
| project map and project descriptions. | | Marsh Creation | 090c | Large-Scale Barataria Marsh Creation | 2 | \$ 560M |
| · | | | 267 | North Barataria Bay Marsh Creation | 2 | \$ 220M |
| | | | 330 | East Bayou Lafourche Marsh Creation | 1 | \$ 1.3B |
| | | | 331b | Southeast Golden Meadow Marsh Creation - North & South | 2 | \$ 270M |
| | | | 331c | Southeast Golden Meadow Marsh Creation - Central | 1 | \$ 100M |

ID# PROJECT NAME

334 Bayou L'Ours Ridge Restoration

082 Upper Barataria Risk Reduction

083 Lafitte Ring Levee

Freshwater Delivery to Western Barataria

Upper Basin Diversion Program - Barataria

PROJECT TYPE

Ridge Restoration

Structural Risk Reduction

PONTCHARTRAIN / BRETON

See page 146 for regional project map and project descriptions.

| | Integrated Project | 310 | Three Mile Pass Marsh Creation and Hydrologic Restoration | 2 | \$ 56 |
|-----|------------------------------|------|--|---|-------|
| | | 035 | Hopedale Marsh Creation | 2 | \$ 16 |
| | | 037e | New Orleans East Marsh Creation | 2 | \$ 1. |
| | | 040 | Central Wetlands Marsh Creation | 1 | \$ 49 |
| | | 246 | Sunrise Point Marsh Creation | 1 | \$ 4 |
| | | 247 | Uhlan Bay Marsh Creation | 1 | \$ 33 |
| | | 248c | Pointe a la Hache and Carlisle Marsh Creation | 1 | \$ 86 |
| | | 249 | Fritchie North Marsh Creation | 1 | \$ 11 |
| | Marsh Creation | 250 | Oak River to Delacroix Marsh Creation | 1 | \$ 17 |
| | | 251 | Spanish Lake Marsh Creation | 2 | \$ 6 |
| | | 253 | Tiger Ridge/Maple Knoll Marsh Creation | 1 | \$ 15 |
| | | 313 | West Delacroix Marsh Creation | 1 | \$ 39 |
| | | 314 | Belle Pass Island Marsh Creation | 1 | \$ 9 |
| | | 315 | North and East Lake Lery Marsh Creation Project | 2 | \$ 89 |
| | | 316 | Chandeleur Sound Island Restoration Projects | 2 | \$ 5 |
| . – | Didge Destaution | 054 | Bayou LaLoutre Ridge Restoration | 2 | \$ 2 |
| 1 | Ridge Restoration | 318 | Tchefuncte River Restoration | 1 | \$ 1. |
| _ | Diversion | 014a | Central Wetlands Diversion | 2 | \$ 27 |
| _ | | 361a | Upper Basin Diversion Program - Pontchartrain | 1 | \$ 75 |
| | Structural Risk Reduction | 029 | Lake Pontchartrain Barrier | 1 | \$ 2. |
| | | 032 | Slidell Ring Levees | 1 | \$ 42 |
|) | | 319 | Braithwaite to White Ditch | 1 | \$ 44 |
| | | 320 | St James-Ascension Parishes Storm Surge Protection | 2 | \$ 73 |

Figure 5.2: 2023 Coastal Master Plan Project List.

77

COST

\$ 9.5M

\$ 120M

\$ 750M

\$ 510M


\$ 1.4B

1

2

1

2



Even with full implementation of the 2023 Coastal Master Plan, the future landscape of coastal Louisiana will be different from today. In comparison to a future without the 65 restoration and 12 risk reduction projects, the plan provides a significant amount of land created or maintained into the future that would otherwise be converted to open water. It is expected that under the master plan's lower environmental scenario, the projects in this plan will create and maintain approximately 314 sq mi of land over 50 years, as shown in the map above. Marsh creation projects in the Breton and Barataria basins contribute substantial areas of additional land, especially in the lower Bayou Lafourche corridor between the Larose to Golden Meadow levee system and Port Fourchon.

78

Marsh creation projects in western Terrebonne, on Marsh Island, and near Freshwater Bayou also bolster the land area in the lower estuaries. Landbridges in Barataria and eastern Terrebonne work synergistically with marsh creation projects to maintain land across the mid-basins. This is especially the case in eastern Terrebonne where there is extensive land loss. In the Chenier Plain, loss is reduced where marsh creation and hydrologic restoration projects sustain land that would otherwise be lost.

>>> Go to **Chapter 6: Regional Approach** for more information on regional benefits of the master plan projects.

P 95


YEAR 50 LOWER SCENARIO

Initial 10 20 30 40 50 YEAR

Land Gained
Land Maintained
Land Lost

Map 5.2: Land Change, Future With Action,
Lower Scenario, Year 50.






The master plan uses an environmental scenario approach to project a range of possible outcomes and applies that information to the planning process. When 2023 Coastal Master Plan projects are implemented under the higher scenario, they build or maintain 233 square miles of land over the 50-year period. While significantly more land loss is projected under the higher scenario compared to the lower, the robust suite of projects selected still has large benefits. Due to higher sea level rise and subsidence in this scenario, individual project effects are much clearer in some areas of the coast. The effects of marsh creation projects and marsh creation components of integrated projects are clear in the Lake Borgne area and in the Breton Basin. In

these areas, many of the marsh creation projects perform well until the later years; so, despite land being lost by Year 50 in many areas, the projects yield substantial benefits throughout much of the 50 years. Landbridges in Barataria and eastern Terrebonne provide continuous land through 50 years. Further west, where subsidence rates are lower, marsh creation in the Calcasieu and Sabine basins provide large areas of continuous wetlands south of the Gulf Intracoastal Waterway (GIWW).

>>> Go to **Chapter 6: Regional Approach** for more information on regional benefits of the master plan projects.

P 95




FLOOD DEPTHS


FUTURE WITH ACTION LOWER SCENARIO | YEAR 50

Structural and nonstructural risk reduction measures are expected to reduce flood damage by \$10.7 billion in EADD under the lower environmental scenario and reduce EASD by up to 78% in Year 50 compared to a future without action. Lower scenario projections of flood depths with a 1% AEP are shown to the right. Even with plan implementation, some areas will experience substantial flooding.

Many communities will benefit from structural risk reduction projects, including new levees and improving some existing structures to withstand greater storm surge. To provide risk reduction to coastal communities outside of current and proposed levee systems, \$11.2 billion of the master plan budget is recommended to support nonstructural risk reduction measures, such as elevations, floodproofing, and voluntary acquisition.




>>> Go to Chapter 6: Regional Approach for more information on regional benefits of the master plan projects. P 95



Future With Action, Lower Scenario, Year 50.






FLOOD DEPTHS


FUTURE WITH ACTION HIGHER SCENARIO | YEAR 50

With the higher environmental scenario, storm surge-based flood depths are expected to increase and extend northward, putting additional communities at risk over 50 years. Under the higher scenario structural and nonstructural risk reduction measures are expected to reduce flood damage by \$14.5 billion in EADD and reduce EASD by up to 65% at year 50 compared to a future without action. Higher scenario projections of flood depths with a storm event of 1% AEP are shown to the right. Even with plan implementation, some areas will experience substantial flooding.


If the higher scenario is realized, elevating homes in some areas would lift homes so high that the increased potential for wind damage begins to be an issue; in these instances, voluntary acquisition may become the most viable approach.



>>> Go to Chapter 6: Regional Approach for more information on regional benefits of the master plan projects. P 95



Future With Action, Higher Scenario, Year 50.



BENEFITS OVER TIME

IMPACTS OF THE PLAN

LAND AREA CHANGE

Even with the 2023 Coastal Master Plan fully implemented, coastal Louisiana's landscape is going to look different 50 years into the future. While the coast as we know it today will continue to change into the future, the master plan delivers significant and essential benefits in terms of the land area that is maintained and/or gained. The projects selected help maintain a diversity of ecosystems and bolster key landscape features. Under the lower scenario 314 sq mi of land is built or

maintained that would have otherwise been lost by Year 50. In fact, we project net positive land change for the first 20 years. Under the higher scenario 233 sq mi of land is built or maintained at Year 50 compared to a future without action. We see a maximum benefit of 395 sq mi of additional land at Year 40 under this higher scenario, however the benefits of many of the early projects diminish in the final decade as they can no longer keep pace with subsidence and accelerated rates of sea level rise.




Figure 5.3: Land Area Over 50 Years, Future With and Without Action, Higher and Lower Scenario.




Figure 5.4: Land Area Built or Maintained Over 50 Years, Future With Action, Higher and Lower Scenario.

RISK AND DAMAGES

The plan identifies 12 structural risk reduction projects. By Year 50, these projects will reduce expected annual damage by \$7.7 billion (EADD) under the lower scenarios and \$10.7 billion (EADD) under the higher scenario compared to a future without action. The plan also allocates \$11.2 billion in nonstructural measures which could further reduce expected annual damage by \$3.0 billion (EADD) and \$3.8 billion (EADD) under the lower and higher scenarios, respectively.

Fully implementing the plan could reduce EADD by up to 70% under the lower scenario and 60% under the higher scenario compared to a future without action. The risk reduction, as measured in EASD, shows similar effects reducing coastwide risk by up to 78% under the lower scenario and 65% under the higher scenario. This level of investment could mean that at Year 50, under the lower environmental scenario, Louisiana has less flood risk from hurricanes and tropical storms than we do today.



Figure 5.5: Amount of Total Annual Expected Damages in Dollars (left) and Structure Equivalents (right),

Future With and Without Action, Higher and Lower Scenario.

FUNDING & IMPLEMENTATION

The master plan identifies projects that can most effectively protect and restore coastal Louisiana over the next 50 years. Moving projects from concept to implementation requires extensive coordination between CPRA, state and federal agencies, local governments, NGOs and stakeholders. These entities, along with elected officials, play an important role in identifying and marshaling the funding necessary to implement the 2023 Coastal Master Plan.

In addition to the master plan, CPRA prepares an annual plan which identifies available funding for a 3-year period and the programs and projects this funding will support. The annual plan is used to track the progress of CPRA projects in different phases of implementation. The implementation plan and funding projections represent a snapshot in time based on available funding sources. The state actively explores new sources of funding to ensure that the coastal program maintains its momentum.

Louisiana will continue to use funding associated with the Deepwater Horizon Oil Spill settlement, including funds administered under the:

- Resources and Ecosystems Sustainability, Tourist Opportunities, and RESTORE Act,
- National Fish and Wildlife Foundation (NFWF), and
- Oil Pollution Act Natural Resource Damage Assessment (NRDA).

Other important sources of funding include the:

- Gulf of Mexico Energy and Security Act (GOMESA),
- Water Resource Development Act (WRDA),
- Coastal Protection & Restoration (CPR) Trust Fund,
- CWPPRA,
- State Capital Outlay funds,
- disaster-based funding, and
- grants to support implementation.

investment in coastal Louisiana that will benefit residents across the coast as \$2.6 billion in funding was allocated to Louisiana to support hurricane risk reduction projects. Through the Extending Government Funding and Delivering Emergency Assistance Act (Supplemental Disaster Relief) and the Infrastructure Investment and Jobs Act (IIJA), USACE dedicated funding to several of CPRA's projects.

Congress provided more than \$2 billion for coastal and other flood risk reduction projects in Louisiana to USACE, including the following:

- \$783 million for New Orleans to Venice Hurricane Protection
- \$453 million for West Shore Lake Pontchartrain
- \$163 million for Atchafalaya Basin
- \$128 million for Comite River Diversion
- \$94.3 million for Southeast Louisiana
- \$8 million for Upper Barataria Basin
- \$3.8 million for Grand Isle and Vicinity
- \$3.5 million for Bayou Segnette Waterway
- \$3 million for Tangipahoa Parish

Congress provided more than \$643 million in IIJA funding to USACE for 21 coastal and water management projects, including the following:

- \$379 million for Morganza to the Gulf
- \$125 million for Southwest Coastal
- \$52.9 million for Atchafalaya Basin
- \$23.2 million for the Gulf Intracoastal Waterway

DEEPWATER HORIZON RELATED FUNDING SOURCES

The RESTORE Act, signed into law on July 6, 2012, created the Gulf Coast Ecosystem Restoration Council (RESTORE Council). The Council's Gulf Coast Restoration Trust Fund (RESTORE Trust Fund) receives 80% of the Deepwater Horizon Oil Spill Clean Water Act civil penalties for purposes of restoring the long-term health of the natural ecosystems and economy of the Gulf Coast region. These funds are distributed over 15 years, ending on April 4, 2031. Louisiana's share will total more than \$841 million, including \$29 million for the Louisiana RESTORE Act Center of Excellence.

Under its approved RESTORE Plan, the state committed to funding two projects (Calcasieu-Sabine Large-Scale Marsh and Hydrologic Restoration project and the Houma Navigation Canal Lock Complex) and two programs (Adaptive Management Program and Parish Matching Fund Program) for a total of approximately \$811.9 million, including contingency funds of approximately \$26.4 million.

CPRA also has the opportunity to submit projects for funding under the Council-Selected Restoration Component. To date, funding has been received to support work on five projects totaling \$182 million.

The NFWF Gulf Environmental Benefit Fund (GEBF) was established in early 2013 as an outcome of plea agreements for the Deepwater Horizon Oil Spill. Over five years, \$2.54 billion was directed to NFWF to support projects that remedy harm to natural resources that were affected by the spill. In Louisiana, the funds must be allocated solely to barrier island restoration projects and river diversion projects along the Mississippi and Atchafalaya Rivers. From 2013 through 2018, GEBF received \$1.27 billion for project expenditures in Louisiana. To date, NFWF has awarded more than \$465 million from GEBF for 12 projects in Louisiana.

Master Plan Consistency: Given the emergency facing coastal Louisiana, it is imperative that all government agencies act quickly and in accordance with the master plan. Governor Edwards' Executive Order No. JBE 2016-09 highlights the need for the plan to drive and expedite state action across agencies. The same need applies to the state's partners at the local and federal levels, consistent with their mandates and missions. While the master plan provides the blueprint for restoration and planning activities in coastal Louisiana, a coalition of support from the nation will be required if we are to create a more sustainable and resilient coastal Louisiana.

NRDA will provide \$5 billion in settlement funds used for Deepwater Horizon Oil Spill restoration activities. This funding stream is overseen by the Louisiana Trustee Implementation Group (LA TIG), who approves restoration and implementation plans that utilize these funds. These funds are distributed annually over 15 years, ending on April 4, 2031.

FUNDING SOURCES NOT RELATED TO DEEPWATER HORIZON

In 2022, CPRA, parishes and NGOs have received more than \$30 million in competitive grant awards for ecosystem restoration projects in Louisiana funded through the Disaster Relief Supplemental Act (DRSA) and IIJA.

GOMESA allows for federal revenues derived from offshore energy production to be shared with the Land and Water Conservation Fund, the four Gulf producing states, and their coastal political subdivisions. In Louisiana, funds have been constitutionally dedicated to the CPR Trust Fund and

TAKE ACTION

are used primarily to fund hurricane risk reduction projects. The state receives its GOMESA payment each spring based on revenues generated during the prior federal fiscal year.

Louisiana's CPR Trust Fund is largely supported by mineral revenues and severance taxes on energy production on state lands. The CPR Trust Fund provides funding for the coastal program's ongoing operating expenses and for continued efforts in coastal restoration and risk reduction.

WRDA 2016 authorized the Southwest Coastal Louisiana project to provide nonstructural risk reduction to communities in this region and subsequent WRDAs have also funded feasibility and planning for several flood risk reduction projects that could lead to further federal funding.

CWPPRA was originally authorized in 1990 and has since been reauthorized several times. Through the CWPPRA Program, CPRA works with five federal agencies — U.S. Environmental Protection Agency, NOAA National Marine Fisheries Service, National Resources Conservation Service (NRCS), U.S. Fish and Wildlife Service (FWS), and USACE — to develop coastal wetlands restoration projects.

Capital Outlay generated by the Louisiana Legislature grants cash and non-cash lines of credit for state and non-state projects. CPRA anticipates receiving \$10 million per year over the next three years in Capital Outlay funding to supplement implementation of 12 projects.

Future disaster-based funding will be applied toward efforts, such as nonstructural mitigation, that remediate damage from the precipitating event. CPRA will coordinate closely with other agencies to direct applicable future disaster funds toward implementation of nonstructural solutions identified in the 2023 Coastal Master Plan.

Grants from businesses, industry, large corporations, and national philanthropic organizations are also a potential future funding source for projects.

IMPLEMENTING NONSTRUCTURAL RISK REDUCTION PROJECTS

Nonstructural risk reduction projects are unique in the master plan process in that they are typically smaller scaled projects – from floodproofing individual businesses to elevating multiple homes along a single road or even the voluntary acquisition of several residential properties in a neighborhood or community with particularly high flood risk. The nature of these projects, which require active participation of individuals and communities, means that pre-selecting a location for a particular project is exceedingly difficult. In practice, many individuals and communities have undertaken these mitigation measures following a storm event where their homes were damaged. Ideally, nonstructural risk reduction strategies should be implemented proactively, before damage occurs.

Additionally, because nonstructural projects are effective against many types of flooding (such as heavy rainfall and high tide flooding events) and not just the storm surge-based flooding that is considered in the master plan, they could potentially be funded by sources that do not typically provide funding for coastal projects. Nonstructural projects are also unique in that CPRA has not traditionally been involved in the implementation of these project types. One exception is the USACE Southwest Coastal Louisiana project. In October 2022, the project secured \$296 million, mostly from the IIJA. To date, more than 3,900 structures have been preliminarily identified as eligible for either elevation or floodproofing measures. USACE is currently working with CPRA to execute a Project Partnership Agreement before proceeding to elevate homes that have been cleared for construction.

State agencies, such as the Office of Community
Development (OCD) and the Governor's Office of
Homeland Security and Preparedness (GOHSEP), are
experienced in working with federal partners, such as the
Department of Housing and Urban Development (HUD)
and FEMA, to marshal funding and manage nonstructural
project implementation. These agencies also have a role
in the disbursement of federal funds made available for
recovery following hurricanes and other natural disasters.



Image: Elevated Home in Montegut, 2023 (CPRA)

Coastal communities are expected to face continuing sea level rise and subsidence into the future and rising water levels will continue to impact residents' way of life. Even if a community does not experience storm surge-based flooding, changing environmental conditions are expected to result in a number of challenges with roads flooding more frequently, rain draining more slowly, and events where a south wind can result in the closure of structures originally designed to prevent flooding from storm surge. As residents consider these and other challenges, some communities may consider moving inland. This is called managed retreat and is the proactive movement of people, structures, and infrastructure out of harm's way before conditions become unlivable. Managed retreat helps communities move away from vulnerable coastal areas and facilitates their transition inland. It involves more than just acquisition of homes and people moving away from harm – it ensures that the community has somewhere to move to, where there are housing, schools, jobs and community facilities.

Managed retreat is an inherently complex and challenging adaptation option for state and local governments and decisions to undertake these efforts need to be made by community members and their local elected officials. There are planning, legal, and financial considerations. Decisionmakers need to ensure that the people most affected are included in the design and implementation of the approach and that the outcomes are equitable for the communities involved. CPRA can support communities considering managed retreat by partnering with them, state agencies, and NGO's to provide data and projections that can help to inform decision-making. Despite the unique realities of implementing nonstructural risk reduction projects, they are considered an integral part of the 2023 Coastal Master Plan. \$11.2 billion of the \$25 billion risk reduction budget in the plan is proposed to pursue nonstructural measures across both implementation periods, reflecting their near- and long-term effectiveness.

>>> Go to **Chapter 4: Evaluate** for more information on nonstructural risk reduction project types recommended for different flood depths.

P 56

BY THE NUMBERS

THE IMPACT OF THE 2023 COASTAL MASTER PLAN



FREQUENTLY ASKED QUESTIONS

What if we don't have the funding to build all the projects in the master plan? The master plan is developed to provide a list that has more projects than the state currently has funding to implement. Funding for restoration and risk reduction projects comes from various sources and is often required to be used for certain project types or to meet particular goals. Because of this, the plan identifies a variety of worthy projects in anticipation of future funding opportunities. Additionally, the master plan is not an all-or-nothing undertaking. Each project is evaluated and selected based on its individual benefits before being modeled as part of the full master plan. This means that all investments toward project implementation, no matter the number or location, will provide benefits in terms of reducing land loss and/or flood risk.

Why is there still damage from storms if so much is spent on risk reduction projects? The project selection for risk reduction projects was based on maximizing the amount of flood risk reduction that could be attained across a wide range of storm surge events in coastal Louisiana. The structural risk reduction projects are designed to provide protection up to a given design event, often the 1% AEP flood depths. However, some storms and extreme events produce greater flood depths than these design elevations, possibly resulting in overtopping of levees and floodwalls. This means there will be some residual risk of damage from large events. It is simply not possible to protect every community from every possible eventuality.

What about areas where no 2023 Coastal Master Plan projects have been selected? It is important to remember that the master plan is part of a much broader coastal program for Louisiana and that restoration and risk reduction efforts have been underway for decades. As the fourth edition of the master plan, the projects selected are in addition to projects already funded and/or implemented and, therefore, included in our baseline FWOA landscape. Areas without selected projects may already have solutions in place or may be less vulnerable to coastal change than those with projects in this plan.

If I live in area where flood depths are high, will I be forced to move? The state will not force anyone to move. But we may offer support to help you elevate your home or move out of a vulnerable area – the 2023 Coastal Master Plan proposes billions of dollars for these types of activities. Many federal programs provide funds for elevation and voluntary acquisition, and most are managed by Parish governments. Properties are usually evaluated on a house by house basis, but some apply only where the whole neighborhood agrees to move. If you might be interested in moving out of an area that may be subject to severe flooding in the future, you are encouraged to contact your Parish government.

>>> HAVE MORE QUESTIONS?

Visit us online at <u>coastal.la.gov</u> or contact us directly at <u>masterplan@la.gov</u>.

2023 COASTAL MASTER PLAN







Coastal Louisiana is home to a wide variety of landscapes and communities that influence the social, economic, and ecological character of the local area. Recognizing this, the 2023 Coastal Master Plan has identified five regions across the coast – Chenier Plain, Central Coast, Terrebonne Basin, Barataria Basin, and Pontchartrain/Breton Basin – that will experience climate and environmental change in distinct ways.


Throughout the master plan development process CPRA has met with residents and convened Regional Workgroups to discuss issues, priorities, and possible solutions for

Through a better understanding of the unique concerns of each region, the 2023 Coastal Master Plan developed tailored approaches to address issues of future land loss and storm surgebased flood risk. The result is a master plan that better reflects the experiences of coastal residents and that supports those that live, work, and play in coastal Louisiana, today and into the future.



Map 6.1: The Five Regions of the Louisiana Coast.





ABOUT THE CHENIER PLAIN

AN INTRODUCTION

Dotted with lakes and marshes, the Chenier Plain is a place where fishing and hunting enthusiasts thrive. The region is also a vital contributor to Louisiana's working coast. The Chenier Plain has suffered greatly from hurricane impacts over the last two decades. Today, many residents in the region are still struggling to recover. The 2023 Coastal Master Plan proposes a number of projects to restore habitats and support the region's continued productivity and economic vitality.

Residents and visitors to the Chenier Plain enjoy the beauty and productivity of the region's vast lake and marsh ecosystems. This area includes the White Lake Wetlands Conservation Area; the Rockefeller Wildlife Refuge; and the Lacassine, Cameron Prairie, and Sabine National Wildlife Refuges and is one of North America's most important waterfowl habitats.

As a vital contributor to Louisiana's working coast, commercial and residential development is centered in the Lake Charles-Sulphur area. The primary economic base of the region includes the chemical and refining industries and oil and liquefied natural gas (LNG) production. Hackberry, south of Lake Charles, is home to a storage site for the Strategic Petroleum Reserve, a system of underground salt




230K residents at risk from storm surge-based flooding

100



35% of Louisiana's total rice and crawfish acreage



The Chenier Plain has suffered greatly from the impacts of hurricanes over the last two decades. In 2005, Hurricane Rita made landfall in Johnson Bayou with an 18 ft storm surge that flooded or destroyed most of the structures in Cameron, Holly Beach, Hackberry, Creole, Johnson Bayou, Grand Chenier, and Pecan Island. Three years later, Hurricane Ike brought a 22 ft storm surge that flooded many of these same communities. In August 2020, Hurricane Laura brought catastrophic flooding to many parts of Cameron Parish, including flood depths greater than 12 ft around the communities of Creole and Grand Chenier, and devastating winds throughout the Chenier Plain, including Lake Charles. Recovery efforts were delayed and damages were experienced again by Hurricane Delta that arrived just a month later. Today, many residents in the region are still struggling to recover. These recent hurricanes have brought renewed interest in structural risk reduction measures for the Chenier Plain. CPRA will help local



220.4M barrels of oil stored as part of Strategic Petroleum Reserve



6M overwintering waterfowl



Image: Harvesting crawfish (Burt Tietje)

entities develop and evaluate structural measures using the tools developed for the master plan. In the near-term, communities and residents should take advantage of nonstructural and disaster recovery programs to mitigate and rebuild in resilient ways.

The Southwest Coastal Louisiana Study is the first federally authorized feasibility-level study with the dual purpose of addressing hurricane and storm damage risk reduction and restoring the coastal ecosystem. The project was authorized by Congress in 2016 and \$296 million was appropriated through the 2022 IIJA. More information about Southwest Coastal can be found in Chapter 7.

The 2023 Coastal Master Plan proposes a number of marsh creation and hydrologic restoration projects for the region. The Chenier Plain's hydrology is highly managed with numerous major water control structures like locks and flap-gated culverts, as well as countless smaller ditches, culverts, and plugs. The master plan evaluated and selected

large-scale hydrologic restoration projects to improve drainage at the basin scale. At a more local scale, cleaning ditches and drainage canals or installing culverts can have a significant impact on wetland productivity. These types of local solutions often rely on the expertise of landowners, land managers, and local coastal zone managers and are considered programmatically consistent with the master plan. More information about programmatic project types can be found in Chapter 4.

To address enormous challenges facing southwest Louisiana, the Cameron Parish Police Jury (CPPJ) and the Chenier Plain Coastal Restoration and Protection Authority (CPCRPA) have both developed local coastal plans. These plans were the source of many project concepts selected for the 2023 Coastal Master Plan and they contain objectives, values, and a vision that align with the master plan. CPRA supports the efforts of the CPPJ and CPCRPA to plan for the future of the coast and will continue to partner closely with them for the betterment of the region.

REGIONAL APPROACH

HIGH TIDE FLOODING (HTF) IN CAMERON PARISH

In addition to storm surge-based flood risk, Louisiana's coastal communities often contend with localized flooding, also known as high tide flooding which can impede day-to-day travel and activity as well as emergency services. The lowlying areas in and around Cameron can expect to experience increased frequency and severity of this localized flooding over the next 50 years, as shown below. Cameron Parish's population mostly lives atop remnant chenier ridges. Forced drainage, i.e., low levees with small pumps, is already used to remove rainfall-runoff from most of this area. Expected sea level rise will impede gravity drainage while exacerbating the frequency and extent of high tide flooding events. Currently, areas near the Cameron Ferry West Landing, the low point on the Highway 27 hurricane evacuation route, almost never experience high tide flooding. In 50 years, under the Lower Environmental Scenario, these areas may experience high tide flood events on more than half of the days in a year.

| | YEAR 1 | YEAR 25 | YEAR 50 |
|---------------------------|--------|---------|---------|
| Ferry West Landing | <5% | 12% | 62% |
| Cameron Evacuation | <5% | <5% | 52% |

Link, LA-27 Low Point

Figure 6.2: Percentage of days that may see HTF at key locations in the Town of Cameron, Lower Environmental Scenario.


For more information see Attachment H3.



Image: Town of Cameron, Louisiana
(Louisiana Sea Grant College Program)



Image: Crabbing at Rockefeller Wildlife Refuge (Louisiana Sea Grant College Program)



 $Figure\ 6.3: Representative\ High\ Tide\ Flooding\ (HTF)\ Elevations\ for\ the\ Town\ of\ Cameron\ at\ Year\ 1\ and\ 50\ in\ the\ Lower\ Scenario.$



Map 6.2: Existing Hydraulic Control Structures Identified throughout the Chenier Plain.



Image: Cameron-Creole Hydrologic Control Structure, 2022 (CPRA)

DRAINAGE CONCERNS

Over the last century, the hydrology of the Chenier Plain has been altered dramatically through a combination of navigation channels, canals, drainage, and water control features. Major historic changes include dredging the Calcasieu and Sabine-Neches Ship Channels and the GIWW along the northern portion of the region that connects the ship channels. Smaller, more localized changes to oilfield canals, construction of salinity and water-level control structures and levees, and impoundment of large areas of the marsh for wildlife management have also impacted the area's hydrology. At the current sea level, opportunities for drainage from the managed marsh ecosystem into coastal lakes are already highly limited — all but the tidally connected marshes are flooded too deeply and for too long to continue to support healthy marsh vegetation. With continued sea level rise in the future, drainage is expected to become more challenging in the region. The hydrologic restoration projects selected for this region in the 2023 Coastal Master Plan address flooding and drainage while maintaining salinity control. More information about these issues can be found in McGinnis, T. et al., 2019. 2019 Basin Summary Report for the Calcasieu-Sabine Basin. CPRA.

CHENIER PLAIN PROJECTS

REGIONAL 2023 PROJECTS MAP

For the 2023 Coastal Master Plan, 16 projects were selected in the Chenier Plain region, including several marsh creation projects spread across the region. Through the help of the Chenier Plain Regional Workgroup, the locations of these marsh creation projects were chosen to address current and future land loss concerns, such as


strengthening the shoreline of Calcasieu Lake and other important regional water bodies. Large-scale hydrologic restoration projects were also selected for the region. These projects were designed, with input from our advisory groups, to provide improved drainage in both the upper Mermentau Basin and the Cameron-Creole Watershed.

>>> Opportunities for structural risk reduction measures vary across the coast, yet all regions face storm surge-based flood risk. For the 2023 Coastal Master Plan, \$11B has been allocated to nonstructural risk reduction strategies, including in the Chenier Plain region. For more information on nonstructural risk reduction projects, see **Chapter 5: Take Action**.

P 90



Map 6.3: Chenier Plain 2023 Coastal Master Plan Projects.






Figure 6.4: Chenier Plain Project List.



Image: Cameron Meadows Restoration Project, 2020 (CPRA)

HYDROLOGIC RESTORATION PROJECTS

The Chenier Plain Regional Workgroup proposed several candidate projects to address persistent marsh flooding and lack of drainage. The Mermentau Basin Hydrologic Restoration and Cameron-Creole to the Gulf Hydrologic Restoration projects were selected for inclusion in IP1 of the 2023 Coastal Master Plan.


The Mermentau project moves water, by way of gravity drainage, southward across Highway 82 into the tidally connected canals throughout the Rockefeller National Wildlife Refuge, and the Cameron-Creole project reduces water levels by maintaining constant (via downstream pumps) mean low tide levels in the Creole Canal, allowing the Cameron-Creole system to efficiently gravity drain to the canal at all times. Combined, these projects relieve pressure on the Mermentau River allowing for more efficient drainage through existing waterways. This results in reduced water levels throughout the southern Mermentau and Cameron-Creole watersheds and healthier, more sustainable marshes in this area, as compared to FWOA.

These two hydrologic restoration projects will work in conjunction with the Calcasieu-Sabine Large-Scale Marsh and Hydrologic Restoration project currently being engineered and designed by CPRA to alleviate chronic inundation of marsh areas to the east of Calcasieu Lake.

REDUCING RISK

The areas of the Chenier Plain most exposed to storm surge are also the most rural, which leaves few cost-effective options for structural protection. Elevating homes and floodproofing businesses have been the standard for building in low-lying coastal communities for decades, yet there is still need and opportunity. CPRA is working with USACE to implement these critical projects through the Southwest Coastal project.

Restoring and maintaining the wetlands and ridges between the Gulf and the more populated areas has been a key concern from some communities further north. The restoration projects proposed in the master plan are projected to reduce EADD in Lake Charles by approximately 19% at Year 50.



Map 6.4: Chenier Plain, Land Change, Future With Action, Lower Scenario, Year 50.

REGIONAL PROJECT BENEFITS

With action, we build and maintain 23,000 acres of land in the lower environmental scenario and 35,000 acres in the higher scenario. Restoration in the region is focused on large-scale marsh creation and ensuring adequate drainage of wetlands in the Mermentau Basin. In the lower environmental scenario, the projects are successful in maintaining much of the land area and extensive intermediate marshes. Under the higher scenario, there is extensive land loss in the Mermentau Basin after 50 years and some increase in salinity, but the restoration projects are successful in maintaining extensive marsh both east and west of Calcasieu Lake. The hydrologic restoration projects and existing management projects help maintain intermediate marsh, although there is an increase in conversion to salt marsh in the last decade.

There were no structural risk reduction projects proposed in the Chenier Plain. The selected restoration projects do have an impact in attenuating storm surge and reducing risk. With the restoration projects on the landscape, the models show a reduction in risk. There is, of course, significant residual risk across the Chenier Plain, which illustrates the need for nonstructural risk reduction projects.




Figure 6.5: Chenier Plain Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario.

20

30

40

50

YEAR



ABOUT THE CENTRAL COAST

AN INTRODUCTION

Sometimes called "The Most Cajun Place on Earth," the Central Coast region is home to some of Louisiana's most iconic communities, cultures, and traditions. The landscape of the Central Coast supports bountiful agriculture and seafood industries, as well as one of the only land-building areas along the coast. The 2023 Coastal Master Plan proposes a number of projects to restore ecosystem function and reduce storm surge-based flood risk to communities within the Central Coast region.

Extending from Freshwater Bayou to Fourleague Bay, the Central Coast of Louisiana is the "Gateway to the Atchafalaya Basin." It ranges inland to the lower reaches of the Atchafalaya Floodway, and encompasses communities along Bayou Teche, the outskirts of Lafayette, and agricultural land west of Abbeville. It includes parts of Iberia, Lafayette, St. Martin, St. Mary, and Vermilion parishes.

Sometimes called "The Most Cajun Place on Earth," the people and places of the Central Coast are a key component of the state's rich cultural heritage The Central Coast is also home to the Chitimacha Tribe of Louisiana, which maintains a reservation adjacent to Charenton in St. Mary Parish. The



130K residents at risk from storm surge-based flooding



36% of Louisiana's sugarcane production

Chitimacha Tribe is the only tribe in Louisiana to still occupy a portion of their original homeland, which once encompassed the entire Atchafalaya Basin, lands westward toward Lafayette, southward to the Gulf, and eastward to the New Orleans area.

The landscape of the Central Coast is shaped by the Atchafalaya River, which branches off the Mississippi River and carries up to 30% of its flow below the Old River Control Structure. Because of the proximity to the Gulf and the influence of the Atchafalaya River, the ecosystems in this region are diverse, from freshwater swamps to saline marshes. The region includes the Atchafalaya Delta Wildlife Management Area, the Marsh Island and Rainey State Wildlife Refuges, the Bayou Teche National Wildlife Refuge, and the National Audubon Society's 26,000 acre Paul J Rainey Wildlife Sanctuary. The Central Coast is one area of the state that is building land through active growth of the Atchafalaya River and the Wax Lake deltas, supporting a growing research economy around the study of natural and constructed river diversions.

The Central Coast region is widely recognized for its fresh seafood, bountiful agriculture, and beautiful and useful waterways. Important ports include the Port of Morgan City, Port of Iberia, and the Port of West St. Mary, which utilize local waterways and



Includes Atchafalaya and Wax Lake deltas



Gateway to the Atchafalaya Basin



Image: Sugarcane production in coastal Louisiana (Lindsey Janies)

their proximity to the GIWW and the Gulf. Intracoastal City is a hub for the local shrimp and pogie fleets on the GIWW near Vermilion Bay, and consistently ranks among the top six seafood ports in the country. Vermilion, Iberia, Lafayette, and St. Mary parishes among the top producing parishes for sugarcane in the state. Four of Louisiana's 11 operating raw sugar factories are located in the region in communities along Bayou Teche. Vermilion is also historically among the top producing parishes for rice. The region also boasts a thriving cultural and ecotourism industry, welcoming visitors drawing to the area's unique landscape and rich cultural heritage.

Despite these assets, the Central Coast faces challenges. The region's agriculture is, in many areas, impacted by subsidence and sea level rise, which make draining agricultural impoundments more difficult. This is expected to be more of a challenge with accelerating rates of sea level rise in the future. The region has also been impacted by numerous storm events in recent decades, including Hurricanes Laura and Delta (2020),

Barry (2019), Lee (2011), Ike (2008), Gustav (2008), Rita (2005), Lili (2002), Bertha (2002), Allison (2001), and Andrew (1992). These storms resulted in economic damages, loss of property, loss of life, and repeated mandatory evacuation costs. The 2023 Coastal Master Plan proposes a number of projects to restore ecosystem function and reduce storm surge-based flood risk to communities within the Central Coast region.

>>> The Atchafalaya Basin is the largest contiguous bottomland hardwood forest in North America and is the largest overflow alluvial hardwood swamp in the United States. The Atchafalaya River Delta is an area of active coastal land building and serves as a living laboratory where monitoring and research activities inform how conservation and restoration can be successfully implemented throughout coastal Louisiana. For more information on CPRA's Atchafalaya Basin Program see Chapter 7.

P 166

113

REGIONAL APPROACH

HIGH TIDE FLOODING (HTF) IN DELCAMBRE

In addition to storm surge-based flood risk, Louisiana's coastal communities often contend with localized flooding, also known as high tide flooding which can impede day-to-day travel and activity as well as emergency services. The low-lying areas around Delcambre, especially those in unprotected areas, can expect to experience increased frequency and severity of this localized flooding over the next 50 years, as shown below. Although elevations and levee heights vary in the area, the average road elevation in the Delcambre area is only about half a foot above sea level. Some low-lying areas of Delcambre, especially along Delcambre Canal, are predicted to experience high tide flooding effects on more than 90% of days in 50 years, under the Lower Environmental Scenario.

| | YEAR 1 | YEAR 25 | YEAR 50 |
|---------------------------|--------|---------|---------|
| Bayou Carlin Cove | <5% | <5% | 23% |
| E Main St and S President | <5% | 26% | 93% |

St Low Area


Figure 6.7: Percentage of days that may see HTF at key locations in Delcambre, Lower Environmental Scenario. For more information see Attachment H3.




Image: Delcambre Shrimp Festival (Louisiana Sea Grant College Program)



Figure 6.8: Representative HTF Elevations for Delcambre at Year 1 and 50 in the Lower Scenario.





Map 6.6: Hypothetical Hurricane Rita Impacts on Initial Conditions Landscape, Lower Scenario.

1 to <4 feet 10 to <13 feet 13 to <16 feet 7 to <10 feet 16 to <21 feet

MILES

Map 6.7: Hypothetical Hurricane Rita Impacts on a Future Landscape, Future Without Action, Lower Scenario, Year 50.

HURRICANE RITA

Hurricane Rita made landfall near the Louisiana/ Texas border on September 24, 2005, less than one month after Hurricane Katrina. Hurricane Rita brought with it up to 15 ft of storm surge throughout southwest Louisiana, and severely damaged several coastal communities and tens of thousands of acres of coastal wetlands.

Storm surge in the Central Coast was measured at about 12 ft with much of Vermilion, Iberia, and St. Mary parishes south of Highway 14 and U.S. 90 inundated. We predict that at Year 50, without further restoration and protection efforts, an additional 2-5 ft of storm surge and nearly three times as much economic damage (in 2020 dollars) would be experienced in the communities of Franklin and Delcambre and surrounding agricultural areas south of Highway 14 and U.S. 90 for a storm similar to Hurricane Rita.




Image: Hurricane Damage (CPRA)



| | ID# | PROJECT NAME | DESCRIPTION | IP | COST |
|--|------|--|--|----|---------|
| | 157c | East Rainey Marsh Creation | Creation of marsh in the northern portion of marsh in the eastern portion of Rainey Marsh to create new wetland habitat, restore degraded marsh, and reduce wave erosion. | 1 | \$ 350M |
| | 213 | West Rainey Marsh Creation | Creation of marsh within a footprint of approximately 10,000 acres at Rainey Marsh near the southeast bank of the Freshwater Bayou Canal to create new wetland habitat, restore degraded marsh, and reduce wave erosion. | 1 | \$ 400M |
| | 344b | Central Coast Marsh Creation - Point Au Fer | Creation of marsh within a footprint of approximately 8,200 acres on Point Au Fer Island to create new wetland habitat, restore degraded marsh, and reduce wave erosion. | 1 | \$ 270M |
| | 346 | Marsh Island Barrier Marsh Creation | Creation of marsh within a footprint of approximately 16,000 acres on Marsh Island to create new wetland habitat, restore degraded marsh, and reduce wave erosion. | 1 | \$ 710M |
| | 231 | Cheniere au Tigre Ridge Restoration | Restoration of approximately 78,000 feet of Bill and Cheniere au Tigre Ridges to an elevation of 5 feet NAVD88 to provide coastal upland habitat, restore natural hydrology, and provide wave and storm surge attenuation. | 1 | \$ 26M |
| | 148 | Franklin and Vicinity | Improvements of a levee to an elevation between 12 and 18 feet NAVD88 from the Wax Lake Outlet to the Charenton Canal as well as the Bayou Sale polder. Project features approximately 210,000 feet of earthen levee, approximately 4,800 feet of T-wall, a 30-foot roller gate and two sluice gates. | 2 | \$ 310M |
| | 150 | Iberia/St. Mary Upland Levee | Construction of a levee to an elevation between 15.5 to 20 feet NAVD88 in Iberia and St. Mary parishes between the Delcambre Canal and the Charenton Canal. Project features approximately 150,000 feet of earthen levee, approximately 15,000 feet of T-wall, five 30-foot barge gates, three 110-foot barge gates, four 40-foot roller gates, 27 sluice gates and seven pump stations. | 1 | \$ 1.7B |
| | 292 | Abbeville and Vicinity | Construction of a levee to an elevation between 15.5 and 20 feet NAVD88 in the area south of Delcambre, Erath, and Abbeville roughly following Highway 330. Project features approximately 100,000 feet of earthen levee, approximately 2,800 feet of T-wall, two 56-foot barge gates, two 20-foot stop log gates, two 30-foot stop log gates, and a sluice gate. | 2 | \$ 610M |
| | | | | | |


Figure 6.9: Central Coast Project List.


IBERIA/ST. MARY UPLAND LEVEE

This project was selected in IP1 of the 2023 Coastal Master Plan and provides storm surge-based risk reduction for the community of New Iberia as well as areas further south, such as Jeanerette, Lydia, and the Port of Iberia. Much of the risk reduction provided by this project is realized in the later years of our model projections as sea level rise, subsidence, and continued land loss over the 50-year period are expected to lead to increased flood risk in areas north of U.S. 90, especially in New Iberia. A similar levee project was among several evaluated in USACE's South Central Coast Louisiana Study, which ultimately selected targeted nonstructural projects as the preferred alternative. CPRA will partner with USACE to implement the nonstructural risk reduction measures identified, as it is the most practical path to help these communities adapt to flood risk in the near-term.

MARSH CREATION PROJECTS

Starting in 2018, CPRA established Regional Workgroups to consider regional issues and to help develop new project concepts and refine past project ideas. Regional Workgroup members were asked to consider how to restore lost areas, take into account projections of land change and hydrologic conditions, and identify the key landscape features to maintain and protect. Workgroup members continually emphasized the importance of maintaining Marsh Island and Point au Fer as barriers between the Gulf and the region's population centers, recommending that we refine past master plan projects in the area to focus on east-west alignments. Both projects were evaluated and ultimately selected for the plan.






Map 6.9: Central Coast, Land Change, Future With Action, Lower Scenario, Year 50.

REGIONAL PROJECT BENEFITS

With action, we build and maintain 29,000 acres of land in the lower environmental scenario and 1,400 acres in the higher scenario. Restoration is focused on maintaining a 'barrier' of marsh between the open bays and the Gulf with marsh creation east of Freshwater Bayou, on Marsh Island, and on Point au Fer. These projects are successful over the next 50 years under the lower environmental scenario but some land loss occurs on Marsh Island and to the north of East Cote Blanche Bay. There is also some land gain in the Atchafalaya and Wax Lake deltas over the first three decades. The marsh creation 'barrier' is also successful in the higher environmental scenario, but the marshes degrade by year 50 and land loss increases markedly in the last decade. Freshwater flows from the Atchafalaya River keep the eastern part of the region fresh, while to the west there is dramatic decrease in intermediate marsh in the last two decades.

Three structural risk reduction projects were selected in the Central Coast region that together span from Abbeville to the Wax Lake Outlet Channel. These projects are predicted to reduce future surge-based flood risk in the region by 65%. These projects provide between \$1 - \$1.6 billion reduction in EADD at Year 50. Over half of that risk reduction is seen in the communities of Abbeville, Franklin, and New Iberia, which are projected to see dramatic increases in surge-based flood risk over the next 50 years without these projects.






Figure 6.10: Central Coast Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario.



ABOUT TERREBONNE

AN INTRODUCTION

The Terrebonne region is known for its meandering bayous, blackwater swamps, and extensive marshes. This watery landscape supports some of the most productive commercial fisheries in the state. The region's relationship to water also poses challenges for residents, many of whom live outside of levee protection systems. The 2023 Coastal Master Plan proposes a variety of project types to reduce risk for these vulnerable communities.

The Terrebonne Region extends from Bayou Lafourche in the east to the Atchafalaya Basin floodway, Fourleague Bay, and Oyster Bayou on the west. The region includes parts of seven parishes: Assumption, Ascension, Iberville, Lafourche, St. Martin, St. Mary, and Terrebonne. The area is often described as being "defined by water." Most communities are on higher land adjacent to natural bayous, such as Bayou Blue and Bayou Black, although thousands live in communities outside of levee protection systems.

The region is home to several groups of Indigenous peoples, including members of the Chitimacha Tribe. The Grand Caillou/Dulac Band of Biloxi-Chitimacha-Choctaw tribal peoples have been living in their ancestral traditional village of Grand Caillou/Dulac



200K residents at risk from storm surge-based flooding



Home of 26% of state's commercial shrimpers

for centuries, living by trapping, fishing, hunting, and farming. Their ancestors were primarily of the historic Biloxi, Chitimacha, and Choctaw but also Atakapas and Acolapissa Tribes. To the east, the Pointe-au-Chien Indian Tribal Community is located in lower Pointeaux-Chênes, a traditional village of their ancestors, the Chitimacha. The Pointe-au-Chien Indians also descend from the Biloxi, Acolapissa, and Atakapas Tribes. Terrebonne is also home to members of the United Houma Nation, a state-recognized tribe. Tribal members reside within a six-parish area along the southeastern coast of Louisiana. These peoples have strong cultural ties to the wetlands that are impacted by land loss, changing habitats, and erosion of key cultural sites, such as burial grounds. For these communities and others that call places like Pointe-aux-Chênes, Isle de Jean Charles, and Dulac home, land loss and rising sea levels pose an existential threat.

Ecosystems in the Terrebonne region include extensive bottomland hardwood and swamp forests in the Verret Basin and floating marshes in the Penchant Basin.

Salt and brackish marshes are prevalent in eastern Terrebonne. The region includes the Elm Hall Wildlife Management Area in the Verret Basin and Pointeaux-Chênes Wildlife Management Area in eastern Terrebonne, as well as the Isles Dernieres Barrier Islands Refuge and the Mandalay National Wildlife Refuge.



Source of 20% of Louisiana's seafood production



Morganza to the Gulf to include 98 mi of hurricane protection levee



Image: Timbalier Island Site Visit, 2021 (CPRA)

Resource-based industries are prevalent in the Terrebonne region's economy, with the energy industry and seafood production as primary sources of revenue. Residents of communities like Houma, Chauvin, Cocodrie, and Dulac contribute to the region's productivity, with the area accounting for over 20% of Louisiana's seafood production. Many of the outlying communities are important hubs for commercial fishing, including shrimp, oysters, and crabs. For example, in 2020, almost 34% of total statewide shrimp landings were from the Terrebonne Basin. In 2018, almost 26% of commercial fishers who landed shrimp in Louisiana lived in Terrebonne Parish. The region also has important public and private oystergrowing areas, including Lake Chien and Sister Lake. Other economic activities in the region include agriculture, ship building and fabrication, and support for the offshore energy industry. Major population centers, such as Morgan City, Houma, and Thibodaux, provide services, such as healthcare and retail, to surrounding communities.

Although beautiful, this region's geography and history of flooding and coastal land loss pose challenges for residents. Terrebonne residents and businesses have a long history of living with hurricanes and associated storm surge-based flooding. In recent decades Hurricanes Andrew (1992), Lili (2002), Rita (2005), Gustav and Ike (2008), and Ida (2021) have all caused extensive flooding. Land loss in the region was extensive during the 20th century in part due to ongoing deltaic subsidence, saltwater intrusion along the HNC and other canals, historic oil and gas activity, and natural deterioration of barrier islands, contributing to the area's vulnerability. Following Hurricane Juan in 1985, concerted efforts began to reduce the risk of flooding for bayou communities and the Houma area. The 2023 Coastal Master Plan identifies a number of projects to reduce storm surge risk in the region, including the Morganza to the Gulf project, which consists of a 98 mi hurricane risk reduction system of grass-covered earthen levees between U.S. 90 near Gibson to the west and Highway 1 near Lockport to the east.

REGIONAL APPROACH

HIGH TIDE FLOODING (HTF) IN DULAC

In addition to storm surge-based flood risk, Louisiana's coastal communities often contend with localized flooding, also known as high tide flooding which can impede day-to-day travel and activity as well as emergency services. Communities are experiencing these issues today, and their residents have informal impact thresholds — areas they know to flood regularly such as the Dulac Community Center's parking lot, which signals the threat of flooding. While the construction of the Morganza to the Gulf project has the potential to mitigate some high tide flooding, communities will still potentially be affected when the floodgates are open, allowing tidal flooding. The combined effects of sea level rise and coastal land loss will exacerbate the magnitude, frequency, and extent of these issues. As sea level rises and the geography of the coast changes, Dulac should continue to experience similar seasonal high to low tide fluctuations as it does now. However, the height of high tide, and thus the extent and magnitude of flooding will continue to increase due to these changes.


| | YEAR 1 | YEAR 25 | YEAR 50 |
|--------------------------|--------|---------|---------|
| Dulac Community Center | 17% | 95% | 95% |
| Shrimpers Row Rd / Bayou | <5% | 92% | 95% |
| Guillaume Rd | | | |

Figure 6.12: Percentage of days that may see HTF at key locations in Dulac, Lower Environmental Scenario.

For more information see Attachment H3.



Image: Shrimpers Row, Dulac (Louisiana Sea Grant College Program)



LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY

Figure 6.13: Representative HTF Elevations for Dulac at Year 1 and 50 in the Lower Scenario.



Image: Gulf Intracoastal Waterway (CPRA)





Image: Gulf Intracoastal Waterway (CPRA)

2023 COASTAL MASTER PLAN


the expected construction of the HNC Lock and



For the 2023 Coastal Master Plan, 17 projects were selected for the Terrebonne region. These projects include a variety of restoration measures, such as marsh creation, riverine diversions, ridge restoration, and the cross-basin Eastern Terrebonne Landbridge project. The Central Terrebonne Hydrologic Restoration project was selected to prevent saltwater intrusion from Caillou Lake into

Lake Mechant and support the ecosystems and habitat in the area. Several structural risk reduction projects were selected to reduce the impact of storm surge-based flooding to coastal communities across the region, such as Houma, Dulac, Larose, and Amelia. These projects, along with nonstructural risk reduction measures, can help reduce risk to residents and communities in the Terrebonne region.

Map 6.11: Terrebonne 2023 Coastal Master Plan Projects.



Hydrologic Restoration

Bank Stabilization

Barrier Island Maintenance




Figure 6.14: Terrebonne Project List.




Image: Bayou Terrebonne Floodgate, 2016 (CPRA)

EASTERN TERREBONNE LANDBRIDGE

A newly selected project for the 2023 Coastal Master Plan, the Eastern Terrebonne Landbridge project extends across the eastern Terrebonne marshes and is planned to be built in phases over both implementation periods. In IP1, the eastern component from Bayou Lafourche to Bayou Pointe-aux-Chênes would be built, and in IP2, the western and central components from Bayou Pointe-aux-Chênes to Bayou Terrebonne would be built. The project will essentially fill all of the open water within the landbridge footprint with only a few bayous remaining open. This will limit water movement from Terrebonne Bay to the interior marshes, reducing salinity levels and land loss in some areas.

MORGANZA TO THE GULF

The Morganza to the Gulf project involves the construction and improvement of a levee around Houma and Terrebonne Ridge communities from Lockport to Humphreys Canal. It is selected in IP1 in the 2023 Coastal Master Plan as it provides extensive benefits. For example, this project will reduce EADD in Houma by more than \$1.5 billion and reduce structural damage, equivalent to more than 1,500 structures at Year 50. Federal funding has only recently been provided, and progress on the system has been spearheaded by the Terrebonne Levee and Conservation District and CPRA using local and state funds. By building to USACE standards, the locally built portions of the system are seen as a contribution to the federal project. This approach can provide a model for moving ahead with a project while awaiting federal authorization and funding.



Map 6.12: Terrebonne, Land Change, Future With Action, Lower Scenario, Year 50.

REGIONAL PROJECT BENEFITS

With action, we build and maintain 58,000 acres of land in the lower environmental scenario and 17,000 acres in the higher scenario. Restoration is focused on maintaining key cross-basin landforms, including ridges, and the Eastern Terrebonne Landbridge provides both continuous marsh and some modulation of tidal flows. The Atchafalaya Diversion also brings freshwater into the Penchant Basin. In the lower scenario, these projects slow the rate of land loss and maintain a diversity of marsh types. Relatively high subsidence and increased sea level rise in the higher scenario result in dramatic loss of wetlands in the next 50 years, much of which occurs in the last two decades of the 50year projections. Fresh marshes, including flotant, persist in the Penchant Basin where the Atchafalaya Diversion is successful in maintaining a more gradual estuarine gradient than to the east of the region.

Three structural risk reduction projects were selected in the Terrebonne region including upgrades to the Larose to Golden Meadow system, which spans the Terrebonne and Barataria regions. In total, the projects reduce future storm surge-based flood risk in the region by 63% at Year 50 under the lower scenario. These projects provide a \$3.7 billion reduction in EADD in at Year 50 under the lower scenario and a \$5.2 billion reduction in EADD at Year 50 under the higher scenario. Even with the implementation of these structural risk reduction projects, significant residual risk both outside and inside of the levee systems remains.




Figure 6.15: Terrebonne Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario.

1% Annual Exceedance Probability, Lower Scenario, Year 50.



ABOUT BARATARIA

AN INTRODUCTION

Stretching from Bayou Lafourche to the Mississippi River, the Barataria region is home to vibrant communities and one of the nation's most productive estuaries. The region's swamps, marshes, and barrier islands provide numerous economic and recreational benefits, as well as protection for inland communities. Land loss, changing environmental conditions, and modifications to the region's hydrology threaten these important wetland ecosystems. Projects proposed in the 2023 Coastal Master Plan will help reverse these trends and complement projects already on-the-ground or under construction.

The Barataria Region includes portions of nine parishes: Assumption, Ascension, St. James, Lafourche, St. John the Baptist, St. Charles, Jefferson, Plaquemines, and Orleans. Extensive residential and commercial development can be found along the Mississippi River and Bayou Lafourche, as well as in the mid-basin along U.S. 90, and on the west bank of Orleans and Jefferson parishes. These include the communities of Des Allemands, Paradis, Luling, and Boutte. The communities of Lafitte, Barataria, Crown Point, and Grand Isle are more isolated and have strong ties to the ecology and natural resources of the basin. The

region has experienced rapid growth and business development over the past several decades, especially in areas such as St. Charles and Jefferson parishes, and also boasts a rich cultural heritage associated with the many Indigenous communities of the area.

The region's ecosystem is characterized by extensive swamps in the upper basin and floating marshes near Lac des Allemands and Lake Salvador. Fresh marshes grade into intermediate, brackish, and salt marshes closer to the Gulf. Several remnant natural ridges are in the area, including Bayou L'Ours, while the lower part of the basin is rimmed with barrier islands. The region includes Lake Boeuf and Salvador/ Timken Wildlife Management Areas, the Elmer's Island Wildlife Refuge, and the Barataria Unit of Jean Lafitte National Historical Park and Preserve.

As in many parts of the coast, natural resources and navigable waterways provide opportunities for economic growth and activity. Refineries, petrochemical plants, and granaries employ residents from across the region. Home to the Port of South Louisiana, the largest port by tonnage of cargo handled in the western hemisphere, and Port Fourchon, the Barataria region is instrumental in the transportation and transfer of goods between ships, barges, and trucks for distribution throughout the United States.



370K residents at risk from storm surge-based flooding



Includes Port Fourchon and Port of South Louisiana



60 projects completed since the 1990s



Home to the LDWF Fisheries Lab and Oyster Hatchery



Image: Pelicans on Queen Bess Island, 2020 (CPRA)

The waters and wetlands of Barataria Basin also support tremendous commercial and recreational fishing opportunities. Waterfowl hunting opportunities here have long been recognized as some of the best in the nation. In 2020, about 20% of total statewide shrimp landings were from the Barataria Basin. In that same year, the basin was responsible for nearly 44% of the statewide landings of oysters from private leases.

Changing environmental conditions are challenging the Barataria Region. Basin hydrology has been extensively altered since European settlement. The basin was isolated from the Mississippi River following the Great Flood of 1927, further limiting riverine inputs of sediment and freshwater to this region. Historic coastal storms impacting the region include Hurricane Betsy in 1965 and, more recently, Katrina (2005), Gustav and Ike (2008), Isaac (2012), and Ida (2021). Recent storm impacts have challenged several communities in the region, and recovery from flood and wind

damage caused by Hurricane Ida is still underway in places like Grand Isle, Lafitte, and Ironton.

Since the 1990s, more than 60 restoration projects have been constructed in the Barataria Basin by local, state, and federal agencies; parishes; NGOs; and private companies. This represents more projects and more expenditures for restoration than in any other basin. Some of these projects were built to support navigation or reduce flood risk. Examples include the Naomi Freshwater Diversion (1992), the West Pointe a la Hache Freshwater Diversion (1992), and the Davis Pond Freshwater Diversion (2002). Others addressed barrier island or headland erosion and fragmentation, such as the massive Caminada Headland Beach and Dune Restoration and the Spanish Pass Increment of the Barataria Basin Ridge and Marsh Creation project. The Mid-Barataria Sediment Diversion, a first-of-its-kind restoration project, has the capability to create and sustain thousands of acres of wetlands in the region (See p.139 for more information on this project).

137

REGIONAL APPROACH

HURRICANE IDA


Hurricane Ida made landfall at Port Fourchon on August 29, 2021 as a strong Category 4 storm and caused immense wind and flood damage. Storm surge of up to 14 ft and sustained 140 mph winds caused the destruction of homes, businesses, and tens of thousands of acres of coastal wetlands. The storm was the greatest test of the completed HSDRRS system to date with storm surge impacts stretching from Jefferson Parish to St. Bernard Parish. Outside of the HSDRRS system, communities like Leeville, Lafitte, Grand Isle, Ironton, and many more suffered devastating storm surge impacts. Some of these communities will see future risk reduction through ongoing projects, such as the New Orleans to Venice project or the Lafitte Tidal Protection project. In south Lafourche, storm surge came within a few feet of overtopping the levees, but the communities of Larose, Cut Off, Galliano, and Golden Meadow were spared catastrophic flooding. To illustrate how land loss, sea level rise, and subsidence may lead to greater future flooding and damages, we modeled Hurricane Ida on both the existing and a future landscape, for both FWOA and with the full implementation of the 2023 Coastal Master Plan. The results for the area near Lafitte show an additional 3-4 ft of storm surge and an additional 2-4 ft of storm surge in the river parish communities for FWOA under the lower scenario. Areas near the Larose to Golden Meadow system would see an additional 3-5 ft of storm surge that would overtop the existing levee and cause extensive flooding and an estimated \$1.6 billion in damage. The Larose to Golden Meadow project (111) included in the 2023 Coastal Master Plan would prevent levee overtopping and flooding within the polder.




Figure 6.17: Hurricane Ida Storm Surge Simulations.



Image: Lafitte, Post Hurricane Ida, 2021 (CPRA)








Figure 6.18: Barataria Project List.



Image: Davis Pond Freshwater Diversion, 2019 (CPRA)

UPPER BASIN DIVERSION PROGRAM


Modeling for the 2023 Coastal Master Plan made the assumption that the Mid-Barataria Sediment Diversion, Mid-Breton Sediment Diversion, and the River Reintroduction into Maurepas Swamp project would be implemented in the early years of the 50year period, in addition to the freshwater diversions already constructed. Many of the additional diversion projects that had been effective as individual projects in building or maintaining land in the 2017 Coastal Master Plan showed mixed landscape results when interacting with other diversions. The combined effects of the additional diversion projects and those already assumed to be operational resulted in excessive water levels in the basin. These results highlight the need for basin wide management of diversions. Additional evaluations suggest that upper basin diversions could play an important role in maintaining swamps and coastal marshes, estuarine gradients, and in Mississippi River flood control. CPRA is proposing to further evaluate these projects and support USACE in their Lower Mississippi River Comprehensive Management Study to identify suitable locations for the construction

of additional diversions. By continuing to evaluate a systems approach to operating multiple diversions, we can further maximize utilization of sediment, freshwater, and nutrient resources of the Mississippi River to protect and restore a larger footprint of the coastal ecosystem.

UPPER BARATARIA RISK REDUCTION

This project includes construction and improvement of a levee along U.S. 90 between the West Bank and Larose, with a barge gate on Bayou des Allemands. Under the lower scenario, at Year 50, the project reduces flood depths by more than 5 ft in the Paradis, Luling, and Boutte areas of St. Charles Parish for the 1% AEP, and results in localized increases in flooding south of the levee. The result is a reduction in EADD of more than \$37 billion under the lower scenario and \$42 billion in the higher scenario over the 50 year planning horizon. USACE recently issued their Upper Barataria Basin Chief's Report with their tentatively selected plan (TSP) which differs slightly from the features evaluated here. CPRA is committed to working with USACE and the Lafourche Basin Levee District (LBLD) to implement the Upper Barataria Risk Reduction project as described in the TSP.

142 LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY 2023 COASTAL MASTER PLAN 2023 COASTAL





Map 6.16: Barataria, Land Change, Future With Action, Lower Scenario, Year 50.

REGIONAL PROJECT BENEFITS

With action, we build and maintain 53,000 acres of land in the lower environmental scenario and 31,000 acres in the higher scenario. Restoration includes cross-basin landbridges, central basin marsh creation areas, restored ridges, and ensuring wetlands are more robust between the Larose to Golden Meadow levee and the Gulf. Many of these projects work in concert with the Mid-Barataria Sediment Diversion, included in FWOA, to maintain extensive marsh areas in the lower scenario. In the higher scenario, increased sea level rise and higher rates of subsidence result in higher land loss. There is extensive loss in the southeast portion of the region and on the western side, south of the GIWW, especially in 30-50 years. However, there is little change in the upper basin and extensive areas of swamp, flotant, fresh and intermediate marshes remain.

Three structural risk reduction projects were selected in the Barataria region, including upgrades to the Larose to Golden Meadow system which spans the Terrebonne and Barataria regions. In total, these projects reduce future surge-based flood risk in the region by 64% at Year 50 under the lower scenario. These projects provide a \$2.0 billion reduction in EADD at Year 50.





 $Figure\ 6.19: Barataria\ Land\ Area\ Over\ 50\ years,\ Future\ With\ and\ Without\ Action,\ Higher\ and\ Lower\ Scenario.$



Figure 6.20: Aerial View of the Pontchartrain/Breton Region with the 2023 Coastal Master Plan Projects.

are separated from the Gulf by a string of barrier islands, including the Chandeleur Islands, part of the Breton National Wildlife Refuge.











ABOUT PONTCHARTRAIN / BRETON

The most densely populated region on the coast, the Pontchartrain/Breton region is known across the world for its celebrated cultural heritage. The allure of its music, food, and celebrations is matched by the beauty of the swamps, marshes, lakes, and rivers that define its landscape. The 2023 Coastal Master Plan builds on the extensive work undertaken since Hurricane Katrina, and proposes a suite of projects to safeguard the region's rich cultural and environmental assets for future generations.

The Pontchartrain/Breton region includes all or part of East Baton Rouge, Livingston, Tangipahoa, St. Tammany, Orleans, St. Bernard, Plaquemines, Jefferson, St. John the Baptist, St. James, and Assumption parishes, and is home to population centers like New Orleans, Metairie, the North Shore communities, the River Parishes, and smaller towns along the lowermost Mississippi River. The region boasts a diversity of residents with significant Black, Creole, Indigenous, Southeast Asian, and Latin American populations in the area.

New Orleans is a popular tourist destination with distinct French and Spanish Creole architecture, cross-cultural and multilingual heritage, and a large annual Mardi Gras celebration. Just outside the city, it is clear why this region is considered a paradise for fishing, hunting, and



1.1M residents at risk from storm surge-based flooding



Home to New Orleans and surrounding communities

bird watching – St. Bernard Parish has several stops on the America's Wetlands Birding Trail, and St. Tammany Parish includes recreational assets like the Tammany Trace and North Shore Fontainebleau State Park.

Other managed lands include Joyce Wildlife
Management Area, St. Tammany Wildlife Refuge, the
Big Branch Marsh, Bayou Sauvage, Delta and Breton
National Wildlife Refuges. To the east, the Breton
Wildlife Refuge provides important wintering habitat for
the federally threatened piping plover. At the other end
of the region, the Maurepas Swamp includes more than
100,000 acres of cypress tupelo swamp, bottomland
hardwood forest, and fresh and intermediate marshes.
Between these is a productive estuary, including
Lake Pontchartrain, Lake Borgne, Breton Sound, and
Chandeleur Sound and includes extensive areas of
marsh on the Orleans Landbridge and Biloxi Marsh.

This landscape supports vibrant recreational and commercial fisheries. In 2020, the region accounted for 37% of the statewide crab landings. It also supports major industrial activity such as ports and petrochemical industries, as well as agriculture, including extensive sugarcane along the Mississippi River corridor.

Many communities within the Pontchartrain/Breton region have levees and other structures to protect them from storm surge-based flooding. Following Hurricane



100,000+ acres of forested wetlands



Includes the Port of New Orleans



Image: Delacroix, Louisiana (CPRA)

Katrina in 2005, HSDRRS was built to reduce flood risk in Orleans, Jefferson, St. Bernard, Plaquemines and parts of St. Charles parishes; much of the area on the East Bank; and other areas in this region. Master plan modeling suggests that, with prescribed maintenance, including authorized lifts, the system will continue to provide a 1% AEP level of risk reduction over the next 50 years even under the higher environmental scenario. In 2021, construction began on the West Shore Lake Pontchartrain Hurricane Protection project. Once complete, the structure will provide 100-year storm surge flood protection to 60,000 Louisianans in St. Charles, St. James, and St. John the Baptist parishes.

A number of innovative restoration projects have also been implemented in this region to maintain or restore degrading wetlands. The Caernarvon Freshwater Diversion, constructed in 1991, was initially designed to manage salinity levels in the Breton Sound area to be suitable for oysters in the public seed grounds. It has since shown that it can build and sustain land and is now operated to better support ecosystem restoration. The West Bay Sediment Diversion, completed in 2003,

is an uncontrolled diversion of Mississippi River freshwater and sediments on the west bank above Head of Passes in the Bird's Foot Delta. The success of these projects supports the currently planned diversion projects in the region, including the River Reintroduction to Maurepas Swamp and the Mid-Breton Sediment Diversion.

In recent years, many communities from East Baton Rouge Parish to Slidell have experienced substantial growth. In these areas, communities are developing in previously undeveloped lowland and flood prone areas. As these areas are developed, risk of damage due to storm surge-based flooding rises substantially. As CPRA and its partners work to mitigate this risk, it is imperative that local authorities support smart growth and development by enacting appropriate policies, ordinances, and rules. Requiring building design to utilize freeboard and build above the base flood elevation and limiting unfettered development in flood-prone areas now can pay dividends later by eliminating unnecessary damages and the need to retrofit structural or nonstructural strategies. Only proper land use planning and appropriate building practices will allow Louisiana to keep up with the changing landscape of risk.

149

REGIONAL APPROACH

HURRICANE ISAAC

Hurricane Isaac first made landfall at Southwest Pass before returning to water and making a second landfall at Port Fourchon on August 29, 2012. The slow-moving storm made landfall as a Category 1 hurricane with maximum sustained winds of 80 mph. Storm surge from Hurricane Isaac reached 11 ft at Shell Beach and 6-8 ft in the surrounding areas of southeast Louisiana. Inundation over ground level reached 17 ft in parts of Plaquemines Parish and overtopped levees in Braithwaite. Its unusual track and speed produced flooding and damage to Terrebonne, Barataria, Breton, and Pontchartrain basins. North Shore communities of Mandeville. Slidell, and Eden Isles saw significant impacts as well as areas of Livingston and Tangipahoa parishes. Using ADCIRC, Hurricane Isaac was modeled on the existing landscape and on the landscape 50 years from now under the lower environmental scenario to illustrate how land loss, sea level rise, and subsidence lead to greater flooding and damage without further action. The results show an additional 2-3 ft of storm surge in communities like Lafitte, Delacroix, Mandeville, and Maurepas. Hurricane Isaac would have produced three times as much economic damage (measured in 2020 dollars) across southeast Louisiana if it occurred 50 years in the future with no additional restoration or risk reduction measures in place. Much of the increase in damage is concentrated in St. Tammany Parish, particularly in Slidell, which illustrates the importance of the Slidell Ring Levee.



Image: Lafitte Post Hurricane Isaac, 2012 (CPRA)





Figure 6.21: Hurricane Isaac Storm Surge Simulations.



Image: Maurepas Swamp (CPRA)



2023 COASTAL MASTER PLAN

Image: Maurepas Swamp (CPRA)

151

150 LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY






Figure 6.22: Pontchartrain/Breton Project List.



Image: Marsh Creation construction of the New Orleans Landbridge, 2022 (CPRA)


NORTH SHORE STRUCTURAL RISK REDUCTION

The communities of Slidell, Eden Isles, and Pearl River collectively have among the highest risk from storm surge-based flooding in coastal Louisiana - an estimated \$845 million EADD under current conditions, which is expected to triple over the next 50 years under the lower environmental scenario. The Slidell Ring Levee project reduces roughly 35% of the risk in these communities. Fully addressing this risk will require both structural and nonstructural mitigation measures. The Slidell Ring Levee project includes the construction or improvement of nearly 17 mi of levees and floodwalls around Slidell. The levee alignment is based on USACE's St. Tammany Parish Feasibility Study Tentatively Selected Plan (TSP). USACE's TSP included a significant nonstructural component, but excludes structural protection for communities like Eden Isles. CPRA will implement structural risk reduction measures (e.g., flood gate, pump station,

road elevation) for that community to supplement the TSP. Such efforts have the potential to further reduce risk for over 2,100 homes.

MARSH CREATION PROJECTS

Several large-scale marsh creation projects were selected in the area of Breton Sound just east of the Mississippi River, including West Delacroix Marsh Creation and Pointe a la Hache and Carlisle Marsh Creation. These projects plan to use sediment dredged from the Mississippi River. The proximity to the Mississippi River as a source of sediment makes these more cost-effective than similar projects without nearby borrow areas. As these projects move into feasibility and design, there may be additional opportunities to coordinate construction of multiple projects and utilize pipeline corridors.



REGIONAL PROJECT BENEFITS

With action, we build and maintain 37,000 acres of land in the lower environmental scenario and 65,000 acres in the higher scenario. Restoration includes extensive marsh creation in the Breton Basin and east of Lake Pontchartrain, as well as a small diversion into the Central Wetlands. The Mid-Breton Sediment Diversion is included in FWOA. In the lower scenario, these projects result in a major increase in land area in the next 50 years. Despite implementation of the plan, land loss continues in the Bird's Foot Delta. In the higher scenario, most of the projects are locally effective in maintaining land over 50 years, although there is extensive loss in the Biloxi marshes and around Lake Borgne. In both scenarios, the swamps and fresh and intermediate marshes around Lake Pontchartrain and in the upper Pontchartrain Basin remain intact, in part due to the influence of the River Reintroduction to Maurepas project, which is in FWOA.

Four structural risk reduction projects were selected in the Pontchartrain/Breton region. In aggregate, they reduce future surge-based flood risk in the region by 35%. These projects provide a \$1.6 billion reduction in EADD at Year 50 under the lower scenario and a \$2.5 billion reduction in EADD at Year 50 under the higher scenario. Even with the implementation of these structural risk reduction projects, significant residual risk remains, especially on the North Shore. Our analysis shows a significant need and opportunity for nonstructural risk reduction in these communities.




Figure 6.23: Pontchartrain/Breton Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario.



BEYOND THE MASTER PLAN

PROGRAMS AND INITIATIVES

This chapter outlines projects, programs, and initiatives that work with the master plan to actively shape the future of coastal Louisiana's communities and landscape.

In support of these efforts, data and information generated through the master plan process are available to all stakeholders, from the general public to government program managers, researchers, and educators. While some are led by CPRA, others are led by CPRA's state and federal agency counterparts whose directives focus on topics related to coastal restoration and protection. Several example efforts highlighted in this chapter are briefly described below.

Most directly tied to the master plan is the 2023 Master Plan Data Viewer. The data viewer complements the master plan by providing access to data and information developed as part of this most recent planning process. This interactive tool displays projected flood risk and land change data that helps viewers visualize what change might look like over time in their communities and across the coast. The data viewer also provides detailed information about recommended protection and restoration projects.

Each six-year master plan update cycle is an adaptive management exercise and includes evaluating and redefining the problem, revisiting overarching goals and objectives, developing and refining system models, identifying uncertainties, formulating the plan, monitoring actions, and assessing the system. The science that underpins the master plan is continually being advanced as the master plan is developed our team evaluates recent analysis and incorporates new research into the process. Field investigations undertaken by CPRA and our partners are also used to refine our understanding of coastal

processes. This approach maximizes the success of the coastal protection and restoration program by iteratively incorporating new information into each step of the planning and decision-making process.

In addition to updating and implementing the master plan, CPRA is also responsible for administering several programs tied to specific regions of the coast. Examples of these programs include the Atchafalaya Basin Program (ABP), the Lowermost Mississippi River Management Program (LMRMP), and the Barrier Island System Management Program (BISM).

The ABP was established to develop and implement a comprehensive plan to address the priority issues affecting the Atchafalaya Basin Floodway System. Implementation of the program occurs through an annual planning process.

Of key importance to the nation, and Louisiana is another river – the Mississippi River. The LMRMP is a \$9.3 million effort that aims to move toward a more holistic approach for water and sediment management that supports the long-term sustainability of the Lowermost Mississippi River.

Barrier islands are another critical component of the coastal landscape that CPRA works to maintain. BISM is a holistic, system wide approach to island management that guides when and where to focus restoration resources (funding and sediment) to maintain barrier island systems.

Although CPRA is solely responsible for developing and implementing many coastal projects, programs, and initiatives, CPRA's leadership and staff understand the importance of collaborating with and leveraging the efforts of other state and

federal partners across the coast. Collective efforts forged through both long-standing and more recent collaborations yield synergistic results. Example collaborative efforts include the Coastal Wetlands Planning, Protection, and Restoration Act (CWPPRA) program, the Southwest Coastal Louisiana Study, and the Louisiana Watershed Initiative (LWI).

The purpose of the CWPPRA program is to identify, prepare, and fund construction of restoration projects throughout coastal Louisiana as well as to promote research and implement wetland preservation. This program has a long history of implementing restoration and monitoring across the coast. The Chairman of the CPRA Board sits on the CWPPRA Task Force.

The Southwest Coastal Louisiana Study was completed in 2016 by USACE with CPRA as the local sponsor; it recommended both risk reduction and ecosystem restoration measures across Calcasieu, Cameron, and Vermilion parishes. Through the Infrastructure Investment and Jobs Act of 2022 and Fiscal Year 22 Community Projects Funding, \$296 million has been secured for implementation of voluntary nonstructural risk reduction measures recommended by the study.

Although CPRA primarily focuses on coastal restoration and protection, the agency participates in important initiatives that extend beyond the coastal area. One example is LWI. CPRA serves as one of five state agencies on the Council on Watershed Management, which administers LWI. LWI represents a new watershed-based approach to floodplain management in Louisiana and seeks to reduce flood risk and improve floodplain management

across the state, including through maximizing the natural and beneficial functions of the floodplain.

One of the programs that LWI is implementing through the Office of Community Development, is a voluntary buyout program. This program was created to provide assistance to willing landowners in flood prone areas. While not limited to the coastal zone, this program provides benefits, primarily to low to moderate income residents, to help move residents out of harm's way and relocate to higher and drier ground.

In addition to efforts in which CPRA is directly involved, other critical efforts are being carried out which affect coastal Louisiana communities. For example, the Climate Initiatives Task Force was established by Executive Order in 2020 to develop strategies and actions to address the causes of climate change, identify strategies to improve resilience, and develop policies to reduce greenhouse gas (GHG) emissions to put Louisiana's efforts in line with the goals of the Paris Climate Agreement. The Louisiana Climate Action Plan was approved in 2022 and contains strategies and actions to reduce GHG emissions across the state's economy. Restoring and conserving coastal wetlands is one of 28 strategies outlined in the plan.

Another example initiative with direct impacts to Louisiana's citizens is the Federal Emergency Management Agency's (FEMA) Risk Rating 2.0. Through this effort, FEMA is updating the National Flood Insurance Program's risk rating methodology through the implementation of a new pricing methodology. The methodology leverages industry best practices and cutting-edge technology to enable FEMA to deliver rates that are actuarially sound, equitable, easier to understand and better reflect a property's flood risk.

160 LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY 2023 COASTAL MASTER PLAN 2023 COASTAL MASTER PLAN

2023 MASTER PLAN DATA VIEWER

For the 2017 plan, CPRA made public access to information a priority and worked to develop a new tool, the Master Plan Data Viewer, to serve as a complement to the plan document.

This interactive tool increases the accessibility of complex model output information and enables coastal Louisiana residents to see how the landscape and their flood risk from storms may change over time 50 years into the future.

Similarly, the 2023 Master Plan Data Viewer is an interactive online companion to the 2023 plan and includes land change, vegetation type, flood depth, damage, and 2023 Coastal Master Plan project information. The land change and vegetation type data can be explored by decade, by environmental scenario, for both with and without the master plan in place. Flood depth and damage information can be explored in the same way, with the added layers of seeing how depth and damage change when the frequency of occurrence (annual exceedance probability) varies and how projected damage is quantified over time either in dollars or by structures.

Not only has the viewer been updated with the 2023 plan information, which includes the most up to date model outputs at a higher resolution, but the viewer's style and functionality has also been improved. While the viewer's goal is to make the master plan data accessible to residents, the viewer holds a wealth of information also used by community planners, businesses, parish officials, other state agencies, and academia. Many of the changes made were a result of feedback received directly from all of these stakeholders.

One significant improvement to the user experience is that the landing screen now has the option to take a guided tour that explains why there is a need for a master plan and illustrates the viewer's features and the types of information available. This new guided tour option allows us to share important context and background on the viewer's data to improve coastal Louisiana residents' understanding and usability of the information, and in turn increases their flood risk awareness and provides them with important information needed to prepare and plan for their futures.

Other important updates to highlight are the ability to access and easily use the 2023 Master Plan Data Viewer on mobile phones and tablets, literally putting the data within arm's reach. This has proved to be invaluable in sharing information and discussion both with and among community members. In addition, the viewer's search bar functionality has expanded beyond entering addresses so you can now search for keywords, such as part of a project name. Additional features include new zoom and highlighting functions whereby clicking on a project name zooms to that location, and clicking on a project type highlights them across the coast.

Explore the 2023 Master Plan Data Viewer and send any questions or feedback to masterplan@la.gov.



Explore more on CPRA's website: https://coastal.la.gov/our-plan/2023-coastal-master-plan/





Figure 7.1: Desktop View of the Master Plan Data Viewer Showing Project Information.



 $\hbox{Figure 7.2: Desktop View of the Master Plan Data Viewer Showing Coastwide Land Change Data. } \\$

ADAPTIVE GOVERNANCE INITIATIVE

The impacts of Louisiana's coastal crisis extend beyond the immediate effects of land loss or hurricane storm damage and demand interventions outside the scope of hurricane protection and coastal restoration projects.

The impacts of coastal change on local communities present significant challenges to stage agencies charged with the continued management of state-owned assets and the provision of services to coastal residents and communities. Recognizing the wide-ranging impacts associated with our changing coast, Governor Edwards signed Executive Order 2020-19 on Coastal Resilience in August of 2020.

Executive Order 2020-19 began the process of building a broader, cross-government approach to resilience by appointing an inaugural Chief Resilience Officer for the state and charging each executive agency with appointing a resilience coordinator to be the agency's point person for advancing responses to the demands of a changing coast. These resilience coordinators are tasked with conducting vulnerability assessments to identify the ways their agencies are impacted by coastal change both now and in the future. They are also responsible for developing adaptation actions that address their agencies' most significant vulnerabilities.

Although each agency in the Executive Branch has a distinct mission and its own expertise, resources, and responsibilities, they are all impacted and tested by the monumental changes occurring across Louisiana's coast.

Each of these agencies also has a role to play in building a more resilient coast. Coastal resilience spans several spheres of state government — it includes a robust built environment, a sustainable natural environment, a strong economy, and health and opportunity for all coastal residents.

The Adaptive Governance Initiative (AGI) asks agencies to consider their role in proactively planning for coastal resilience and ensuring that they can continue to meet their mission in the face of increasing coastal change. Such a multi-sector, holistic approach to the coastal crisis is necessary to support coastal residents and business in the face of rapid change.

The crisis on the coast is punctuated by singular disasters like hurricanes, but it also brings chronic stressors for the people, communities, natural resources, and economies of Louisiana as water levels rise and land degrades. These chronic issues often manifest in higher management costs, increased workloads, and extended periods of emergency operations within state agencies. Through the AGI each agency is identifying ways to adapt to these changes while also elevating the challenges and needs that are common across several agencies.

Together, agencies are helping to build a more resilient state by supporting more comprehensive and adaptable programs and assets that meet the changing needs of our coastal populations.

Louisiana's master plan offers a foundation for the agencies' work by providing analysis and insights into how the coast will change over time, including




Figure 7.3: Cascading Impacts of Coastal Change to a Selection of State Agencies.

which areas may face increasing environmental risk and which may have more time to adapt. Equipped with this critical information, agencies across government can better plan their investments in assets and adjust their programs to serve the people of Louisiana and carry out their missions more effectively and efficiently today and in the future.

The AGI is a joint effort of the Office of the Governor and the Center for Planning Excellence (CPEX) and is being implemented with support from the Walton Family Foundation, the Kresge Foundation, Foundation for Louisiana, Greater New Orleans Foundation, and CPRA.

- "...Whereas the full breadth of tools, expertise, and missions of Louisiana's various state agencies must be brought to bear to more fully and more directly address the economic and social implications of Louisiana's degrading coast; and whereas this multi-agency approach will ensure the best outcomes for the people of Louisiana and better position the state to partner with the parishes and municipalities most at risk from coastal change..."
- Governor John Bel Edwards Executive Order JBE 2020-19

ATCHAFALAYA BASIN PROGRAM

The Atchafalaya Basin is the nation's largest river swamp, containing almost one million acres of America's most significant bottomland hardwoods, swamps, bayous, and backwater lakes. The basin begins near Simmesport, LA, and stretches 140 mi southward to the Gulf of Mexico. Currently, the Atchafalaya Basin is bound by ridges formed by levee building along active and abandoned courses of the Mississippi River and serves as a critical relief valve for extreme flood events on the Mississippi River.

Authorized in 1928 by the Flood Control Act, the Atchafalaya Basin Floodway System serves as a system of public works within the lower Mississippi Valley, providing flood risk management and a stable, efficient navigation channel using levees and floodwalls, floodways, channel improvements and stabilization. Over time, however, modifications to the natural flow regime of the Atchafalaya River and its swamp have caused sedimentation and water quality issues in the basin. Poor water quality is the result of poor connectivity of waterways in the basin, leaving many areas stagnant and with low dissolved oxygen that, in turn, promotes an overabundance of invasive, aquatic plants, such as water hyacinth and hydrilla. These pervasive issues threaten the ecosystem, navigation, flood control, and the communities that rely on the basin's natural and cultural resources.

The Atchafalaya Basin Program (ABP) was established to develop, implement, and manage a comprehensive state master plan for the Atchafalaya Basin Floodway System. ABP is part of CPRA's overall annual planning process. The primary goal of ABP

is to improve water quality and improve access to the basin through the implementation of hydrologic restoration projects. Through the implementation of these projects, the program ensures that the ongoing work aligns with the state's coastal priorities.

Although ABP is administered by CPRA, many entities provide recommendations and guidance such as the Atchafalaya River Basin Restoration and Enhancement Task Force (ARBRE). ARBRE is made up of stakeholders that include state and local leaders, academics, private citizens, and state agency representatives. ARBRE is chaired and staffed by the Governor's Office of Coastal Activities (GOCA). ARBRE was created to identify major concerns and develop strategies and recommendations to the CPRA Board.

ARBRE works to elevate critical issues facing the Atchafalaya Basin, identify and build support for new and recurring sources of funding, identify shared goals and values for restoration and enhancement of the basin, and serve as a proactive means to build consensus and advise ABP on matters relating to the implementation of the Atchafalaya Basin Floodway System. Once ARBRE was established, its primary mission was to study the Atchafalaya Basin and develop an initial report on findings for the CPRA Board. The recommendations included the following:

- Enhance outreach that highlights the importance of the Atchafalaya Basin locally
- Urge and request Congress to fully fund construction of finalized USACE studies relevant to the management of the Atchafalaya Basin as well as fund authorized studies
- Urge USACE to approach management of the Atchafalaya Basin holistically, designating



Image: Atchafalaya Swamp, 2018 (Louisiana Sea Grant College Program)

ecological restoration as a primary component along with flood control and navigation

- Request the CPRA Board evaluate inclusion of the remainder of the Atchafalaya Basin within the Louisiana Coastal Zone
- Restore the north/south sheet flow within the basin
- Restore and conserve deep water habitats within the basin
- Examine ways to better manage sediment within the Atchafalaya Basin
- Examine the current hydrology of the Atchafalaya Basin, including management of the Old River Control Complex and the Atchafalaya Basin channel outlets
- Update the state's Atchafalaya Basin Master
 Plan to include current conditions and challenges
 as determined by the ARBRE Task Force
- Recommend the CPRA Board and CPRA enhance public engagement concerning the

- management of the Atchafalaya Basin
- Recommend the ARBRE Task Force be used to discuss and inform potential management actions within the Atchafalaya Basin
- Explore opportunities for significant recurring funding for ABP

These recommendations inform CPRA on the implementation of future projects. CPRA considers projects for funding on an annual basis. All projects submitted through CPRA's ABP solicitation process are screened on a variety of metrics, including master plan consistency, geographic areas with issues of water quality, sedimentation, public access, and nonduplication of submissions previously turned down. CPRA, as the non-federal sponsor for USACE Floodway Projects, provides the mechanisms to match federal dollars used in the mitigation of the Atchafalaya Basin Floodway System.

CLIMATE INITIATIVES TASK FORCE

In August 2020, Governor John Bel Edwards signed an Executive Order to create the Louisiana Climate Initiatives Task Force in response to the 2018 Intergovernmental Panel on Climate Change (IPCC) Special Report on greenhouse gas (GHG) emissions reduction pathways. The Task Force was established to develop strategies and actions to address the causes of climate change, identify strategies to improve resilience, and develop policies to reduce GHG emissions in an effort to help avoid the worst impacts of climate change as well as put Louisiana's efforts in line with the goals of the Paris Climate Agreement.

The Louisiana Climate Initiatives Task Force was a 2-year initiative to support the state achieving net zero GHG emissions by 2050. In order to achieve net zero emissions, the Task Force has set the following emission reduction goals:

- By 2025, reduce net GHG emissions by 26-28% of 2005 levels
- By 2030, reduce net GHG emissions by 40-50% of 2005 levels
- By 2050, reduce GHG emissions to net zero

More than 140 experts participated as members of the Task Force, its committees, or its advisory groups and engaged across nearly 50 public meetings held since November 2020. The Task Force includes scientists, state administrators, academics, oil industry representatives, and environmental advocates. The Task Force was supported by volunteers from diverse backgrounds organized into six sector committees, representing different sectors of the state's economy and four advisory groups focused on equity, science,

legal, and financial considerations. The 23-member body set priorities for the overall planning process as well as an approved set of recommendations for the Climate Action Plan. The Task Force was chaired and staffed by the Governor's Office of Coastal Activities (GOCA). Under leadership of the Governor's Executive Assistant for Coastal Activities, GOCA served as the staff and managers of the Task Force, advisory groups, and sector committees in coordination with advisory and committee chairs.

Louisiana is among the most vulnerable states in the United States to the impacts of climate change. The state's hot and humid climate and location at the mouth of the Mississippi River and the edge of the Gulf of Mexico carry environmental challenges that have direct and indirect impacts on local communities. Throughout the state, whole communities are being displaced. Louisiana is home to people, critical industries, cultural resources, and tourism economies. The coastal plain and low-lying regions of the southeast are extremely vulnerable to climate change impacts. Flood frequencies, extreme rainfall events, and sea level rise affect property values and the viability of infrastructure. Extreme heat and changing seasonal climates are projected to have impacts on exposure-linked health and economic vulnerabilities in agricultural, timber, and manufacturing sectors.

The Louisiana Climate Action Plan contains 28 strategies and 84 specific actions to reduce GHG emissions across the state's economy. The report provides details from activities across the economy about where Louisiana's GHG emissions originate, where they are naturally absorbed from the atmosphere, and direction about how to approach GHG emissions reductions in a focused way. The planning process for developing the Final Climate

Report was developed through the Structured Decision Making approach, which integrates science and policy to break down complex decisions and identify solutions that achieve the desired ends.

With the technical support of the Louisiana State University (LSU), the LSU Center for Energy Studies conducted an update to Louisiana's GHG inventory using the United States Environmental Protection Agency's State Inventory Tool methodology to ensure consistency with the methodology used to prepare the state's previous inventory. A Science Advisory Group provided oversight and direction to guide the GHG inventory update process, including two rounds of comments. The inventory estimates and assesses the state's GHG emissions from all major sources, activity types, economic sectors, and pollutant types and provides an important updated snapshot in time of Louisiana's GHG baseline. Overall, the findings of this inventory suggest that industrial decarbonization is critical to achieve future GHG emission goals in Louisiana.

A presentation of draft findings was shared with the Task Force in its July 2021 meeting. The plan recommends strategies (high-level approaches) and actions (practical and implementable policy steps) to reduce GHG emissions to net zero by 2050 and avert the worst impacts of climate change.

The recommendations span eight sections and include the following:

- Clean energy transition
- Industrial decarbonization
- Actively managed methane emissions
- Transportation, development, and the built environment

- Natural and working lands and wetlands
- An inclusive, low-carbon economy
- Collaboration and partnership to ensure successful implementation
- Accountability and adaptability to ensure lasting success

The plan also includes three priority policy pillars:

- · Renewable electricity generation
- Industrial electrification
- Industrial fuel switching to lowand no-carbon hydrogen.

The plan also offers strategies and actions that can improve health outcomes and the quality of life of Louisiana residents immediately. These actions include reducing the amount of fossil fuel combustion in the production of electricity and manufactured goods and from buildings and transportation while helping to slow the warming of the atmosphere that causes other climate impacts that harm health, safety, and quality of life.

The Climate Action Plan was approved on January 31, 2022, and the final plan, Louisiana's Climate Action Plan was sent to the Governor for his consideration on February 1, 2022. The Task Force met again in March 2022 to move forward with the plan's implementation. As the state's first effort to address the root causes of climate change, the Climate Action Plan also contains a detailed description of the science of climate change and details how a warmer planet is impacting Louisiana people, environment, and economy with increasing severity and frequency.

SOUTHWEST COASTAL LOUISIANA

The people, economy, environment, and cultural heritage of Southwest Coastal Louisiana are at risk from damages caused by hurricane storm surge-based flooding. The area's flat, low elevation, proximity to the Gulf of Mexico, subsiding lands, and rising seas, are all contributing factors that cause coastal flooding, shoreline erosion, saltwater intrusion, and loss of wetland and Chenier habitats.

The Southwest Coastal Louisiana Study is the first federally authorized feasibility level study with the dual purpose of addressing hurricane and storm damage risk reduction and restoring the coastal ecosystem of southwest Louisiana. The study focuses on 4,700 sq mi in the Calcasieu, Cameron, and Vermilion parishes. In 2016, the study established the Southwest Coastal Louisiana Final Integrated Feasibility Report and Environmental Impact Statement (2016 Feasibility Report).

After the study was completed in 2016, Congress authorized the Southwest Coastal Louisiana Hurricane and Storm Surge Damage Risk Reduction and Ecosystem Restoration Project in the Water Infrastructure Improvements for the Nation Act of 2016 (WIIN Act of 2016). This project will decrease damages related to storm surge-based flooding by implementing risk reduction strategies, such as floodproofing, structural elevation, and localized storm surge risk reduction measures (berms). Implementation of the project will benefit social and economic factors related to housing, tax revenue and property values, and community cohesion. Participation in this project is completely voluntary. Benefits that structure owners may experience as a result of the project may include reduced storm damages for little-to-no out of pocket expenses and increased community resilience.

Construction funding was added to the 2022 Infrastructure Investment and Jobs Act in the amount of \$120 million. The funds are only available for the storm damage risk reduction features of the project. Additional USACE guidance is forthcoming once the funds are made available. The \$296 million investment is projected to elevate over 500 structures.

USACE will work closely with the CPRA Board, who will serve as the non-federal sponsor, to execute a Project Partnership Agreement. Once the agreement is in place, USACE will solicit and award a Design/Build Construction Contract to prepare individual plans. Once agreed to by the homeowner, the CPRA Board and USACE will issue a notice to proceed to elevate the structure to the projected Year 2075 100-year base flood elevation. Homeowners will be required to sign a floodproofing agreement stating that they cannot use the space below the first floor for living space along with other terms.

To date, 27 structures have been approved for construction and elevation — 10 in Calcasieu Parish and 17 in Vermilion Parish. USACE prioritized the structures by their first floor elevation and the low to moderate income area status. Approximately 150 voluntary applications have been received for inclusion in the project from the targeted list of homeowners, and elevation of the first structures is expected in early 2023.

BARRIER ISLAND SYSTEM MANAGEMENT

Coastal Louisiana's barrier island systems are an important component of the Mississippi River Delta Plain, providing a variety of ecosystem services, such as habitat, storm surge buffering, and maintenance of marine and estuarine gradients. For decades, there have been efforts to restore and protect these rapidly degrading barrier islands. In 2021, CPRA developed the Barrier Island System Management (BISM) program with facilitation by the Water Institute of the Gulf. BISM is a holistic, system-wide approach to barrier island management that guides when and where to focus restoration resources to maintain barrier island integrity, while minimizing overall system maintenance costs and reducing project implementation times.

Two databases were created to support the BISM program. The BISM Database of Databases is an inventory of data relevant to barrier island restoration decisions. The BISM Stakeholder Concern Inventory details decision-maker and stakeholder interests relevant to barrier island restoration, including potential funding entities and regulatory authorities.

Louisiana has also developed the Barrier Island Restoration Tradeoff Analysis (BIRTA) toolkit to support quantitative analysis of restoration project consequences, identify future sediment and funding needs, and provide input into the design of monitoring programs. Because the model is probabilistic and driven directly by available data, it can identify the largest uncertainties and most critical gaps in barrier island restoration prioritization.

There are several additional steps that can be taken to advance the programmatic objectives of BISM, including:

- Expansion of Louisiana Sediment Availability and Allocation Program for broader use in Regional Sediment Management and linkage with the BISM BIRTA toolkit
- Coordination of BISM and Barrier Island Comprehensive Monitoring Program (BICM) as part of an adaptive management approach to barrier island and headland restoration and monitoring
- Enhance linkages of BISM with the master plan
- Working Group to streamline project permitting

COASTAL WETLANDS PLANNING, PROTECTION, AND RESTORATION ACT

The Coastal Wetlands Planning, Protection, and Restoration Act (CWPPRA) was established in 1990 through federal legislation to identify, prepare, and fund construction of coastal wetland restoration projects throughout Louisiana. While restoration is a major part of the initiative, CWPPRA also aims to promote research and implement wetland preservation. Since its foundation, Louisiana has benefited from the continued efforts of CWPPRA in overseeing and implementing roughly 210 coastal restoration or protection projects.

The CWPPRA Program is managed by the CWPPRA Task Force comprised of representatives of the Louisiana's Governor's Office of Coastal Activities as well as five federal agencies, including USACE, NOAA, the U.S. Fish and Wildlife Service, the U.S. Department of Agriculture (USDA) Natural Resources Conservation Services, and the U.S. Environmental Protection Agency. The Task Force plans and implements projects that create, protect, restore, and enhance wetlands throughout coastal Louisiana.

Because CWPPRA projects are partially funded by the state, all CWPPRA projects are required to be consistent with the master plan. Input and public participation are essential parts of project design, planning, and selection each year. The selection process consists of four regional planning teams accepting projects nominated by the public, with a coastwide planning team selecting up to 20 engineering and design projects and six demonstration (planning) projects from the nominated list. Ten candidate projects and three demonstration projects are selected for more detailed assessments. Work groups review and

evaluate project costs, need, feasibility, and the overall benefit. The CWPPRA Technical Committee conducts public hearings to release findings and receive comments about the candidate projects. The Technical Committee recommends up to four of the 10 candidate projects for the CWPPRA Task Force to select projects to receive funding.

CWPPRA project funding is allocated through an annual funding stream, with a mix of federal and state funds. Federal funding comes through the Sport Fish Restoration and Boating Trust Fund, which is funded by taxes on marine fuel, boater registrations, and fishing equipment. There is an 85% federal, 15% state cost share, with roughly \$5 million allocated for planning, \$3 to \$4 million allocated for engineering and design projects, and project-dependent funding for construction and post completion monitoring/maintenance. Funded projects provide for the long-term conservation of wetlands and dependent fish and wildlife populations with cost-effective plans for creating, restoring, protecting, or enhancing coastal wetlands.

Considered the backbone for restoration throughout the state, CWPPRA has an entire suite of projects identified for restorative habitat. Administered by USACE, typical projects undertaken through CWPPRA include marsh creation, shoreline protection, hydrologic restoration, beneficial use of dredged material, terracing, sediment trapping, vegetative planting, barrier island restoration, and bank stabilization. Funded projects provide for the long-term conservation of wetlands and dependent fish and wildlife populations by creating, restoring, protecting, or enhancing coastal wetlands.

LOWERMOST MISSISSIPPI RIVER MANAGEMENT PROGRAM

The Lowermost Mississippi River Management
Program (LMRMP) aims to move toward a more
holistic approach for water and sediment management
that supports the long-term sustainability of the
Lowermost Mississippi River (LMR), defined for
purposes of the program as the Mississippi River
and its outlets in southern Louisiana below, and
inclusive of, the Old River Control Structure.

LMRMP effort was launched in 2018 and will conclude in fall 2023 and is supported primarily by a \$9.3 million award to CPRA from the Gulf Coast Ecosystem Restoration Council-funded Component of the Resources and Ecosystems Sustainability, Tourist Opportunities, and Revived Economies of the Gulf Coast States (RESTORE) Act. CPRA also leveraged external funding from the National Wildlife Federation. It builds upon the Louisiana Coastal Area Mississippi River Hydrodynamic and Delta Management Study previously conducted by USACE and CPRA and serves to further develop the science needed to adequately inform decision-makers on future LMR management.

LMRMP is structured to strengthen partnerships, improve/develop science and technical tools, and help advance holistic water and sediment management that yield practical benefits across all interests.

CPRA objectives for managing LMR include:

- Support the long-term sustainability of the coast and reduce land loss to the extent possible,
- Maintain and enhance channels that support use of the LMR for navigation,
- Enhance the health of ecosystems associated with the LMR,
- Mitigate threats to communities and infrastructure posed by river flooding, and

 Support holistic management of LMR water and sediment resources to maximize benefits across all missions.

LMR's response to previous and ongoing management, sea level rise, subsidence, and watershed-scale precipitation trends related to climate change will continue to test our knowledge and management capabilities. Data and decision support tools are needed to evaluate existing river conditions and approaches for future management strategies.

Specific tasks include synthesizing existing and newly collected data, conducting numerical and physical modeling, performing economic analyses, investigating existing river management, identifying and evaluating high-level "what if" river management strategies and future environmental scenarios, and coordinating with other programs and initiatives such as the Mississippi River Mid-Basin Sediment Diversion Program.

Efforts associated with LMRMP will result in greater understanding of river hydrodynamics and flow, sediment transport and dredging, and landscape condition and change, and will support progression toward holistic management of Mississippi River sediment and water resources. More information on the program and individual tasks, links to task overviews, team members, and deliverables, can be found at https://cims.coastal.la.gov/outreach/Projects/LMRMP. All deliverables associated with LMRMP will be made available through CPRA's Coastal Information Management System (CIMS), and river-focused datasets will be made available on the RESTORE-funded Mississippi River Data Portal (https://cims.coastal.la.gov/river/).

172 LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY 2023 COASTAL MASTER PLAN 2023 COASTAL

LOUISIANA WATERSHED INITIATIVE

In 2016, historic flooding throughout Louisiana exposed deficiencies in the state's approach to floodplain management at all levels of government, prompting a reassessment of how Louisiana prepares for increasing flood events. An early investigation into innovative solutions identified regional watershed-based floodplain management as a means to systemically address water management and avoid interventions that may unintentionally increase runoff or subsequent flooding on adjacent communities, whether upstream or downstream.

In 2018, Governor John Bel Edwards issued Executive Order JBE18-16 to create the Council on Watershed Management (Council) to reform the state's approach to flood risk mitigation. The Council is composed of five state agencies — the Office of Community Development (OCD), the CPRA, the Department of Transportation and Development (DOTD), the Governor's Office of Homeland Security and Emergency Preparedness (GOHSEP), and the Department of Wildlife and Fisheries (DWF). These agencies are working together to provide funding, technical support, data, and resources for flood risk reduction across the state. The Council administers the Louisiana Watershed Initiative (LWI) — a new watershed-based approach to floodplain management in Louisiana. LWI's mission is to reduce flood risk and improve floodplain management across the state, including through maximizing the natural and beneficial functions of the floodplain. The state agencies composing LWI are actively implementing this mission through a holistic approach that includes:

- Improving the way residents and governments understand, address, and respond to flood risk
- Organizing a structure for making decisions and improvements on a regional scale
- Developing the modeling, planning, and data tools needed to inform and support effective watershed-based decisions and projects

In August 2019, the Council agreed to use eight watershed regions as a starting point to coordinate efforts among parishes and distribute project funds.

Following the launch of LWI, the U.S. Department of Housing and Development (HUD) allocated approximately \$1.2 billion to Louisiana in Community Development Block Grant Mitigation (CDBG-MIT) funding for the purpose of mitigating current and future flood risk, providing an unprecedented opportunity to enhance and expedite LWI efforts. Guided by a federally approved Action Plan, LWI is utilizing these funds to support statewide planning, watershed modeling, data collection, and flood mitigation projects that reduce flood risk across the state. In administering this grant, the state and its various jurisdictions and political subdivisions are coordinating expenditures and activities throughout LWI to improve statewide floodplain management.

More information on LWI, including its various programs — many of which are ongoing and supported by the CDBG-MIT funding stream —can be found at https://watershed.la.gov/.

HYPOXIA TASK FORCE

The Mississippi River/Gulf of Mexico Watershed Nutrient Task Force, or "Hypoxia Task Force," is a partnership of 12 states along the Mississippi River, five federal agencies, and Tribes working in collaboration to reduce nutrient pollution in the Mississippi/Atchafalaya River Basins and the extent of the hypoxic zone in the Gulf of Mexico. Established in 1997 to understand the causes and effects of eutrophication in the Gulf of Mexico and to coordinate management activities throughout the Mississippi-Atchafalaya River Basin, Hypoxia Task Force activities include improvements in management of both point sources and nonpoint sources of nutrient pollution to reduce inputs into the river system. The goal of the Hypoxia Task Force is to reduce the hypoxic zone to less than 5,000 km² by 2035 with an interim target to reduce nitrogen and phosphorus loading 20% by 2025 (relative to the 1980-1996 baseline average loading to the Gulf).

Every five years, the Hypoxia Task Force updates its Gulf Hypoxia Action Plan to assess actions taken, discuss success stories, and prioritize future efforts. A critical component to the state aligning to the goals of the Gulf Hypoxia Action Plan has been development and implementation of Louisiana's Nutrient Reduction and Management Strategy.

The implementation strategy focuses on six key areas: river diversions, nonpoint source pollution management, point source pollution management, incentives, leveraging opportunities, and new science-

based technologies and applications. The Louisiana Nutrient Reduction and Management Strategy is being implemented by an interagency team with members from CPRA, the Louisiana Department of Environmental Quality, Department of Agriculture and Forestry, Department of Natural Resources, and the Governor's Office of Coastal Activities. Also, with the development of the System-Wide Assessment and Monitoring Program, water quality and nutrient sampling has been implemented coastwide to improve spatial and temporal understanding of water quality within our coastal waters. These additional monitoring sites not only provide improved baseline water quality data but will also help inform master plan models and measure proposed changes to water quality in coastal Louisiana.

RISK RATING 2.0

UPDATES TO THE NATIONAL FLOOD INSURANCE PROGRAM AND COASTAL LOUISIANA

Flooding – whether from storm-surge, high water levels in rivers and bayous, or from heavy rain events – is a risk that residents throughout Louisiana face every year. Options to address this risk include implementation of flood protection features (such as levees and flood gates) and proper floodplain management. However, even with mitigation measures in place, flooding events can still impact the lives and livelihoods of Louisianans, therefore we recognize the benefits of a strong National Flood Insurance Program (NFIP); and strongly encourage all Louisianans (especially those in coastal areas) to assess their flood risk and purchase flood insurance if their situation and financial resources allow.

The Federal Emergency Management Agency (FEMA) administers the NFIP and has, among other programmatic goals, a statutory responsibility to clearly communicate flood risk to citizens. FEMA recently modified its flood insurance rating methodology for the first time since the 1970s. The new methodology, known as Risk Rating 2.0 (RR2.0), is intended to help individuals and communities to make more informed decisions when purchasing flood insurance and to provide details on mitigation options that may reduce flood risk and lower flood insurance rates.

When setting NFIP premiums using RR2.0, FEMA now takes multiple variables into account for each individual property. These variables include the ground elevation, proximity to a flooding source, first floor elevation, foundation type, construction details, and whether the property is located in a community that is protected by levees or has otherwise implemented additional flood mitigation measures such as participating in the Community

Rating System (CRS). Prior to RR2.0, all NFIP policyholders had been subject to premium increases; the annual rate increases were capped at 18% for most policyholders and increases were applied to all properties. Under RR2.0, premiums are tailored to an individual property and annual rate increases will continue at no more than 18% per year until an individual property's "full risk-based rate" is met. With the implementation of RR2.0, 80% of Louisiana policyholders saw an increase in insurance rates.

While the goals of the NFIP are in line with the 2023 Coastal Master Plan's goal of reducing flood risk, there are concerns about the impact of the implementation of the RR2.0 methodology in Louisiana. Increases to flood insurance rates may make it harder to ensure a stable and affordable housing market which is necessary to not unduly disrupt local revenues, culture, productive fisheries, and the productive economy of Louisiana's working coast. Because the storm surge-based flood risk modeling undertaken for the master plan incorporates the latest details on Louisiana's storm surge risk reduction activities, it could be leveraged by FEMA for determining tractable, accurate, and defensible flood risk exposure values for use in NFIP policy-writing within coastal Louisiana.

Additionally, the proposed structural and nonstructural risk reduction projects, as well as wetland restoration projects, identified in the 2023 Coastal Master Plan provide a direct path forward for reducing storm surge-based flood risk for coastal residents in Louisiana. The construction of new levees, such as those included in this plan, as well as individual nonstructural mitigation activities should be taken into account



Image: Pointe-aux-Chênes, 2020. (Louisiana Sea Grant College Program)

and regularly updated in the NFIP premium-determination process. However, under RR2.0, the benefits of structural and nonstructural flood protection are no longer tightly coupled to premium rates due to a smaller impact of home elevation (relative to base flood elevation) in the overall rate-setting calculations. Incorporating additional factors such as proximity to water complicates the rate-setting and likely has the unintended consequence of reducing the insurance-related incentive for homeowners to elevate their homes.

The state, parishes, levee districts, congressional delegates, and Governor John Bel Edwards have all asked for clarity from FEMA; specifically, that details are provided on exactly how the new "full risk-based rates" were determined in our state in areas protected by levees or otherwise. The information that FEMA has provided to date has

been insufficient for Louisianans to fully understand how the rates are set and, importantly, what the impact of coastal risk reduction projects would have on premiums. While we continue to ask for clarity, parish and municipal governments should continue to implement flood mitigation policies and projects with the direct intention of increasing the communities' participation in CRS in order to reduce their residents' NFIP premiums. As of 2022, only 12% of NFIP-participating communities in Louisiana are enrolled in CRS. Communities already enrolled should continue to implement projects and policies to further reduce their residents' premium rates; those communities not enrolled should be encouraged by their constituents to explore CRS enrollment.



ACKNOWLEDGMENTS

We would like to offer our thanks to the participants and contributors of the 2023 Coastal Master Plan Coastal advisory groups, technical advisory committees, and other strategic partners who shared their expertise and perspectives on Louisiana's coastal protection and restoration challenges.

- Team member is no longer affiliated with the organization and/or participating
- † Team member is deceased

ADVISORY GROUPS

COASTAL ADVISORY TEAM (CAT)

Anne Coglianese*, City of New Orleans

Brad Inman, U.S. Army Corps of Engineers (USACE)

Brad Robin, Oyster Task Force

(NOAA - NMFS)

Brady Carter, Louisiana Department of Wildlife and Fisheries (LDWF)

Cassidy Lejeune, Ducks Unlimited

Chett Chiasson, Greater Lafourche Port Commission

Craig Gothreaux, National Oceanic and Atmospheric Administration – National Marine Fisheries Service

David Cresson, Coastal Conservation Association (CCA)

David Muth, National Wildlife Federation (NWF) / Mississippi River Delta Coalition (MRD) (retired)

Dwayne Bourgeois, North Lafourche Levee District George Ramseur*, Mississippi Department of Marine Resources

Greg Linscombe, Continental Land and Fur / Louisiana Landowners Association (LLA)

Joey Breaux, Louisiana Department of Agriculture and Forestry (LDAF)

John Ettinger, RESTORE Council

Karen Gautreaux, The Nature Conservancy (TNC)

Keith Lovell, Louisiana Department of Natural

Resources (LDNR) - Office of Coastal Management

Kimberly Davis Reyher, Coalition to Restore Coastal Louisiana (CRCL)

Laurie Cormier*, Calcasieu Parish

Lori Leblanc*, Mid-Continent Oil and Gas

Mike Carloss*, Ducks Unlimited

Michael Miller, Associated Brand Pilots

Michelle Gonzales, Jefferson Parish

Natalie Snider, MRD / Environmental Defense Fund (EDF)

Patrick Forbes, Louisiana Office of Community Development (OCD)

Patrick Landry, Louisiana Department of

Transportation and Development (DOTD)

Patrick Witty, Louisiana Economic Development (LED)

Small Business

Paul Frey*, Louisiana Landowners Association (LLA)

Quenton Fontenot, Nicholls State University

Quin Kinler, U.S. Department of Agriculture - Natural Resources Conservation Service (USDA - NRCS)

Robert Twilley, LSU Coastal Sustainability Studio

Ron Boustany, USDA - NRCS

Ronald Paille, U.S. Fish and Wildlife Service (USFWS)

Sam Bentley, LSU Coastal Studies Institute (CSI)

Scott Kirkpatrick, Coast Builders Coalition

Sharon Osowski, U.S. Environmental Protection

Agency (EPA) - Region 6

Sidney Coffee*, America's Wetland Foundation

Simone Maloz, MRD

Spencer Murphy, Canal Barge Co. Inc.

Steve Cochran*, MRD

Susan Bergeron*, Barataria-Terrebonne National Estuary (BTNEP)

Tim Matte, St. Mary Levee District

Todd Baker*, LDWF

Tokesha Collins-Wright, Louisiana Chemical Association

Tyler Gray*, Mid-Continent Oil and Gas

REGIONAL WORKGROUPS (RWs)

CHENIER PLAIN RW

Andrew (Andy) MacInnes, USACE

Charles Hebert, USACE

Chad Courville, Miami Corporation

Chad Lege, Vermilion Parish Police Jurors

Dennis Scott*, Calcasieu Parish

Doug Miller, Sweet Lake Land & Oil

George Melancon, LDWF – Fisheries

Glenn Harris, U.S. Fish and Wildlife Service (USFWS) -

Southwest Louisiana National Wildlife

Refuge Complex Manager

Greg Linscombe, Continental Land and Fur

Jenneke Visser, University of Louisiana at Lafayette (retired)

John ("Andy") Nyman, LSU Renewable Natural Resources (RNR)

Kara Bonsall, Cameron Parish Police Jury

Kevin Sagrera*, Vermilion Parish Police Jurors

Kevin Savoie, LSU AgCenter / Louisiana Sea Grant

Laurie Cormier*, Calcasieu Parish

Phillip ("Scooter") Trosclair, LDWF - Wildlife

Regan Brown, Port of Lake Charles

Rica Canik*, Cameron Parish Police Jury

Ryan Bourriaque*, Cameron Parish Police Jury

CENTRAL COAST RW

Ann Howard*, LDWF

Billy Broussard, Vermilion Corp

Cassidy Lejeune, Ducks Unlimited

Chad Lege, Vermilion Parish Police Jurors

Donald Sagrera, Teche Vermilion Freshwater District

John ("Andy") Nyman, LSU RNR

Karen Westphal*, MRD / National Audubon Society

Kevin Sagrera*, Vermilion Parish Police Jurors

Lance Campbell, LDWF - Wildlife

Mark Shirley, LSU AgCenter

Randy Moertle[†], McIlhenny Corp

Ralph Libersat[†], Chenier Plain Coastal Restoration &

Protection Authority

Robert Twilley, LSU Coastal Sustainability Studio (CSS)

Ron Boustany, USDA - NRCS

Scott Saunier, Iberia Parish

Tim Matte, St. Mary Levee District

TERREBONNE BASIN RW

Alex Kolker, Louisiana Universities Marine Consortium (LUMCON)

Amanda Voisin, Lafourche Parish

Brady Carter, LDWF - Fisheries

Chris Swarzenski, U.S. Geological Survey (USGS)

Dwayne Bourgeois, North Lafourche Levee

Earl Melancon, Louisiana Sea Grant

Greg Linscombe, Continental Land and Fur

Jennifer Gerbasi, Terrebonne Parish Consolidated Government (TPCG)

Jonathan Willis, Nicholls State University

Lance Campbell, LDWF - Wildlife

Leslie Suazo, Ducks Unlimited

Mart Black, TPCG

Matt Benoit, BTNEP

Quenton Fontenot, Nicholls State University

Reggie Dupre, Terrebonne Levee & Conservation District

Richard Demay*, BTNEP

Ronald Paille, USFWS

Simone Maloz*, Restore or Retreat (ROR)

Tim Allen, Apache Louisiana Minerals LLC

Victoria Bourque, ROR / MRD

Windell Curole, South Lafourche Levee

BARATARIA BASIN RW

Alisha Renfro, NWF / MRD

Amanda Voisin, Lafourche Parish

Blaise Gravois*, St. James Parish

Brady Carter, LDWF - Fisheries

Craig Gothreaux, NOAA – NMFS

Dwayne Bourgeois, North Lafourche Levee District

Earl Matherne, St. Charles Parish

Joni Tuck, Lafourche Port Interests

Julie Whitbeck, National Park Service

Kevin Roy, USFWS

Lance Campbell, LDWF - Wildlife

Lauren Averill*, Jefferson Parish

Michael Massimi*, BTNEP

Michael Miller, Associated Branch Pilots

Michelle Gonzales, Jefferson Parish

Ordis (Buddy) Smith*, ConocoPhillips

Robert Spears, Plaquemines Parish **Sam Bentley.** LSU CSI

Windell Curole, South Lafourche Levee District

181

PONTCHARTRAIN/BRETON BASIN RW

Ann Howard*, LDWF

Barret Fortier, USFWS

Brady Carter, LDWF - Fisheries

Carol Franze, LSU AgCenter / Louisiana Sea Grant

Danny Breaux, USFWS

Elizabeth deEtte Smythe, St. Tammany Parish

George Ramseur*, Mississippi Department of

Marine Resources

Henry DiFranco, Jr.*, St. Tammany Levee Drainage and Conservation District

Ioannis Georgiou, University of New Orleans

Jerome Landry, Orleans Parish

John Lane, St. Bernard Parish

John Lopez, Delta Science LLC (retired from Lake

Pontchartrain Basin Foundation)

Ken Krauss, USGS

Kiley Bates, Tangipahoa Parish

Lauren Averill*, Jefferson Parish

Michael Hopkins, Pontchartrain Conservancy

Michael Miller, Associated Branch Pilots

Mike Benge, Delacroix Corporation

Randy Pausina, St. Tammany Parish

Robert Spears, Plaguemines Parish

Tara Lambeth, St. John Parish

COMMUNITY ENGAGEMENT WORKGROUP (CEW)

Andreanecia Morris, Housing NOLA / Greater New Orleans Housing Alliance (GNOHA)

Angela Chalk, Healthy Community Services

Bette Billiot*, Gulf Coast Center for Law and Policy

Chief Shirell Parfait-Dardar, Grand Caillou / Dulac

Biloxi Chitimatcha Choctaw

Clair Marceaux, Alliance Transportation Group

Colette Pichon Battle, Taproot Earth (previously Gulf

Coast Center for Law and Policy)

Corey Miller*, Coalition to Restore Coastal Louisiana (CRCL)

Darilyn Demolle Turner, Zion Travelers Cooperative Center

Donald Bogen, Bayou Interfaith Shared Community Organizing (BISCO)

Phanat Xanamane, Envision Da Berry

182

Tish Taylor, Coalition Against Death Alley

TECHNICAL ADVISORY COMMITTEES

PREDICTIVE MODELS TECHNICAL **ADVISORY COMMITTEE (PM-TAC)**

Jen Irish, Virginia Tech - Chair

Courtney Harris, Virginia Institute of Marine Science,

William & Mary

Wim Kimmerer, San Francisco State University

Matthew Kirwan, Virginia Institute of Marine Science,

William & Mary

A.R. Siders, University of Delaware

Mark Stacy, University of California, Berkeley

Samuel Brody*, Texas A&M

MODELING TEAMS

ICM-HYDROLOGY

Md Nazmul Azim Beg, Tulane University

Martijn Bregman, The Water Institute of the Gulf

Kevin Hanegan, Moffatt & Nichol

Kelin Hu, Tulane University

Alex McCorquodale, The Water Institute of the Gulf

Ehab Meselhe, Tulane University

Christopher Siverd, Moffatt & Nichol

Yushi Wang, The Water Institute of the Gulf

Zhanxian Jonathan Wang, Moffatt & Nichol

Eric D. White, CPRA

Chia-Yu Wu*, Tulane University

ICM-MORPHOLOGY AND ICM-VEGETATION

Melissa M. Baustian*, The Water Institute of the Gulf

Brady Couvillion, USGS

Kristin DeMarco, LSU

Scott Duke-Sylvester[†], University of Louisiana at Lafayette

Madeline Foster-Martinez, University of New Orleans

Madeline LeBlanc Hatfield, CPRA

Elizabeth Jarrell*, CPRA

Tommy McGinnis, CPRA

Denise Reed, University of New Orleans

Donald Schoolmaster, USGS

Leigh Anne Sharp, CPRA

Gregg Snedden, USGS

Jenneke Visser, University of Louisiana at Lafayette

(retired)

Hongqing Wang, USGS

Eric D. White, CPRA

ICM-HABITAT SUITABILITY INDEX (HSI)

Brady Carter, LDWF

Laura D'Acunto, USGS Wetland and Aquatic

Research Center

Ann C. Hijuelos, USACE (formerly with USGS)

Erik Johnson, Audubon Louisiana

Megan K. La Peyre, USGS, Louisiana Fish and Wildlife

Cooperative Research Unit

Summer Langlois, CPRA David Lindquist, CPRA

Nicole Michel, Audubon Louisiana

Lindsay Nakashima, Audubon Louisiana

Ann M. O'Connell, University of New Orleans

Brett Patton, USGS Wetland & Aquatic Research Center

Katie Percy, Audubon Louisiana

Elizabeth M. Robinson, LSU AgCenter

Shaye E. Sable, Dynamic Solutions LLC

Eric D. White. CPRA

ICM-BARRIER ISLANDS

Ben Beasley, Applied Coastal

Jonathan Bridgeman*, CPRA

Zach Cobell, The Water Institute of the Gulf

Soupy Dalyander, The Water Institute of the Gulf

Ovel Díaz García, The Water Institute of the Gulf

Diana Di Leonardo, The Water Institute of the Gulf

Zhifei Dong, APTIM

Catherine Fitzpatrick*, CPRA

Madeline Foster-Martinez, University of New Orleans

Ioannis Georgiou, The Water Institute of the Gulf

Madeline LeBlanc Hatfield, CPRA

Elizabeth Jarrell*, CPRA

Darin Lee, CPRA

Michael Miner, The Water Institute of the Gulf

Eric D. White, CPRA

STORM SURGE AND RISK ASSESSMENT

Stuart Brown, CPRA

Ashley C. Cobb, CPRA

Zach Cobell, The Water Institute of the Gulf

Ovel Díaz García, The Water Institute of the Gulf

David DeSmet, RAND Corporation

Jordan Fischbach, The Water Institute of the Gulf

Angelina Freeman, CPRA

Nathan Geldner, Purdue University

Scott Hemmerling, The Water Institute of the Gulf

Krista L. Jankowski, CPRA

Elizabeth Jarrell*, CPRA

David Johnson, Purdue University

Patrick Kane, The Water Institute of the Gulf

Abby Littman. The Water Institute of the Gulf

Sam Martin, CPRA

Mikaela Meyer, Carnegie Mellon University

Hugh Roberts, The Water Institute of the Gulf

Chuck Stelzner, RAND Corporation

Jingya Wang, Purdue University Michael Wilson, RAND Corporation

Eric D. White, CPRA

HIGH TIDE FLOODING

Harris Bienn, The Water Institute of the Gulf

Ashley C. Cobb, CPRA

Zach Cobell, The Water Institute of the Gulf **Dexter Ellis.** The Water Institute of the Gulf

Jordan Fischbach. The Water Institute of the Gulf

Scott Hemmerling, The Water Institute of the Gulf

Krista L. Jankowski, CPRA

Elizabeth Jarrell*, CPRA

David Johnson, Purdue University Sam Martin, CPRA

Brett McMann, The Water Institute of the Gulf

Jessi Parfait*, The Water Institute of the Gulf

Hugh Roberts, The Water Institute of the Gulf

Rachelle Sanderson*, CPRA

Yushi Wang, The Water Institute of the Gulf

Eric D. White, CPRA

PLANNING TOOL TEAM

Stuart Brown, CPRA

Jake DeWeese, RAND Corporation

David Groves, RAND Corporation (Adjunct as of 2021)

183

Elizabeth Jarrell*, CPRA

Krista L. Jankowski, CPRA

Madeline LeBlanc Hatfield, CPRA

Sam Martin, CPRA

Christina Panis, RAND Corporation

Denise Reed, University of New Orleans Michael Wilson, RAND Corporation

Eric D. White, CPRA

DATA SUPPORT TEAM

PROJECT DEVELOPMENT DATABASE (PDD)

Dave Gong, Arcadis
Tim Nelson*, Arcadis
Derek Norman, Arcadis
Heather Sprague, Arcadis
Amanda Weikmann, Arcadis

PITTSBURGH SUPERCOMPUTING CENTER (PSC)

Juan Puerto, PSC Matt Yoder, PSC

Computational resources and software development staff time on Bridges-2 at Pittsburgh Supercomputer Center supported by: Extreme Science and Engineering Discovery Environment (XSEDE) grant: NSF grant number ACI-1548562

STRATEGIC PARTNERS

SCAPE LANDSCAPE ARCHITECTURE

Pippa Brashear, SCAPE
Caroline Brodeur, SCAPE
Liz Camuti*, SCAPE
Kate Orff, SCAPE
Ryan Pryandana*, SCAPE
Sophie Riedel, SCAPE
Dylan Roth, SCAPE
Despo Thoma, SCAPE
Nans Voron, SCAPE
Andrew Wright, SCAPE

OUTREACH AND ENGAGEMENT SUPPORT

Seth Irby*, Emergent Method **Keesler Morrison**, Emergent Method **Therese Walker**, Emergent Method

ADDITIONAL DOCUMENT SUPPORT

Alaina Grace, Royal Engineering Mandy Green, Royal Engineering Nick Gremillion, CPRA Susan Phelps Larcher, Arcadis Makida Zackery, Arcadis

TECHNICAL CONTRIBUTORS

Jacques Boudreaux, CPRA
Angelina Freeman, CPRA
Blaire Hutchison, USGS
Syed Khalil, CPRA
Jim Pahl, CPRA
Jas Singh, CPRA
Joe Wyble, CPRA

MASTER PLAN MODEL DEVELOPMENT TEAM

Stuart Brown, CPRA Ashley C. Cobb, CPRA Catherine Fitzpatrick*, CPRA Andrea Galinski*, CPRA Mandy Green*, CPRA Madeline LeBlanc Hatfield, CPRA Valencia Henderson, CPRA Krista L. Jankowski, CPRA Elizabeth Jarrell*, CPRA David Lindquist, CPRA Sam Martin, CPRA Denise Reed, University of New Orleans Zachary Rosen*, CPRA Rachelle Sanderson*. CPRA Forrest Town*, CPRA Eric D. White, CPRA

STRATEGY TEAM

Stuart Brown, CPRA
Ashley C. Cobb, CPRA
Catherine Fitzpatrick*, CPRA
Mandy Green*, CPRA
Madeline LeBlanc Hatfield, CPRA
Valencia Henderson, CPRA
Krista L. Jankowski, CPRA
Elizabeth Jarrell*, CPRA
Sam Martin, CPRA
Denise Reed, University of New Orleans
Forrest Town*, CPRA
Eric D. White, CPRA

GLOSSARY

Annual Exceedance Probability (AEP) Flood Depth:

The flood depth, at a specific location, that has a likelihood of being met or exceeded in any given year. For example, a 1% AEP flood depth is the depth that has a 1% (or 1-in-100) chance of occurring (or being exceeded) in any given year; this specific example is often referred to as a 100-year flood.

Environmental Scenarios: Sets of assumptions about key environmental drivers affecting land change and flood risk. These include several climate and non-climate drivers of change such as sea level rise, precipitation, and subsidence. To evaluate and prioritize projects, this process utilized two scenarios that represent a range of plausible future environmental conditions that were utilized to account for uncertainty in planning.

Expected Annual Damage in Dollars (EADD):

An annualized estimate of storm surge damage. Includes damage to structures, their contents, and other direct losses incurred during the recovery period after a storm event, such as lost wages, costs associated with evacuation and temporary displacement, and other considerations. Measured in \$USD.

Expected Annual Structural Damage (EASD):

An annualized estimate of structural damage that represents an aggregate risk to structures, with damage to each structure expressed as a proportion of its replacement cost. Considers equity in project selection process by eliminating the role of property values in estimating damages. Measured in structure equivalents.

Future With Action (FWA): A modeling condition in which 2023 Coastal Master Plan projects are represented on the modeled landscape and outputs are a result of the impact of their implementation.

Future Without Action (FWOA): A modeling condition in which 2023 Coastal Master Plan projects are not represented on the modeled landscape.

Outputs provide an understanding of what the future coast could look like without the investments outlined in the 2023 Coastal Master Plan.

Land Loss: The loss of land in coastal Louisiana is caused by a combination of many natural and human-caused factors, including altered hydrology, sea level rise, and land subsidence. Limiting land loss is a decision driver for master plan project selection.

Land Subsidence: Lowering of the land surface due to a combination of natural and human-induced processes such as the removal of oil and natural gas, soil compaction, etc. A major component of relative sea level rise in coastal Louisiana.

Risk: In the master plan context, risk is a term used to mean the potential for damages from storm surge-based flooding. There are additional types of risk that impact coastal communities as a result of the adverse consequences of climate-related and other hazards.


Storm Surge-Based Flooding: Flooding generated by a hurricane or tropical storm, over and above the predicted astronomical tides. Limiting damages from storm surge-based flooding is a decision driver for master plan project selection.

FIGURES & MAPS

FIGURES

| Figure 1.1: The 2023 Coastal Master Plan Development Process. | 5 |
|--|------------|
| Figure 1.2: Timeline of Master Plan Efforts Leading up to 2023 and Other Notable Events. | 8 |
| Figure 1.3: Acres Created by Dredging per Year. | 11 |
| Figure 2.1: Six-Year Cycle to Update the Master Plan. | 19 |
| Figure 2.2: Predictive Model Inputs. | 29 |
| Figure 2.3: Predictive Model Outputs. | 30 |
| Figure 3.1: Sea Level Rise Curves for Project Selection and Range of Plausible Curves. | 35 |
| Figure 3.2: Environmental Drivers for the Higher and Lower Scenarios. | 35 |
| Figure 3.3: Land Area Over 50 Years, FWA and FWOCFP, Higher and Lower Scenario. | 38 |
| Figure 3.4: Expected Annual Damage in Dollars (EADD) and Expected Annual Structural Damage (EASD), | |
| Over 50 Years, Future Without Action, Higher and Lower Scenario. | 39 |
| Figure 3.5: By the Numbers, Future Without Action. | 48 |
| Figure 4.1: Structural Risk Reduction Project Type Visualization. | 57 |
| Figure 4.2: Nonstructural Risk Reduction Project Type Visualization. | 57 |
| Figure 4.3: Ridge Restoration Project Type Visualization. | 59 |
| Figure 4.4: Marsh Creation Project Type Visualization. | 59 |
| Figure 4.5: Landbridge Project Type Visualization. | 61 |
| Figure 4.6: Diversion Project Type Visualization. | 61 |
| Figure 4.7: Hydrologic Restoration Project Type Visualization. | 63 |
| Figure 4.8: Barrier Island Maintenance Project Type Visualization. | 63 |
| Figure 4.9: Project Selection Process. | 68 |
| Figure 4.10: Project Information in the Data Viewer Desktop View. | 70 |
| Figure 4.11: Land Change Data in the Data Viewer Desktop View. | 70 |
| Figure 5.1: Planning Budget Allocation by Project Type in USD. | 75 |
| Figure 5.2: 2023 Coastal Master Plan Project List. | 77 |
| Figure 5.3: Land Area Over 50 Years, Future With and Without Action, Higher and Lower Scenario. | 86 |
| Figure 5.4: Land Area Built or Maintained Over 50 Years, Future With Action, Higher and Lower Scenario. | 86 |
| Figure 5.5: Amount of Total Annual Expected Damages in Dollars and Structure Equivalents, Future With and Without Action, Higher and Lower | Scenario87 |
| Figure 5.6: The 2023 Coastal Master Plan By the Numbers. | 92 |
| Figure 6.1: Aerial View of the Chenier Plain Region with the 2023 Coastal Master Plan Projects. | 98 |
| Figure 6.2: Percentage of days that may see HTF at key locations in the Town of Cameron, Lower Environmental Scenario. | 102 |
| Figure 6.3: Representative High Tide Flooding (HTF) Elevations for the Town of Cameron at Year 1 and 50 in the Lower Scenario | 102 |
| Figure 6.4: Chenier Plain Project List. | 106 |
| Figure 6.5: Chenier Plain Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario | 109 |
| Figure 6.6: Aerial View of the Central Coast Region with the 2023 Coastal Master Plan Projects. | 110 |
| Figure 6.7: Percentage of days that may see HTF at key locations in Delcambre, Lower Environmental Scenario | 114 |
| Figure 6.8: Representative HTF Elevations for Delcambre at Year 1 and 50 in the Lower Scenario. | 114 |
| Figure 6.9: Central Coast Project List. | 118 |
| Figure 6.10: Central Coast Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario. | 121 |
| Figure 6.11: Aerial View of the Terrebonne Region with the 2023 Coastal Master Plan Projects. | 122 |
| LOUISTANIA COACTAL PROTECTION AND RECTORATION AND RECTORATION | |

| Figure 6.12: Percentage of days that may see HTF at key locations in Dulac, Lower Environmental Scenario. | . 126 |
|---|-------|
| Figure 6.13: Representative HTF Elevations for Dulac at Year 1 and 50 in the Lower Scenario. | . 126 |
| Figure 6.14: Terrebonne Project List | . 130 |
| Figure 6.15: Terrebonne Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario | . 133 |
| Figure 6.16: Aerial View of the Barataria Region with the 2023 Coastal Master Plan Projects | . 134 |
| Figure 6.17: Hurricane Ida Storm Surge Simulations | . 138 |
| Figure 6.18: Barataria Project List | 142 |
| Figure 6.19: Barataria Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario. | . 145 |
| Figure 6.20: Aerial View of the Pontchartrain/Breton Region with the 2023 Coastal Master Plan Projects | . 146 |
| Figure 6.21: Hurricane Isaac Storm Surge Simulations. | . 150 |
| Figure 6.22: Pontchartrain/Breton Project List | . 154 |
| Figure 6.23: Pontchartrain/Breton Land Area Over 50 years, Future With and Without Action, Higher and Lower Scenario | 157 |
| Figure 7.1: Desktop View of the Master Plan Data Viewer Showing Project Information. | |
| Figure 7.2: Desktop View of the Master Plan Data Viewer Showing Coastwide Land Change Data | |
| Figure 7.3: Cascading Impacts of Coastal Change to a Selection of State Agencies. | |
| | |
| MAPS | |
| Map 1.1: Implemented Projects as of January 2023. | 11 |
| Map 3.1: Land Change, Future Without Action, Lower Scenario, Year 50. | 41 |
| Map 3.2: Land Change, Future Without Action, Higher Scenario, Year 50. | 43 |
| Map 3.3: Flood Depths,1% Annual Exceedance Probability, Future Without Action, Lower Scenario, Year 50. | 45 |
| Map 3.4: Flood Depths,1% Annual Exceedance Probability, Future Without Action, Higher Scenario, Year 50 | |
| Map 5.1: Projects selected as part of the 2023 Coastal Master Plan | |
| Map 5.2: Land Change, Future With Action, Lower Scenario, Year 50 | |
| Map 5.3: Land Change, Future With Action, Higher Scenario, Year 50 | |
| Map 5.4: Flood Depths, 1% Annual Exceedance Probability, Future With Action, Lower Scenario, Year 50 | |
| Map 5.5: Flood Depths Difference between FWA and FWOA, 1% Annual Exceedance Probability, Lower Scenario, Year 50 | |
| Map 5.6: Flood Depths, 1% Annual Exceedance Probability, Future With Action, Higher Scenario, Year 50 | |
| Map 5.7: Flood Depths Difference between FWA and FWOA, 1% Annual Exceedance Probability, Higher Scenario, Year 50 | |
| Map 6.1: The Five Regions of the Louisiana Coast | |
| Map 6.2: Existing Hydraulic Control Structures Identified throughout the Chenier Plain. | |
| Map 6.3: Chenier Plain 2023 Coastal Master Plan Projects. | |
| Map 6.4: Chenier Plain, Land Change, Future With Action, Lower Scenario, Year 50. | |
| Map 6.5: Chenier Plain, Flood Depths Difference between FWA and FWOA, 1% Annual Exceedance Probability, Lower Scenario, Year 50 | |
| Map 6.6: Hypothetical Hurricane Rita Impacts on Initial Conditions Landscape, Lower Scenario | |
| Map 6.7: Hypothetical Hurricane Rita Impacts on a Future Landscape, Future Without Action, Lower Scenario, Year 50 | |
| Map 6.8: Central Coast 2023 Coastal Master Plan Projects | |
| Map 6.9: Central Coast, Land Change, Future With Action, Lower Scenario, Year 50. | |
| Map 6.10: Central Coast, Flood Depths Difference between FWA and FWOA, 1% Annual Exceedance Probability, Lower Scenario, Year 50 | |
| Map 6.11: Terrebonne 2023 Coastal Master Plan Projects. | |
| Map 6.12: Terrebonne, Land Change, Future With Action, Lower Scenario, Year 50. | |
| Map 6.13: Terrebonne, Flood Depths Difference between FWA and FWOA, 1% Annual Exceedance Probability, Lower Scenario, Year 50 | |
| Map 6.14: Mid-Barataria, Land Change between FWOA and FWOCFP, Year 50, Lower Scenario. | |
| Map 6.15: Barataria 2023 Coastal Master Plan Projects | |
| Map 6.16: Barataria, Land Change, Future With Action, Lower Scenario, Year 50. | |
| Map 6.17: Barataria, Flood Depths Difference between FWA and FWOA, 1% Annual Exceedance Probability, Lower Scenario, Year 50 | |
| Map 6.18: Pontchartrain/Breton 2023 Coastal Master Plan Projects | |
| Map 6.19: Pontchartrain/Breton, Land Change, Future With Action, Lower Scenario, Year 50 | |
| Man 6.20: Pontchartrain / Breton, Flood Donths Difference between FWA and FWAA 1% Appual Exceedance Probability Lower Scenario, Veer 50 | |





COASTAL PROTECTION AND RESTORATION AUTHORITY OF LOUISIANA coastal.la.gov

