


### **Project Area**


- Lafourche Parish
- Approximately 30 miles south of New Orleans
- Land majority owned by Delta Farms and Clovelly Farms






### Original Project Concept — BA-0260

- Goal reestablish the boundary between Delta Farms marsh and Little Lake
- Marsh Creation 669 acres of marsh creation along the northwest rim of Little Lake
- Shoreline Protection reinforce the Little Lake shoreline adjacent to the marsh creation
- Borrow Little Lake






#### 2023 Coastal Master Plan


- USGS land change analysis in 2022 estimated land change rate of 0.09% per year
- Hurricane Ida reduced the BA-260 Project Area from 84% marsh to 25%
- The 2023 Master Plan highlighted this region for a \$520M project including 3,800 acres of marsh and 63,000 feet of shoreline protection






### Reconnaissance Effort






### Data Collection - Geotech



Donath	Borrow Area Classification										
Depth	101	103	105	107	109	111	113	115	117	119	121
0	СН	CH	CH	CH	СН	СН	СН	CH	СН	СН	СН
2	CL	CH	CH	CH	CH	СН	CH	CH	CH	СН	СН
4	CL	CL	CL	CH	CH	СН	CH	CH	CH	СН	СН
6	CL	CH	CL	CH	CH	СН	CL	CH	CL	СН	СН
8	CL	CH	CL	CH	CL	СН	CL	CH	CH	CL	СН
10	CL	CH	CL	SC	CL	СН	CL	SC	CH	СН	CL
12	CL	CL	CH	CL	СН	SC	SC-SM	CL	СН	СН	CL
14	CL	SC	СН	CL	СН	SC	SC-SM	CL	CL	СН	CL
15								CH			
16	CL	SC	SM	CL	CL	CL	SC-SM	CL	SC	СН	CL
17								СН			
18	CL	SM	SM	SM	СН	CL	SC-SM	СН	CL	СН	-
19						SM	SM		SM		CL
20	CL	SM	SM	SM	SC	SC	SC-SM	СН	CL	СН	CL
21					CH	30			SM		
22	SC	SM	SM	ML	СН	SM	CL	SM	CL	СН	CL
23							SM				
24	СН	SP-SM	SM	ML	СН	SC	CL	СН	СН	СН	CL
25							SM	СП	СП	СП	CL


PT	Peat		
ОН	Organic Clay		
СН	Fat Clay		
CL	Lean Clay		
ML	Sandy Silt		
SC	Clayey Sand		
SM	Silty Sand		

23 10	N
	1 mi



### Unique Challenges — Historic Significance







### Current Progress for Northwest Little Lake

#### **BA-260**:

- Permit submitted
- Design package in development

### **BA-260 Terrace Field:**

**Data collection complete** 

#### **BA-268:**

30% design complete

#### **BA-276:**

Finalizing data collection scopes




# Proposed Project Features & Quantities

- Little Lake Borrow Area:
  - 799 acres
  - 18 MCY of borrow
- One MCA totaling approximately:
  - 650 acres
  - 5 MCY of fill
- ~27,800 LF of Earthen Containment Dike
- ~3,400 LF of Marine Mattress Shoreline Protection
- ~ 700 LF of Sheet Pile Gap Closure


#### **Additional Notes:**

- Avoidance Areas
- Pipelines



# Borrow Area Layout and Typical Section

- Little Lake Mixed Sediment: primarily fat clays in upper 15 ft with mixed organics and sand
- No-excavation zone around pipeline
- -20 ft cut (maximum)
- ~18 MCY available
  - ~5,000,000 CY fill requirement
  - Sharing borrow material with BA-268
- Maximum pump distance 3 miles




POTENTIAL ACCESS DREDGING

EQUIPMENT ACCESS ROUTE


# Dredge Pipeline Corridor/Equipment Access

- Equipment Access to Borrow Area:
  Barataria Waterway to Little Lake
  - No access dredging Several pipelines along both routes
- Dredge Pipeline/Equipment Access for Marine Mattress Installation
  - ~ 9,260 LF of access dredging
  - Avoidance areas




# Typical Sections – ECD and Marsh Fill

- ~27,800 LF of ECD
- ECD Crown Elevation: +3.5ft (NAVD88)
- ECD Crown Width: 10 ft along Little Lake shoreline; 5 ft elsewhere
- ECD Side Slopes: 4H:1V
- Training dike to separate the MCA in two parts
- MCA Fill Elevation: +2.5ft (NAVD88)
- Average Mudline Elevation (Approx.): -1.8 ft (NAVD88)



# Typical Section – Marine Mattress

- ECD Reinforcement Marine Mattress ~3,400 LF
  - 8-inch thickness, 40 ft long, with 5 ft placed across the crown
  - Follows ECD 4H:1V slope into the water
  - Geotextile fabric placed prior to the mattress



# **Project Quantities**

Item No.	Work or Material	Quantity	Unit
1	Mobilization or Demobilization (TS-100)	1	LUMP SUM
2	Surveys (TS-200)	1	LUMP SUM
3	Grade Stakes (TS-220)	65	EACH
4	Settlement Plates (TS-250)	13	EACH
5	Earthen Containment Dikes (TS-300)	27,800	LINEAR FOOT
6	Sheet Pile Gap Closure (TS-310)	700	LINEAR FOOT
7	Pile Wall Sand (TS-311)	2,546	CUBIC YARD
8	Access and Flotation Channels (TS-320)	1	LUMP SUM
9	Hydraulic Dredging and Marsh Fill (TS-400)	5,000,000	CUBIC YARD
10	Non-Woven Geotextile Fabric (TS-600)	21,408	SQUARE YARD
11	Geogrid Marine Mattress (TS-650)	15,556	SQUARE YARD

# Project Schedule

- Final Design/Bid Package Development: In progress
- Construction Permit: Submitted and Under Review
- Landrights/Servitude Agreements: In progress
- Anticipated Bid Advertisement: Spring/Summer 2026
- Construction Duration: Approximately 863 days

- Hurricane Ida devastated a previously stable marsh habitat in the Little Lake vicinity
- Without action, erosion will continue and the levee system protecting communities like LaRose and Cut Off could be compromised
- Support from the Master Plan led to the planning of other collaborative efforts with multiple program and agency cooperation

# Parting Thoughts



